




ADDITIONAL NOTES

15. THE CHAMBER SIZE OF MANHOLES WITH MORE THAN ONE CONNECTION IN THEM MAY NEED TO BE INCREASED AN INCREMENT TO ACCOMMODATE THE CONNECTIONS AND BENDS.
16. THE MINIMUM CRUSHING STRENGTH FOR CLAY PIPES SHOULD BE AS FOLLOWS: 100MM DIA. 40KN/M, 150MM DIA. 40KN/M, 225MM DIA. 45KN/M AND 300MM DIA. 72KN/M. THE MINIMUM CRUSHING STRENGTH FOR CONCRETE PIPES SHOULD BE: (CLASS 120 TO EN 1916/BS5911-2 2002). PIPES SHOULD CONFORM TO WIS 4-35-01 AND BS13476.
17. ALL EXISTING CONNECTION WILL BE REINSTATED TO THE DIVERTED SEWER.
18. THE EXISTING SEWER WHERE PURPOSE TO DIVERT WILL BE GRUBBED OUT/REMOVED.



EX MHS8 DETAIL



This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the scaled dimensions.

AECOM

PROJECT

MANCHESTER
COLLEGE
PHASE 2

CLIENT

THE MANCHESTER
COLLEGE

CONSULTANT

AECOM
100 Embankment
Cathedral Approach
Manchester
M3 7FB
T: +44-161-601-1700
www.aecom.com

NOTES

1. DO NOT SCALE FROM THIS DRAWING.
2. ALL DIMENSIONS, CO-ORDINATES AND LEVELS ARE GIVEN IN METRES UNLESS SHOWN OTHERWISE.
3. THE CONTRACTOR IS TO VERIFY EXACT DETAILS OF EXISTING SERVICES, ALL GROUND LEVELS AND BUILDING / SITE DIMENSIONS ALONG PROPOSED PIPE ROUTES PRIOR TO CONSTRUCTION
4. COLOURED PLASTIC MARKER TAPE AT LEAST 150mm WIDE IS TO BE Laid TO A MINIMUM OF 200mm ABOVE THE SOFFIT OF THE PIPE. THE TAPE SHALL BE PRINTED WITH A DESCRIPTION OF THE SERVICE IN BOLD CAPITAL LETTERS THROUGHOUT ITS LENGTH IN INTERVALS NOT EXCEEDING 700mm AND SHALL INCORPORATE A CORROSION RESISTANT TRACING SYSTEM FOR NON-METALLIC PIPES
5. THE CONTRACTOR IS TO CONSTRUCT THE WORKS IN ACCORDANCE WITH CESWI 7TH EDITION, THE CODE OF PRACTICE FOR THE SELF-LAYING WATER MAINS AND SWW'S TECHNICAL STANDARDS FOR THE WATER INSTALLATIONS AND DRAINAGE TO BE CONSTRUCTED IN ACCORDANCE WITH SEWERS FOR ADOPTION 7th EDITION AND THE CIVIL ENGINEERING SPECIFICATION FOR THE WATER INDUSTRY 7th EDITION
6. ALL PIPES TO BE LAY (HEPWORTH SUPERSELEVE) OR SIMILAR TO ALLOW MAXIMUM POSSIBLE JOINT DEFLECTION IN ANTICIPATED POOR GROUND CONDITIONS.
7. ALL ADAPTABLE SEWER WORKS AND MATERIAL TO BE IN ACCORDANCE WITH "CODE FOR ADOPTION". THE RELEVANT BRITISH STANDARDS REQUIREMENTS/ADDENDUM TO THE MECHANICAL AND ELECTRICAL SPECIFICATION AND KITEMARKED.
8. MANHOLE COVERS SHALL BE OF A CLEAR OPENING OF 600mm AND SHALL BE CLASS D400 TO BS EN 124 WITH 150mm DEEP FRAMES IN HIGHWAYS.
9. FILL UNDER MUST BE FILLED AND CONSOLIDATED UNDER THE SUPERVISION AND TO THE SATISFACTION OF THIRD PARTY OWNER BEFORE ANY SEWER WORKS ARE CARRIED OUT
10. SULPHATE RESISTANT CEMENT (**C20-D2**) AND PRECAST CONCRETE PRODUCTS MUST BE USED OR A LABORATORY REPORT PROVIDED PROVING THAT SUCH PRECAUTIONS ARE NOT NECESSARY.
11. THE ADAPTABLE SEWERS MUST BE A MINIMUM OF 1m AND MANHOLES 0.5m FROM KERB FACES AND SERVICE MARGINS. SEWERS MUST HAVE 5 METRES CLEARANCE FROM TREES AND HEDGES.
12. SEWERS TO BE LAID IN CLASS "S" BEDDING (150mm GRANULAR BED AND SURROUND). WHERE DEPTH OF COVER TOP OF SEWER IS LESS THAN 1.2m IN HIGHWAYS AND VERGES (OR LESS THAN 900mm IN NONE VEHICULAR ACCESS AREAS) THEN A CONCRETE SLAB SHOULD BE PROVIDED ABOVE GRANULAR BED AND SURROUND.
13. BEDDING AND BACKFILL MATERIAL TO CONFORM TO THE REQUIREMENT OF WATER INDUSTRY SPECIFICATION 4-08-02 (TABLE A2).

ISSUE/REVISION

C02	17/10/2024	PLANNING AUTHORITY	NM	GT	DH
C01	05/02/2024	FOR CONSTRUCTION	NM	GT	VB
I/R	DATE	DESCRIPTION	BY	CK	AP

SUITABILITY

S2 - Suitable for information

PROJECT NUMBER

60594458

SHEET TITLE

MANCHESTER COLLEGE
PHASE 2
MANHOLE DETAILS
PLANNING AUTHORITY

SHEET NUMBER

CCPH2-ACM-Z0-XX-DR-C-6002

SCALE

1:10 @ A1

REVISION

C02