

NB- DEMOLITION TO BE OF NON ORIGINAL MATERIAL
UNLESS SPECIFICALLY NOTED OTHERWISE

SHOULD SUSPECTED ORIGINAL MATERIAL BE IDENTIFIED WORKS TO PAUSE AND THE ARCHITECT AND PROJECT MANAGER TO BE NOTIFIED

REMOVAL OF ALL LOOSE FURNITURE

2. FLOORS
REMOVE AND DISPOSE OF ALL:
- CARPET TILES
- BELOW FLOOR VENTILATION
- SKIRTINGS
- HANDRAILS AND STEPS

3. MAIN FLOOR LOBBY STAIRCASES ALTER STAIRCASE AND HANDRAIL TO ACCOMMODATE NEW FLOOR LEVEL

9. COLUMN ENCASEMENT
ASSUMMED NON ORIGINAL
-TEST AREA TO CONFIRM BEFORE PROCEEDING

HEAD DETAIL TO MATCH OTHER EXPOSED COLUMNS
ON THE FLOOR AND ELSEWHERE IN THE BUILDING

DOORS AND PANELLING TO BE REMOVED AND
STORED FOR REUSE

PROJECT
**ROYAL LONDON HOUSE,
DEANSGATE, MANCHESTER**

TITLE
PROPOSED 5TH FLOOR
DEMOLITION PLAN

JOB No 1573	DWG No AL(05)5070	REV
----------------	----------------------	-----

Jeffrey Bell Architects
3 Cobourg Street
Manchester
M1 3GY

t +44 [0]161 228 0651
e studio@jeffreymbellarchitects.co.uk