

DO NOT SCALE FROM THIS DRAWING

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER HBL DRAWINGS ISSUED FOR THIS PROJECT

Node ID	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Width (mm)	Node Type	MH Type	Connections	Link ID	IL (m)	Dia (mm)	Link Type
SW1	384630.255	390770.846	35.600	0.708	450			Inspection Chamber		0	1.000	34.892	100 Circular
SW2	384639.943	390781.689	35.600	0.853	450			Inspection Chamber		1	1.000	34.747	100 Circular
SW3	384638.889	390771.548	36.000	1.300				RWP		0	1.001	34.747	100 Circular
SW4	384644.395	390777.711	35.700	1.062			Junction			0	2.000	34.700	100 Circular
SW5	384643.016	390767.861	36.000	1.300				RWP		1	1.001	34.659	100 Circular
SW6	384648.522	390774.024	35.800	1.324			Junction			2	2.900	34.638	100 Circular
SW7	384647.142	390764.174	36.000	1.300				RWP		0	1.002	34.659	100 Circular
SW8	384652.648	390770.337	35.900	1.586			Junction			0	3.000	34.700	100 Circular
SW9	384647.756	390755.211	36.000	1.300				RWP		1	1.002	34.497	100 Circular
SW10	384657.816	390765.721	36.000	1.861	450			Inspection Chamber		2	3.000	34.476	100 Circular
SW11	384661.269	390769.014	36.000	2.009	1050			Precast Concrete		0	1.003	34.497	100 Circular
SW12	384650.490	390792.266	34.340	0.495				RWP		1	1.003	34.335	100 Circular
SW13	384642.838	390782.767	35.600	1.877	450			Inspection Chamber		2	4.000	34.314	100 Circular
SW14	384655.798	390769.715	35.900	2.361	450			Inspection Chamber		0	1.004	34.335	100 Circular
SW15	384662.064	390771.144	36.000	2.525	450			Inspection Chamber		1	1.005	34.139	100 Circular
SW16	384659.118	390782.743	34.340	0.495				RWP		0	1.005	33.991	100 Circular
SW17	384666.306	390775.207	35.950	2.534	450			Inspection Chamber		1	1.006	33.991	100 Circular
SW18	384662.108	390787.932	34.340	0.495				RWP		0	6.000	33.845	100 Circular
SW19	384671.157	390778.446	35.950	2.638	1050			Precast Concrete		1	6.000	33.723	100 Circular
SW20	384683.917	390790.616	36.000	2.806	1050			Precast Concrete		0	6.001	33.723	100 Circular
SW21	384678.425	390796.375	36.000	2.859			Junction			1	6.001	33.539	100 Circular
SW22	384653.065	390789.611	34.340	0.495				RWP		0	6.002	33.539	100 Circular
SW23	384653.984	390795.244	34.340	0.495				RWP		1	6.002	33.475	100 Circular
SW24	384658.850	390795.129	34.340	0.595				RWP		0	6.003	33.475	100 Circular
SW25	384661.746	390797.892	34.190	0.749	450			Inspection Chamber		0	7.000	33.845	100 Circular
SW26	384663.064	390796.510	34.190	0.772	450			Inspection Chamber		2	6.003	33.416	100 Circular
SW27	384667.492	390795.578	37.000	3.746	450			Inspection Chamber		2	7.000	33.420	100 Circular
SW28	384674.421	390806.187	35.700	3.067	1200			Precast Concrete		0	6.004	33.416	100 Circular
SW29	384675.876	390807.575	35.700	3.080	1200			Precast Concrete		1	6.004	33.416	100 Circular
CW1								Precast Concrete		0	8.000	33.845	100 Circular
								Precast Concrete		1	1.006	33.362	100 Circular
								Precast Concrete		2	6.004	33.362	100 Circular
								Precast Concrete		3	8.000	33.362	100 Circular
								Precast Concrete		0	1.007	33.312	150 Circular
								Precast Concrete		1	1.007	33.194	150 Circular
								Precast Concrete		0	1.008	33.194	150 Circular
								Precast Concrete		1	1.008	33.141	150 Circular
								Precast Concrete		0	1.009	33.141	150 Circular
								Precast Concrete		1	9.000	33.845	100 Circular
								Precast Concrete		0	10.000	33.845	100 Circular
								Precast Concrete		1	9.000	33.745	100 Circular
								Precast Concrete		2	10.000	33.745	100 Circular
								Precast Concrete		0	9.001	33.745	100 Circular
								Precast Concrete		1	9.001	33.441	100 Circular
								Precast Concrete		0	9.002	33.441	100 Circular
								Precast Concrete		1	9.002	33.417	100 Circular
								Precast Concrete		0	9.003	33.417	100 Circular
								Precast Concrete		1	9.003	33.304	100 Circular
								Precast Concrete		0	9.004	33.254	150 Circular
								Precast Concrete		1	1.009	32.633	150 Circular
								Precast Concrete		2	9.004	32.633	150 Circular
								Precast Concrete		0	1.010	32.633	150 Circular
								Precast Concrete		1	1.010	32.620	150 Circular

C02	DEC'20	AP	MINOR AMENDMENTS TO RWP LOCATIONS	AP	ALS
C01	JUL'20	HM	ISSUED FOR CONSTRUCTION	ALS	ALS
T1	NOV'19	AP	SCHEDULE UPDATED	AP	ALS
T0	SEP'19	HM	ISSUED FOR TENDER	ALS	ALS
REV.	DATE	DRAWN	DESCRIPTION	CHKD	APPRD
STATUS DESCRIPTION				STATUS	
APPROVED				A1	



Brook House
Weybrook Road,
Manchester M19 2QD
+44 (0)161 432 9977 | www.hbl.ltd
Consulting Civil & Structural Engineers

PROJECT			
PROPOSED RESIDENTIAL DEVELOPMENT THE LIMES, DIDSBURY			
DRAWING TITLE			
PROPOSED SURFACE WATER MANHOLE SCHEDULE			
CLIENT			
PROPERTY ALLIANCE GROUP			
HBL REF.	DATE	SCALE(S)	
6633	JULY 2019	1:250	A1
DRAWN	CHECKED	APPROVED	
LB	AP	AP	
DRAWING No.			REV.
6633-HBL-XX-XX-DR-D-0302			C02