



01 Plan
Ground floor






02 Plan
Level 1

Note:

Whether in hardcopy or digital format, this drawing should not be used as a basis for measurement or setting-out unless specific dimensions have been provided. SimpsonHaugh and Partners will not be responsible for the accuracy of any dimension that is scaled or measured from this information.

North:



DEMOLITION KEY

Areas to be demolished

Refurbishment

The renovation and refurbishment will encompass but not be limited to:

- Façade cleaning where required to be undertaken using suitable conservation cleaning
- Repointing to be completed using traditional lime mortar
- Brick replacement to be carried out using traditional soft red bricks bedded in lime mortar
- Window repairs / replacement to be designed with sensitivity to the existing historic form of the window layout
- Slate replacement to be carried out on a like for like basis using good quality UK sourced slate laid to match existing
- Brickwork to be made good on a like for like basis to match retained sections following demolition
- Replacement, removal, reinforcement and amendment of internal and external fabric and structure where required to enable the new layouts to be designed with sensitivity to the existing historic form.

| Rev | Date | Description |
|---|---|---|
| P2 | Aug 2024 | Planning Issue Update |
| P1 | 03.04.2019 | Planning Issue |

LOGIK DEVELOPMENTS

Sir Robert McALPINE Capital Ventures

Project Title
ARUNDEL STREET
MANCHESTER
M15 4JZ

Drawing Title
Proposed Demolition Floor Plans
Building 3 - Ground Floor, Level 1
General Arrangement
April 2019 Planning Application

Status
Planning

| Job No | Scale | Date |
|---|---|---|
| 10090 | A1 - 1:100 | 03/04/2019 |

| Drawing No | Revision |
|---|---|
| 10090-1903-A-JC20-P-150 | P2 |

simpsonhaugh

MANCHESTER
Riverside, 4 Commercial St
Manchester M15 4RQ
+44 (0)161 835 2345

www.simpsonhaugh.com

LONDON
5-6 Roberts Place
London EC1R 0BB
+44 (0)20 7549 4000

mail@simpsonhaugh.com

© SimpsonHaugh and Partners 2024