










Node ID	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Width (mm)	Node Type	MH Type	Connections	Link ID	IL (m)	Dia (mm)	Link Type
14	384639.035	390779.281	35.600	1.600	450		Manhole	Inspection Chamber		0	8.000	34.000	100 Circular
11	384655.716	390778.773	34.340	0.495				SVP		0	7.000	33.845	100 Circular
18	384659.378	390782.992	34.340	0.495				SVP		0	10.000	33.845	100 Circular
17	384659.529	390787.986	34.340	0.495				SVP		0	9.000	33.845	100 Circular
19	384661.658	390785.167	34.340	0.587			Junction			1 2	13.000 33.756 2 9.000	33.756 33.753	100 Circular
20	384661.139	390781.458	34.340	0.495				SVP		0	9.001	33.753	100 Circular
21	384663.263	390783.494	34.340	0.645			Junction			1 2	9.001 11.000 2 11.000	33.695 33.698	100 Circular
23	384662.543	390788.339	34.340	0.495				SVP		0	9.002	33.695	100 Circular
24	384662.886	390791.188	34.340	0.495				SVP		0	12.000	33.845	100 Circular
25	384664.146	390789.868	34.340	0.550			Junction			1 2	13.000 12.000 2 12.000	33.790 33.790	100 Circular
26	384667.451	390791.329	34.340	0.495				SVP		0	12.001	33.790	100 Circular
27	384664.991	390788.982	34.340	0.590			Junction			1 2	14.000 12.001 2 12.001	33.750 33.753	100 Circular
CW1	384675.878	390807.575	35.700	3.080	900		Manhole	Precast Concrete		1	1.008	32.620	100 Circular
30	384686.234	390795.528	36.000	3.274	450		Manhole	Inspection Chamber		0	1.007	32.726	150 Circular
22	384668.161	390778.349	35.950	2.905	450		Manhole	Inspection Chamber		1 2	1.008 1.005 2 9.002	32.726 33.045 33.095	150 Circular
16	384658.406	390768.924	36.500	3.365	450		Manhole	Inspection Chamber		1 2	1.006 1.004 2 1.004	33.045 33.185 33.185	150 Circular
15	384654.859	390765.082	35.950	2.487	450		Manhole	Inspection Chamber		1 2	1.005 1.000 2 8.000	33.135 33.468	100 Circular
13	384651.098	390775.532	35.600	2.292	450		Manhole	Inspection Chamber		1 2	1.003 1.001 2 1.003	33.308 33.463	100 Circular
12	384654.971	390779.229	34.340	0.626	450		Junction			1 2	1.004 7.000 2 6.000	33.308 33.714 33.714	100 Circular
28	384671.810	390781.832	36.000	3.044	450		Manhole	Inspection Chamber		1 2	1.001 1.006 2 1.007	33.431 32.956 32.956	150 Circular
5	384644.295	390782.662	35.600	2.169	450		Manhole	Inspection Chamber		1 2	1.001 1.002 2 1.002	33.431 33.431 33.398	100 Circular
4	384653.237	390790.941	34.340	0.604			Junction			1 2	1.000 2.000 3.000	33.745 33.736 33.736	100 Circular
10	384655.706	390784.198	34.340	0.495				SVP		0	1.001	33.736	100 Circular
1	384653.657	390794.933	34.340	0.495				SVP		0	6.000	33.845	100 Circular
3	384654.600	390792.964	34.340	0.495				SVP		0	1.000	33.845	100 Circular
9	384646.123	390780.745	35.600	2.202			Junction			1 2	4.001 1.002 1.003	33.988 33.398 33.398	100 Circular
8	384653.010	390787.314	34.340	0.552			Junction			1 2	4.000 2.000 5.000	33.794 33.786	100 Circular
7	384654.186	390788.435	34.340	0.495				SVP		0	4.001	33.788	100 Circular
2	384651.776	390793.172	34.340	0.495				SVP		0	5.000	33.845	100 Circular
6	384652.800	390789.359	34.340	0.495				SVP		0	2.000	33.845	100 Circular

DO NOT SCALE FROM THIS DRAWING					
THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER HBL DRAWINGS ISSUED FOR THIS PROJECT					
C03	DEC20	AP	UPDATED IN LINE WITH H DRAINAGE LAYOUT	AP	ALS
C02	DEC20	AP	MINOR AMENDMENTS TO SVP LOCATIONS	AP	ALS
C01	JUL20	HM	ISSUED FOR CONSTRUCTION	ALS	ALS
T1	NOV19	AP	SCHEDULE UPDATED	AP	ALS
T0	SEP19	HM	ISSUED FOR TENDER	ALS	ALS
REV.	DATE	DRAWN	DESCRIPTION	CHKD	APPROD
STATUS DESCRIPTION					STATUS
APPROVED					A1
					
PROJECT			Brook House Weybrook Road, Manchester M19 2QD +44 (0)161 432 9977 www.hbl.itd Consulting Civil & Structural Engineers		
PROPOSED RESIDENTIAL DEVELOPMENT THE LIMES, DIDSBURY					
DRAWING TITLE					
PROPOSED FOULWATER MANHOLE SCHEDULE					
CLIENT					
PROPERTY ALLIANCE GROUP					
HBL REF. 6633		DATE JULY 2019		SCALE(S) 1:250	A1
DRAWN LB		CHECKED AP		APPROVED AP	
DRAWING No. 6633-HBL-XX-XX-DR-D-0303					REV. C03