ISO A1 594mm x 841mm
Last saved by: CONROY.THOMAS (2024-05-29) Last Plotted: 2024-05-29
File name: \\emea.aecomnet.com\LF\SIEMEA\Manchester-UKMCR5\DCS\Projects\BP\01_MAG_FRAMEWORK_CIVILS_23241900_CAD_GIS\60578226 - CBB\910_CAD\911_CivilsCAD (Drawings)\912_1_WIP\60719865-ACM-CBB-XX-DR-CE-000510 - PROPOSED DRAINAGE



THIRD PARTY INFORMATION	ISSUED BY	REFERENCE	DATE RECEIVED
TOPOGRAPHICAL SURVERY	ATLANTIC GEOMATICS	3543P06-P11	JUNE 2018
OS MASTERPLAN	MAG	ASSET TEAM	18/02/2024

THIRD PARTY INFORMATION	ISSUED BY	REFERENCE	DATE RECEIVED

0 25 50 m
1:1000

NOTES CONTINUED

10. OUTFALL PIPES INTO THE PROPOSED SWALE WILL OUTFALL DIRECTLY ONTO A CONCRETE SLAB 0.5m BY 0.5m WITH A DEPTH OF 0.15m.
11. OUTFALL PIPES SURROUND WILL BE BEDDING TYPE Z FOR ALL COVER DEPTHS 0.6m AND LOWER UNTIL THE POINT WHERE THE PIPE INTERSECTS WITH THE SWALE SIDE SLOPE.

KEY

- EXISTING WATERCOURSE
- PROPOSED SWALE
- PROPOSED MODULAR ATTENUATION TANK
- PROPOSED CARRIER DRAIN
- PROPOSED FILTER DRAIN
- INT PROPOSED INTERCEPTOR
- PROPOSED KERB DRAIN
- RE PROPOSED RODDING EYE
- PROPOSED OUTFALL TO SWALE
- PROPOSED CASCADE LOCATION
- PROPOSED CHAMBER

AECOM

PROJECT

CLOUGH BANK B

CLIENT

MAG

CONSULTANT

AECOM
100 Embankment
Cathedral Approach
M1 7FB
T:+44-161-601-1700
www.aecom.com

NOTES

1. ALL DIMENSIONS ARE IN METERS AND ALL LEVELS IN METERS ABOVE ORDNANCE DATUM UNLESS NOTED OTHERWISE.
2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER SCHEME DRAWINGS AND DOCUMENTS.
3. THIS DRAWING IS TO BE ISSUED ONLY BY THOSE TO WHOM IT HAS BEEN FORMALLY ISSUED BY AECOM OR THE CLIENT (MAG).
4. ONLY WRITTEN DIMENSIONS SHALL BE USED. CRITICAL DIMENSIONS AND LEVELS SHALL BE VERIFIED ON SITE BY THE CONTRACTOR PRIOR TO WORK COMMENCEMENT.
5. ANY DISCREPANCIES IN DIMENSIONS OR DETAILS ON OR BETWEEN THESE DRAWINGS SHALL BE DRAWN TO THE ATTENTION OF THE PROJECT MANAGER FOR CLARIFICATION.
6. ATTENUATION TANK SYSTEMS SHALL BE DESIGNED BY THE SUPPLIER AND DETAILS SUBMITTED TO THE DESIGNER TO REVIEW. ATTENUATION TANKS SHALL INCLUDE A POLYSTORM ACCESS TURRET FOR CLEANSING AND INSPECTION. FOR ASSEMBLY DETAILS REFER TO POLYPIPE DRAWING NO. PSM_SD_007.
7. ALL INTERCEPTORS SHALL BE KLARGESTER OIL FUEL SEPARATORS, UNIT NSBE010, OR SIMILAR APPROVED INTERCEPTOR.
8. WHERE PERFORATED PIPES ARE SHOWN CROSSING CRATES, THESE ARE TO BE INSTALLED ABOVE ATTENUATION SYSTEMS
9. THE CHAMBER DIRECTLY UPSTREAM OF THE ATTENUATION TANK WILL BE SILT TRAP, FOR DETAIL REFER TO 60719865-ACM-CBB-XX-DR-CE-000520.

ISSUE/REVISION

I/R	DATE	DESCRIPTION	BY	CK	AP
P05	28/05/2024	UPDATED AS PER MAG REQUIREMENTS ON 22.05.24	CT	GT	VB
P04	17/05/2024	NOTES UPDATED AS PER CLIENT COMMENT	NM	GT	VB
P03	03/05/2024	LANDSCAPE UPDATE	CT	GT	VB
P02	25/04/2024	UPDATED DRAINAGE LAYOUT	CT	RG	VB
P01	22/03/2024	TENDER ISSUE	NM	RG	VB

SUITABILITY

D2 - Suitable for Tender

PROJECT NUMBER

60719865

SHEET TITLE

CLOUGH BANK B
PROPOSED SURFACE
WATER DRAINAGE

SHEET NUMBER

60719865-ACM-CBB-XX-DR-CE-000510

SCALE 1:1000 @ A1

REVISION P04

This drawing has been prepared for the use of AECOM's client. It may not be used, modified, reproduced or relied upon by third parties, except as agreed by AECOM or as required by law. AECOM accepts no responsibility, and denies any liability whatsoever, to any party that uses or relies on this drawing without AECOM's express written consent. Do not scale this document. All measurements must be obtained from the stated dimensions.