SPACE

External Materials Schedule

Spaceworks
Benton Park Road
South Gosforth
Newcastle upon Tyne
NE7 7LX

+44 (0) 844 800 6660
www.spacearchitects.co.uk

Date: May 2024 – Revision P01

Project: Lidl – Mauldeth Road West, Chorlton

External Walls

1. Facing Brickwork to be Forterra Southdown Multi with natural mortar.
2. Panels of feature brickwork to be laid in English Bond arrangement with 20mm projection to alternating bricks on each header course.
3. Acoustic enclosure to be natural Siberian Larch planed tongue & groove cladding.

Main Roof

1. Roof Covering to be aluminium standing seam with 25mm high seams at nominal 450mm centres with zinc grey finish.
2. Timber soffit to be natural Siberian Larch planed tongue & groove cladding.

External Openings

1. Aluminium curtain wall frames to be polyester powder coated RAL 7024 30% gloss.
2. Glazing units to be toughened float glass with minimum light transmittance value of 0.75.
3. External doors to be coated steel polyester powder coated in RAL 7024 30% gloss.
4. Aluminium/steel sectional delivery door to have smooth surface finish in RAL 7024 30% gloss.

Rainwater Goods

1. Aluminium gutters, colour to match roof covering.
2. Aluminium downpipes, colour to match roof covering.