

DO NOT SCALE FROM THIS DRAWING

THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER HBL DRAWINGS ISSUED FOR THIS PROJECT

Node ID	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Width (mm)	Node Type	MH Type	Connections	Link ID	IL (m)	Dia (mm)	Link Type
1	384630.129	390770.705	36.000	1.000				RWP		0	1.000	35.000	100 Circular
2	384639.943	390781.689	35.600	0.745	450		Manhole	Inspection Chamber		1	1.000	34.855	100 Circular
3	384638.889	390771.548	36.000	1.300				RWP		0	1.001	34.855	100 Circular
4	384644.395	390777.711	35.700	1.062			Junction			0	2.000	34.700	100 Circular
										1	1.001	34.659	100 Circular
										2	2.000	34.636	100 Circular
5	384643.016	390767.861	36.000	1.300				RWP		0	1.002	34.659	100 Circular
6	384648.522	390774.024	35.800	1.324			Junction			0	3.000	34.700	100 Circular
										1	1.002	34.497	100 Circular
										2	3.000	34.476	100 Circular
7	384647.142	390764.174	36.000	1.300				RWP		0	1.003	34.497	100 Circular
8	384652.648	390770.337	35.900	1.586			Junction			0	4.000	34.700	100 Circular
										1	1.003	34.335	100 Circular
										2	4.000	34.314	100 Circular
9	384648.129	390754.878	36.000	1.300				RWP		0	1.004	34.335	100 Circular
10	384657.816	390765.721	36.000	1.861	450		Manhole	Inspection Chamber		0	5.000	34.700	100 Circular
										1	1.004	34.139	100 Circular
										2	5.000	34.139	100 Circular
11	384661.269	390769.014	36.000	2.009	1050		Manhole	Precast Concrete		0	1.005	34.139	100 Circular
										1	1.005	33.991	100 Circular
12	384650.490	390792.266	34.340	0.495				RWP		0	1.006	33.991	100 Circular
13	384642.838	390782.767	35.600	1.877	450		Manhole	Inspection Chamber		0	6.000	33.845	100 Circular
										1	6.000	33.723	100 Circular
14	384655.798	390769.715	35.900	2.361	450		Manhole	Inspection Chamber		0	6.001	33.723	100 Circular
										1	6.001	33.539	100 Circular
15	384662.064	390771.144	36.000	2.525	450		Manhole	Inspection Chamber		0	6.002	33.539	100 Circular
										1	6.002	33.475	100 Circular
16	384659.118	390782.743	34.340	0.495				RWP		0	6.003	33.475	100 Circular
17	384666.306	390775.207	35.950	2.534	450		Manhole	Inspection Chamber		0	7.000	33.845	100 Circular
										1	6.003	33.416	100 Circular
										2	7.000	33.420	100 Circular
18	384662.108	390787.932	34.340	0.495				RWP		0	6.004	33.416	100 Circular
19	384671.157	390778.446	35.950	2.713	1050		Manhole	Precast Concrete		0	8.000	33.845	100 Circular
										1	1.005	33.362	100 Circular
										2	6.004	33.362	100 Circular
										3	8.000	33.362	100 Circular
20	384683.745	390790.452	36.000	2.879	1200		Manhole	Precast Concrete		0	1.007	33.237	225 Circular
										1	1.007	33.121	225 Circular
										2	9.000	33.194	150 Circular
22	384653.065	390789.611	34.340	0.495				RWP		0	1.008	33.121	225 Circular
23	384653.984	390795.244	34.340	0.495				RWP		0	10.000	33.845	100 Circular
24	384658.850	390795.129	34.340	0.595			Junction			0	11.000	33.845	100 Circular
										1	10.000	33.745	100 Circular
										2	11.000	33.745	100 Circular
25	384661.746	390797.892	34.190	0.495	450		Manhole	Inspection Chamber		0	10.001	33.695	100 Circular
										1	10.001	33.695	100 Circular
26	384663.064	390796.510	34.190	0.528	450		Manhole	Inspection Chamber		0	10.002	33.662	100 Circular
										1	10.002	33.662	100 Circular
27	384667.563	390799.514	37.000	3.746	450		Manhole	Inspection Chamber		0	10.003	33.662	100 Circular
										1	10.003	33.304	100 Circular
29	384671.339	390803.247	35.700	3.016	1200		Manhole	Precast Concrete		0	10.004	33.264	150 Circular
										1	1.005	32.685	225 Circular
										2	10.004	33.134	150 Circular
CW1	384675.876	390807.575	35.700	3.080	1200		Manhole	Precast Concrete		0	1.010	32.684	150 Circular
20A	384693.425	390799.375	36.000	2.625	450		Manhole	Inspection Chamber		0	1.010	32.620	150 Circular
20B	384681.607	390792.657	36.000	3.266	1200		Manhole	Precast Concrete		0	9.000	33.375	150 Circular
										1	1.008	33.109	225 Circular
										0	1.009	32.734	225 Circular

C03	DEC'20	AP	UPDATED IN LINE WITH DRAINAGE LAYOUT	AP	ALS
C02	DEC'20	AP	MINOR AMENDMENTS TO RWP LOCATIONS	AP	ALS
C01	JUL'20	HM	ISSUED FOR CONSTRUCTION	ALS	ALS
T1	NOV'19	AP	SCHEDULE UPDATED	AP	ALS
T0	SEP'19	HM	ISSUED FOR TENDER	ALS	ALS
REV.	DATE	DRAWN	DESCRIPTION	CHKD	APPRD
STATUS DESCRIPTION				STATUS	
APPROVED				A1	

HBL

Brook House

Weybrook Road,

Manchester M19 2QD

+44 (0)161 432 9977 | www.hbl.ltd

Consulting Civil & Structural Engineers

PROJECT			
PROPOSED RESIDENTIAL DEVELOPMENT THE LIMES, DIDSBURY			
DRAWING TITLE			
PROPOSED SURFACE WATER MANHOLE SCHEDULE			
CLIENT			
PROPERTY ALLIANCE GROUP			
HBL REF.	DATE	SCALE(S)	
6633	JULY 2019	1:250	A1
DRAWN	CHECKED	APPROVED	
LB	AP	AP	
DRAWING No.			REV.
6633-HBL-XX-XX-DR-D-0302			C03