

- Notes:
-  Break out existing hard landscaped areas
 -  Remove and re-locate existing gates to main entrance
 -  Remove and re-locate existing bus stop
 -  Remove and relocate existing intercom system
 -  Remove land re-locate existing lamp post
 -  Remove and re-locate existing sign
 -  Section of fencing to be removed

SAFETY HEALTH AND ENVIRONMENT INFORMATION

In addition to the risks normally associated with the types of works involved in this project, please note the following risk information. Project specific S.H.&E. information is also given.

Risks here are not exhaustive and should be read in conjunction with CDM risk assessments/risk registers.

SAFETY HEALTH AND ENVIRONMENT INFORMATION

- All fire exits to the building are to be maintained for the duration of the works. The contractor should provide overhead protection as necessary.
- Vehicle movement and deliveries should not take place during periods where the external grounds are heavily trafficked.
- The premises will be occupied for the duration of the works and so the contractor must ensure that steps are taken to mitigate noise associated with this. Close communication between separate trades will be required at all times to ensure that the likelihood of accidents is minimised.
- Deliveries do not take place during school hours.
- Any site vehicles / equipment should be secure at the end of each working day and not left in use.
- Ensure that the working areas are secure at all times and that materials, tools etc are stored away when not in use. The working areas should be segregated by fully secured hoard fencing / gates / scaffold sheets and adequate signage as a minimum requirement.
- Contractor to refer to the underground utility service drawing which has identified existing services/utilities running beneath the site. The contractor must ensure that none of these services are disturbed by the works.

CONSTRUCTION STAGES RISKS

- No individual other than those involved in the project should be granted access to the working areas without supervision and a full site induction. Ensure that the site is fully secured at all times.
- Please refer to risk assessments and the PCP document for further information.
- Working hours - 08:00 to 16:00 - Please refer to the PCP document for further information.
- Materials deliveries / vehicle movement - Collisions between vehicles and pedestrians
- Site safety - All site workers must wear PPE and follow the rules of the site and all other relevant rules to ensure that there are no clashes.

AS BUILT/IN USE INFORMATION

For information relating to Use, Cleaning, and Maintenance.

See the Health and Safety File relating to the roofing works available on site.

Other previous job specific Health and Safety Files are available on site available from the site manager.

DISMANTLING/DEMOLITION INFORMATION

- All materials that are to be disposed of should be stored in lockable skips that are to be located within the contractor's compound.
- Please refer to all asbestos information, prior to the commencement of any demolition works.

Copyright: All rights reserved. This drawing must not be reproduced without permission from AA Projects Ltd. Do not scale off this drawing. All dimensions are to be checked on site by contractor / sub contractor. Any discrepancies are to be reported to AA Projects Ltd.

Rev	Date	Revision notes	By	Check
A	18.05.23	Amendments to EV Chargers	IR	

Jackson House
Sibson Road
Sale
Manchester
M33 7RR
Tel: 0161 973 7410

Office Locations
Birmingham, Leeds, Liverpool, London, Manchester, Oxford, Rugby, Newcastle
www.aaprojects.co.uk

Client Prosper Trust	Drawing Title Existing Car Park Demolition Plan
Project Title Grange School External Works	Drawn IR Checked CH
	Date 25/02/2023 Date 25/02/2023

Tree to
Remain
No
Pruning
Required

Tree to remain,
Hand dig around Roots
Etc

MATTHEWS LANE

Trees to Be
Retained

Fence line for
Work Area

Fence line for Work Area
Fence line to protect
Trees

REFER TO SLA DRWG LL07 - CAR PARK SETTING OUT

Mini bus

Mini bus

SITE BOUNDARY

CP022

SEP100

CP021

32125

SEP003A

CP020