Appendix B - Tree Schedule

ID number	Common name	Latin name	Age	Height metres	DBH mm	Rating	Life expect	Approx work completion	Observations	Recommendations	Location
T1	Lime *(Tilia cordata)*		Mature	18	425	**C2**	10	6 months	Below ground constraints with the wall removing 50% of its natural spreading roots. This has resulted in the wall being moved and cracks appearing. The tree is moving in strong winds which in turn moves the trees root plate moving the wall. This is not the only vegetation causing stress on the wall.	Reduce the canopy to a 5m nature pole, reassessment of the tree and wall within 36 months. Tree replacement with species that will not outgrow its location and away from the wall by 1.2m	Parsonage Gardens

Key; Green text is High Quality and Value, Blue is Medium, Grey is Low and Red is Remove, see Appendix D - for Tree Categorisation Chart
DBH Diameter at Breast Height. Life expect of 40 suggests 40 years plus

Visual and occupancy
Moderate visual value with high occupancy