

General Notes

BASIS OF DESIGN
This drawing has been prepared from information supplied to us by, or on behalf of the contractor, who should check that the requirements have been correctly interpreted and that all loadings, dimensions, lift heights, bay sizes, erection/stringing sequences etc. are as required and practicable.

IMPOSED LOADS
The contractor is to ensure that the existing structure, it's fabric and/or the ground will safely support the extra imposed loads; or supply new.
Maximum calculated tie load: See notes
Maximum calculated leg load: See notesSee notes

LOADINGS ALLOWED
The contractor must ensure that all loading(s) allowed for is sufficient.
Live loads: See notes
Wind Loadings: As per BS EN1991-1-4.
Maximum number of boarded levels: As Shown

SHORING WORK
We can not and will not pass comment on the structure being shored, as this involves matters beyond our control and knowledge. It is the contractors responsibility to ensure that the existing structure will safely span between our supports, and can be safely shored in the way indicated.

FOUNDATIONS
The contractor must prepare all foundations prior to erection.

TEMPORARY ROOFS
No temporary roof can be made watertight.
Loading: Snow loading assessed using BS EN1991-1-3 (current editions) unless the contractor adopts a snow management system.

MATERIALS
All scaffolding materials forming this structure are to comply, and be constructed in accordance with BS139, BS EN281 and TG20 (current editions).

MODIFICATIONS
No alteration is to be made to the structure detailed on this drawing without prior written permission from Prime Scaffold & Structural Designs Ltd.

PROPERTY
This drawing is confidential and the exclusive property of THE SCAFFOLD CONTRACTOR. No unauthorised use, copy or disclosure is to be made, and is to be returned on request.

DIMENSIONS
Written dimensions shall take precedence over scaled dimensions. The contractor must verify all site dimensions and notify of any discrepancies prior to erection.

PERMITS & PERMISSIONS
The contractor must obtain all permits and permissions prior to erection.

CONSTRUCTION NOTES
1. All beams must be fully laced and plan braced as per manufacturer guidelines and NASC guidance.
2. Unless stated other wise noted all lifts are to be installed using load bearing couplers.
3. Unless stated otherwise maximum transom spacing's are not to exceed 12m c/c.
4. All general construction is to be in accordance with TG20 unless noted otherwise.
5. Main contractor to undertake all making good where necessary.
6. Main contractor are to provide & maintain adequate tie positions.
7. No additional sheeting, wind protection or fans to be added to this structure without prior written permission from Prime Scaffold & Structural Designs Ltd.

ISSUED AS WORKING DRAWING
[APPROVED FOR CONSTRUCTION]

Revisions

	Date	Revision Details	Initial
A	26-04-2024	Initial Issue	HB
B	26-04-2024	Add Bridging beams	HB

Client

TITCHFIELD GROUP
MEDIA • CONSTRUCTION • FABRICATION

Prime Scaffold and Structural Designs Limited
Tel: 0204 581 5020 Web: www.psd.uk.com
f in @ #psdcasffdesign

Title

Proposed Scaffold Layout
Scaffold Banner Frame
70 High St, Manchester M4

DRAWN BY: Hudson Byaruhanga
CHECKED BY: Vipin Bariya
DATE: 26-04-2024
SCALE: As Drg @ All
DOCUMENT NO. PSD009 (1049x594) - Version 4.0 - 30/03/2023

