
BLOCK A
BLOCK B
BLOCK C
BLOCK D
TREE PITS TO BE RELOCATED TO AVOID CLASH WITH PROPOSED MANHOLE & TANK LOCATIONS. LANDSCAPE ARCHITECT & CONTRACTOR TO COORDINATE TREE PIT TO ENSURE MAINTENANCE ACCESS TO CHAMBERS IS ACHIEVABLE.
ALL INTERNAL MANHOLES TO BE DOUBLE SEALED AND LOCKABLE. ARCHITECT TO CONFIRM WHICH MANHOLE COVERS (IF ANY) ARE TO BE RECESSED WITH FINISH TO MATCH SURROUNDING FLOORS OR EXTERNAL AREAS.
CONCRETE COVER SLAB REQUIRED ABOVE TANK DUE TO MINIMAL COVER. TANK MANUFACTURER TO CONFIRM IF REQUIRED.
SITE BOUNDARY
ALL PROPOSED RWP's WITHOUT A DIRECT CONNECTION TO A MANHOLE OR PPIC TO HAVE RODDABLE ACCESS IN FORM OF ACCESS PIPE OR GULLY ABOVE FFL LEVEL
LIFT PIT DRAINAGE TO CONSIST OF FLOOR GULLY WITHIN 500X500X500 SUMP. BLOCK A TO BE PUMPED VIA PUMP CHAMBER INTO FOUL DRAINAGE NETWORK.
CONTRACTOR TO IDENTIFY LOCATION AND DEPTH OF ALL EXISTING SERVICES AND UTILITIES WITHIN AND SURROUNDING THE PROPOSED SITE, PRIOR TO COMMENCEMENT OF ANY WORKS. WHERE NECESSARY, DIVERT/PROTECT EXISTING UTILITIES AND SERVICES, PRIOR TO THE COMMENCEMENT OF ANY WORKS.
M&E TO CONFIRM THE POSSIBILITY OF SWAPPING POP-UP LOCATIONS FOR EASE OF CONSTRUCTION
15.9m³ (11.7m² x 1.61m DEEP) ACO STORMBRIXX HD CELLULAR ATTENUATION TANK OR SIMILAR APPROVED. TO PROVIDE ATTENUATION STORAGE UP TO AND INCLUDING 1 IN 100 YEAR +40% CLIMATE CHANGE RAINFALL EVENT, WITHOUT FLOODING.
M&E TO CONFIRM THE POSSIBILITY OF SWAPPING POP-UP LOCATIONS FOR EASE OF CONSTRUCTION
ALL DRAINAGE PIPEWORK DUCTS AND POWERDATA SUPPLY REQUIREMENTS FOR RAINWATER HARVESTING TANK TO BE CONFIRMED BY 4BACESHES. 4BACESHES TO ALSO CONFIRM WHICH RWPS ARE TO DRAIN INTO RAINWATER HARVESTING TANK AND BELOW GROUND DRAINAGE TO BE REDESIGNED TO SUIT
EXISTING UNITED UTILITIES SEWER WITHIN SITE BOUNDARY TO BE ABANDONED UPSTREAM OF NEW COMBINED MANHOLE. SUBJECT TO SECTION 116 AGREEMENT WITH UNITED UTILITIES.
PROPOSED NEW ADOPTABLE COMBINED WATER MANHOLE ON LINE OF EXISTING UNITED UTILITIES COMBINED WATER SEWER WITH NEW DRAINAGE CONNECTIONS FROM BLOCKS A & B NETWORK.
NON-RETURN VALVE TO INCOMING SURFACE WATER PIPELINE. TIDEFLEX CHECKMATE INLINE VALVE BY ALTHON OR SIMILAR APPROVED. ASSUMED INCOMING FOUL PIPELINES DO NOT REQUIRED NON-RETURN VALVES DUE TO BACKDROPPING INTO COMBINED MANHOLE.
PROPOSED BLOCKS A & B HYDROBRAKE CHAMBER TO RESTRICT SURFACE WATER RUNOFF TO MAXIMUM DISCHARGE RATE OF 8.4 l/s.
EXACT LOCATIONS OF PROPOSED FOUL POP-UPS IN THIS AREA TO BE CONFIRMED BY OTHERS.
POTENTIAL CLASH BETWEEN DRAINAGE AND PROPOSED PLANT. M&E DESIGNER & CONTRACTOR TO COORDINATE PLANT TO ENSURE MAINTENANCE ACCESS TO CHAMBERS IS ACHIEVABLE.
PROPOSED FLOOR GULLY LOCATION TO BE CONFIRMED, LOCATION TO SUIT ANJ PLANT
ANY PROPOSED WORKS OUTSIDE OF RED LINE BOUNDARY ARE SUBJECT TO SECTION 278 AGREEMENT WHICH IS TO BE COMPLETED BY OTHERS.
POTENTIAL CLASH BETWEEN DRAINAGE AND PROPOSED PLANT. M&E DESIGNER & CONTRACTOR TO COORDINATE PLANT TO ENSURE MAINTENANCE ACCESS TO CHAMBERS IS ACHIEVABLE.
PROPOSED 150mmØ PERFORATED UNDERDRAIN TO COLLECT RUNOFF FROM PROPOSED AREAS OF NON-INFILTRATION PERMEABLE PAVING.
NON-RETURN VALVE ON OUTFALL PIPELINE FROM SWW. TIDEFLEX CHECKMATE INLINE VALVE BY ALTHON OR SIMILAR APPROVED.
PROPOSED AREAS OF NON-INFILTRATION (TANKED) PERMEABLE PAVING TO HAVE MINIMUM OF 300mm DEEP GRANULAR DRAINAGE BLANKET
LIFT PIT DRAINAGE TO CONSIST OF FLOOR GULLY WITHIN 500X500X500 SUMP. BLOCK B TO DRAIN VIA GRAVITY INTO FOUL DRAINAGE NETWORK
51.2m³ (11.0m x 4.5m x 1.125m DEEP) CELLULAR ATTENUATION TANK BY SDS OR SIMILAR APPROVED. TO PROVIDE ATTENUATION STORAGE UP TO AND INCLUDING 1 IN 100 YEAR +40% CLIMATE CHANGE RAINFALL EVENT, WITHOUT FLOODING.
M&E DESIGNER & ARCHITECT TO CONFIRM IF POP-UP LOCATIONS CAN BE SWITCHED TO AVOID PIPE BRANCH CROSSOVERS
PROPOSED FILTER DRAIN LOCATED AT BASE OF PROPOSED SLOPE, TO COLLECT ANY RUNOFF FROM PROPOSED LANDSCAPED SLOPE.
LIFT PIT DRAINAGE TO CONSIST OF FLOOR GULLIES WITHIN 500X500X500 SUMP. BLOCK D TO DRAIN INTO FW35A PUMP CHAMBER WHERE IT IS TO BE PUMPED INTO FOUL DRAINAGE NETWORK
PROPOSED NEW WC POP-UP LOCATION AND FLOW RATE TBC BY OTHERS
REQUIRED EASEMENT FOR EXISTING GAS MAINS. DISCUSSIONS WITH SHIPPER REGARDING PROPOSED DRAINAGE LOCATIONS AND PROPOSED SEWERS CROSSING GAS MAINS REQUIRED.
ALL DRAINAGE PIPEWORK DUCTS AND POWERDATA SUPPLY REQUIREMENTS FOR RAINWATER HARVESTING TANK TO BE CONFIRMED BY 4BACESHES. 4BACESHES TO ALSO CONFIRM WHICH RWPS ARE TO DRAIN INTO RAINWATER HARVESTING TANK AND BELOW GROUND DRAINAGE TO BE REDESIGNED TO SUIT
PLEASE REFER TO AJP DWG "FSS-AJP-XX-00-DR-C-0009" FOR TYPICAL SECTION THROUGH PERMEABLE PAVING AND GAS MAIN.
42.8m³ (4.5m x 7.0m x 1.5m DEEP) CELLULAR ATTENUATION TANK BY SDS OR SIMILAR APPROVED. TO PROVIDE ATTENUATION STORAGE UP TO AND INCLUDING 1 IN 100 YEAR +40% CLIMATE CHANGE RAINFALL EVENT, WITHOUT FLOODING.
43.3m³ (9.0m x 4.0m x 1.2m DEEP) CELLULAR ATTENUATION TANK BY SDS OR SIMILAR APPROVED. TO PROVIDE ATTENUATION STORAGE UP TO AND INCLUDING 1 IN 100 YEAR +40% CLIMATE CHANGE RAINFALL EVENT, WITHOUT FLOODING.
EXISTING UNITED UTILITIES SEWER PASSING THROUGH SITE IS ALREADY ABANDONED. EXISTING ABANDONED PUBLIC SEWER TO BE GRUBBED UP OR GROUTED UP WHERE REQUIRED. DETAILS OF GROUTING OR GRUBBING UP TO BE DISCUSSED WITH UNITED UTILITIES.
ANY PROPOSED WORKS OUTSIDE OF RED LINE BOUNDARY ARE SUBJECT TO SECTION 278 AGREEMENT WHICH IS TO BE COMPLETED BY OTHERS.
M&E TO CONFIRM THE POSSIBILITY OF SWAPPING POP-UP LOCATIONS FOR EASE OF CONSTRUCTION
SITE BOUNDARY
Oxford Street
First Street
Store Street
Whitworth Street West
Whitworth Street
Mancunian Way
Fairfield Street
Dale Street
Chorlton Street
Oxford Road
Portland Street
Princess Street
Canal Street
Sackville Street
Piccadilly
Manchester Piccadilly
Manchester Oxford Road
Manchester Victoria
Manchester Deansgate
Manchester Castlefield
Manchester Salford Central
Manchester Salford Crescent
Manchester Salford Central
Manchester Salford Crescent
Manchester Victoria
Manchester Deansgate
Manchester Castlefield
Manchester Oxford Road
Manchester Piccadilly