

1. NOTIFICATION NOTES:
2. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL MSE SCHEDULES & SPECIFICATIONS.
3. ALL DUCTWORK TO BE MANUFACTURED IN ACCORDANCE WITH HVCA DW 144.
4. ALL STEELWORK FOR THE SUPPORT OF DUCTWORK, RIGGING ETC. SHALL BE PROVIDED BY THE MECHANICAL CONTRACTOR.
5. CONTRACTOR TO INCLUDE FOR COORDINATING HIS WORK WITH ALL OTHER TRADES.
6. ALL DUCTWORK PASSING THROUGH FIRE WALLS TO BE COMPLETE WITH FIRE/SMOKE DAMPERS INCLUDING BUILDING IN FRAMES.
7. NEW ALL DUCTWORK TO BE COMPLETE WITH ACCESS PANELS AT ALL REGULAR INTERVALS FOR CLEANING. ACCESS PANELS TO BE PROVIDED AT 3 METRE INTERVALS AT ALL BRANCH CONNECTIONS. ACCESS PANELS TO BE PROVIDED BOTH SIDE FIRE/SMOKE DAMPERS & VOLUME CONTROL DAMPERS.
8. ALL GRILLES & DIFFUSERS TO BE SUPPORTED INDEPENDENTLY OF THE FALSE CEILING GRID.
9. THE FIRE/SMOKE DAMPER INSTALLATION METHODS HAVE BEEN TESTED AND COMPLY WITH ENEN 1366-2 AND DW145. CONTRACTOR TO CHECK DAMPER MANUFACTURERS LATEST TESTS AND APPROVED INSTALLATION METHODS PRIOR TO INSTALLATION.
10. FINAL CONNECTIONS TO GRILLES & DIFFUSERS TO BE CARRIED OUT IN FINISH DUCTWORK TO A MAXIMUM LENGTH OF 500mm.
11. FLEXIBLE DUCTWORK TO BE SUITABLE FOR A HIGH TEMPERATURE SITUATION.
12. ALL DUCTWORK AND LOUVER PLUNJINS TO BE THERMALLY INSULATED AS PER THE MECHANICAL ENGINEERING SPECIFICATION. FRESH AIR INTAKE, EXHAUST, SUPPLY AND EXTRACT AIR DUCTWORK INCLUDED.
13. DUCTWORK MANUFACTURERS=INSTALLERS FABRICATION DRAWINGS ARE TO BE UTILIZED FOR THE INSTALLATION. THESE ARE TO BE ISSUED TO SUBJECT MATTER MANAGER FOR REVIEW PRIOR TO INSTALLATION.

	EXHAUST AIR DUCTWORK
	FRESH AIR DUCTWORK
	KITCHEN EXTRACT
	EXTRACT AIR DUCTWORK
	SUPPLY AIR DUCTWORK
	TOILET EXTRACT

FATB	SERVICE FROM ABOVE TO BELOW
FB/TA	SERVICE FROM BELOW TO ABOVE
DTB	DROP TO BELOW
RTA	RISE TO ABOVE
DFA	DROP FROM ABOVE
RFB	RISE FROM BELOW
 v	PIR FOR VENTILATION CONTROL
	AC CONTROLLER
	FAN CONTROLLER
	THERMOSTAT

FIRE

[illegible]

P02	REVISED SCOPE FOLLOWING VE	19/12/23	LP	DM
P01	ISSUE FOR COMMENT	13/08/23	LP	DM
REV.	DESCRIPTION	DATE	DRW.	CHK.

STATUS	PURPOSE OF ISSUE
S0	WORK IN PROGRESS

DRAWN BY LP	CHECKED BY DM	DATE 12/09/2023
----------------	------------------	--------------------

SCALE (@A0) 1:50	PROJECT NUMBER 13392
---------------------	-------------------------

FILE DRAWING NUMBER	REV.
13392-SIS-XX-00-DR-M-5701	P02