This drawing is subject to copyright and is not to be reproduced in part or whole without approval.
Do not scale this drawing - check all dimensions on site

Health & Safety Notes

1. Contractor must ensure that all work on site is carried out in a safe & satisfactory manner, in accordance with Health & Safety At Work Act 1974, COSHH Regulations 2002 & requirements of C.D.M

NOTE 1

REFER TO CPW DRAWINGS AND SPECIFICATIONS FOR ELCETRONIC ACCESS CONTROL REQUIREMENTS


NOTE 2

* - DENOTES NEW FIRE DOORS FITTED INTO EXISTING HERITAGE FRAMES / SCREENS. CERTIFICATION WILL NOT BE POSSIBLE BUT THIS IS A MODIFIED UPGRADE TO THE EXISTING DOORS / SCREENS AS ACCEPTED BY BUILDING CONTROL.

** - DENOTES NEW TYPE L DOOR (SEE BELOW)



TYPE L
SOLID CORE TIMBER PANEL DOOR
SIZE AND SETTING OUT TO MATCH EXISTING TIMBER PANEL DOOR D1.01.102C & D1.01.104B
NEW MORTICE DEAD LOCK, SHOOT BOLT, PUSH PLATE AND PULL HANDLE



TYPE L
SOLID CORE TIMBER PANEL DOOR
SIZE AND SETTING OUT TO MATCH EXISTING TIMBER PANEL DOOR D1.01.102C & D1.01.104B
NEW MORTICE DEAD LOCK, SHOOT BOLT, PUSH PLATE AND PULL HANDLE

GENERAL

ALL EXISTING STRUCTURAL OPENINGS MUST BE MEASURED BY THE DOOR / SCREEN MANUFACTURER PRIOR TO ANY SHOP FABRICATION.

ALL STRUCTURAL OPENINGS ARE TO BE MEASURED ON SITE PRIOR TO PURCHASE AND INSTALLATION.

SEE NOTE 2

L20/410 - DENOTES NEW FULL DOORSET
L20/411 - DENOTES NEW DOOR FITTED TO EXISTING FRAME

GROUND FLOOR DOOR SCHEDULE

DOOR REF.	ROOM NAME	ROOM NO.	DOOR TYPES	STRUCTURAL OPENING WxHmm	DOOR FINISH	WALL TYPE	CLOSER	DOOR ACCESS (SEE NOTE 01)	FIRE RATING	VISION PANEL	NBS SPEC	NOTES
D1.GF.001	STUDIO	G01	J	1965 X 2865	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	
D1.GF.001A	STUDIO	G01	J	1965 X 2865	LAMINATE	EXISTING	CONCEALED CLOSER			CLEAR	L20/ 410	
D1.GF.002	STUDIO	G02	C - EXTG FRAME	965 X 2140	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD30S *	CLEAR	L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.
D1.GF.004	WC	G04A	A - EXTG FRAME	965 X 2140	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via lock and key			L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.
D1.GF.005	STAFF WC	G05	A - EXTG FRAME	815 X 2060	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via lock and key			L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.
D1.GF.006	CORRIDOR	G06	SEE NOTES COLUMN	2780 x 4400 (Frame height to be 4100)		EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD30S	CLEAR	L20/ 410	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017111
D1.GF.007	WC'S	G07B	A - EXTG FRAME	810 X 1975	LAMINATE	EXISTING	CONCEALED CLOSER				L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.
D1.GF.007A	DIS WC	G07A	A - EXTG FRAME	830 X 2025	LAMINATE	EXISTING	CONCEALED CLOSER				L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.
D1.GF.007B	WC	G07B	A	810 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.GF.007C	WC	G07B	A	810 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.GF.007D	WC	G07B	A	810 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.GF.010B	CORRIDOR	G10	SEE NOTES COLUMN	3000 x 3000		EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD30S	CLEAR	L20/ 410	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017111
D1.GF.010C	CORRIDOR	G10	SEE NOTES COLUMN	2780 x 4400 (Frame height to be 4100)		EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD30S	CLEAR	L20/ 410	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017111
D1.GF.010D	DUCT	G10	A	1010 x 2100	LAMINATE	EXISTING			FD30		L20/ 410	DOOR OMITTED
D1.GF.012	ENTRANCE	G12	SEE NOTES COLUMN	2981 x 3062	LAMINATE	EXISTING	CONCEALED CLOSER				L20/ 411	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017111 ALLOW FOR REFURBISHING THE EXISTING LIGHT BOXES ON EACH SIDE, INCLUDING NEW GLASS, LIGHTS ETC.
D1.GF.013	OFFICE	G13	C - EXTG FRAME	965 X 2140	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD30S *	CLEAR	L20/ 411	~~FRAME TO BE UPGRADED AS PER NBS SPECIFICATION~~
D1.GF.014	OFFICE	G14	M - EXTG FRAME	1910 X 2678	PAINTED TIMBER	EXISTING	CONCEALED CLOSER	Access control via lock and key	FD30S *	CLEAR	--	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118
D1.GF.014a	OFFICE - RISER	G14	A	810 X 2110	LAMINATE	NEW STUD					L20/ 411	~~NEW DOOR FITTED IN NEW PARTITION FORMING FRAMING FOR MECHANICAL EQUIPMENT. IRONMONGERY TO INCLUDE: LEVER HANDLE, THUMBTURN, CLOSER, MORTICE DEADLOCK, STAINLES STEEL BUTT HINGES AND KICKPLATES.~~
D1.GF.015A	OFFICE	G15	C - EXTG FRAME	975 X 2125	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD30S *	CLEAR	L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.
D1.GF.015B	OFFICE	G15	C	824 x 2145	LAMINATE	EXISTING	CONCEALED CLOSER			CLEAR	L20/ 410	
D1.GF.015C	OFFICE	G15	EXISTING				FACE FIXED					DOOR TO BE REFURBISHED AND REPAINTED ONLY
D1.GF.016	KITCHENETTE	G17	C - EXTG FRAME	950 X 2150	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S *	CLEAR	L20/ 411	
D1.GF.017	WC'S	G17A	A - EXTG FRAME	950 X 2150	LAMINATE	EXISTING	CONCEALED CLOSER				L20/ 411	
D1.GF.020	G20	G20	C	1010 X 2110	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card		CLEAR	L20/ 410	INCREASE SIZE OF OPENING WITHIN EXISTING STUD FRAME TO ACCOMDATE DOOR SIZE
D1.GF.022A	CORRIDOR	G22	K	1420 X 2150	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD60S	CLEAR	L20/ 410	DOOR SWING TOWARDS ARTS & HUMANITIES / DIRECTION OF ESCAPE FROM GROSVENOR WEST
D1.GF.022B	CORRIDOR	G22	J	2075 x 2165	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	OPEN UP INFILL ARCH ABOVE TOP OF EXISTING DOOR FRAME
D1.GF.023	ARCHIVE STORE	G23	C	1010 C 2110	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via lock and key		CLEAR	L20/ 410	INCREASE SIZE OF OPENING WITHIN EXISTING STUD FRAME TO ACCOMDATE DOOR SIZE
D1.GF.024A	MULTI-PURPOSE STUDIO	G24	L	1090 X 3025	LAMINATE	EXISTING	CONCEALED CLOSER		~~FD30S~~		L20/ 410	
D1.GF.024B	MULTI-PURPOSE STUDIO	G24	L	1090 X 3025	LAMINATE	EXISTING	CONCEALED CLOSER		~~FD30S~~		L20/ 410	
D1.GF.024C	MULTI-PURPOSE STUDIO	G24	A	1110 X 2110	LAMINATE	NEW STUD	CONCEALED CLOSER		~~FD30~~		L20/ 410	FD 30 RATING REMOVED FOLLOWING CONFIORMATION ON NON-FIRE RATED REQUIREMENT FROM FIRE ENGINEER AND BUILDING CONTROL ON CONFIRMATION FROM END USER THAT NON-FLAMMABLE MATERIALS ONLY TO BE STORED
D1.GF.024D	MULTI-PURPOSE STUDIO	G24	M	1810 X 3025	LAMINATE	NEW STUD	CONCEALED CLOSER		~~FD30~~		L20/ 410	
D1.GF.024E	MULTI-PURPOSE STUDIO	G24	A	1010 X 2110	LAMINATE	NEW STUD	CONCEALED CLOSER		~~FD30~~		L20/ 410	
D1.GF.025	STUDIO	G25	E	960 X 3000	LAMINATE	EXISTING	CONCEALED CLOSER		~~FD30S~~	CLEAR	L20/ 410	**REFER TO DRAWING 1002B-CAA-ZZ-GF-DR-A-017606 FOR FULL DETAILS OF DOOR REQUIRMENTS**
D1.GF.031A	WORKSHOP	G31	E	1330 X 3650	LAMINATE	EXISTING	CONCEALED CLOSER		~~FD30S~~	CLEAR	L20/ 410	**REFER TO DRAWING 1002B-CAA-ZZ-GF-DR-A-017607 FOR FULL DETAILS OF DOOR REQUIRMENTS**
D1.GF.031B	WORKSHOP	G31										**REFER TO DRAWING 1002B-CAA-ZZ-GF-DR-A-017608 FOR FULL DETAILS OF DOOR REQUIRMENTS**
D1.GF.032	WORKSHOP	G32	C	900 X 2100	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card		CLEAR	L20/ 410	
D1.GF.034	STUDIO	G34	C	1010 X 2110	LAMINATE	NEW STUD	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	
D1.GF.035	STORAGE UNDER LANDING	G35	A	1010 X 1815	LAMINATE	NEW STUD			FD30		L20/ 410	
D1.GF.037	STUDIO	G37	C	1000 X 2270	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	
D1.GF.038A	HOLDEN GALLERY	G38	EXISTING	1250 X 2440		EXISTING	FACE FIXED		FD30S (EXISTING)		--	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118 NOTE: REQUIRMENT FOR ENVIROGRAPH INTUMESCENT CLEAR LAQUER TO DOOR AND FRAME HAS BEEN **OMITTED** AS AGREED WITH BUILDING CONTROL AND HOARE LEA
D1.GF.038B	HOLDEN GALLERY	G38	EXISTING	1250 X 2440		EXISTING	FACE FIXED		FD30S (EXISTING)		--	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118 NOTE: REQUIRMENT FOR ENVIROGRAPH INTUMESCENT CLEAR LAQUER TO DOOR AND FRAME HAS BEEN **OMITTED** AS AGREED WITH BUILDING CONTROL AND HOARE LEA
D1.GF.038C	HOLDEN GALLERY	G38	EXISTING	1425 X 2240		EXISTING	FACE FIXED	Access control via magnetic lock and swipe card	FD30S (EXISTING)		--	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118 NOTE: REQUIRMENT FOR ENVIROGRAPH INTUMESCENT CLEAR LAQUER TO DOOR AND FRAME HAS BEEN **OMITTED** AS AGREED WITH BUILDING CONTROL AND HOARE LEA
D1.GF.038D	HOLDEN GALLERY	G38	EXISTING	1425 X 2100		EXISTING	FACE FIXED	Access control via magnetic lock and swipe card	FD30S (EXISTING)		--	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118 NOTE: REQUIRMENT FOR ENVIROGRAPH INTUMESCENT CLEAR LAQUER TO DOOR AND FRAME HAS BEEN **OMITTED** AS AGREED WITH BUILDING CONTROL AND HOARE LEA
D1.GF.040	STORE	G40	A	910 X 2110	LAMINATE	NEW STUD	CONCEALED CLOSER		FD30		L20/ 410	
D1.GF.042	CLEANERS CUPBOARD	G42	A	1010 X 2110	LAMINATE	NEW STUD	CONCEALED CLOSER		FD30		L20/ 410	
D1.GF.043	OFFICE	G43	M - EXTG FRAME	1910 x 2680	PAINTED TIMBER	EXISTING	CONCEALED CLOSER	Access control via lock and key	FD30S *	CLEAR	--	~~FRAME TO BE UPGRADED AS PER NBS SPECIFICATION~~ REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118 NOTE: REQUIRMENT FOR ENVIROGRAPH INTUMESCENT CLEAR LAQUER TO DOOR AND FRAME HAS BEEN **OMITTED** AS AGREED WITH BUILDING CONTROL AND HOARE LEA
D1.GF.043a	OFFICE - RISER	G43	A	810 X 2110	LAMINATE	NEW STUD					L20/ 411	~~NEW DOOR FITTED IN NEW PARTITION FORMING FRAMING FOR MECHANICAL EQUIPMENT. IRONMONGERY TO INCLUDE: LEVER HANDLE, THUMBTURN, CLOSER, MORTICE DEADLOCK, STAINLES STEEL BUTT HINGES AND KICKPLATES.~~
D1.GF.051	STAIRCASE 1	G51	C	860 X 2175	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card	FD30S	CLEAR	L20/ 410	
D1.GF.054A	STAIRCASE 4	G54	E	3650 x 4300	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	THIS DOOR AND SCREEN HAS BEEN OMITTED
D1.GF.054B	STAIRCASE 4	G54	B	1610 X 2110	LAMINATE	NEW STUD	CONCEALED CLOSER		FD30S		L20/ 410	

ALL STRUCTURAL OPENINGS ARE TO BE MEASURED ON SITE PRIOR TO PURCHASE AND INSTALLATION.

SEE NOTE 2

L20/410 - DENOTES NEW FULL DOORSET
L20/411 - DENOTES NEW DOOR FITTED TO EXISTING FRAME

FIRST FLOOR DOOR SCHEDULE

DOOR REF.	ROOM NAME	ROOM NO.	DOOR TYPES	STRUCTURAL OPENING WxHmm	DOOR FINISH	WALL TYPE	CLOSER	DOOR ACCESS	FIRE RATING	VISION PANEL	NBS SPEC	NOTES
D1.01.100	100 **????**	100	E	880 X 3000	LAMINATE	EXISTING	CONCEALED CLOSER			CLEAR	L20/ 410	THIS DOOR AND SCREEN HAS BEEN OMITTED
D1.01.101	OFFICE	101	C	830 X 1975	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card		CLEAR	L20/ 410	
D1.01.102A	STUDIO	102	C	980 X 2000	LAMINATE	EXISTING	CONCEALED CLOSER			CLEAR	L20/ 410	
D1.01.102B	STUDIO	102	J - EXTG FRAME	1965 X 2165	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S *	CLEAR	L20/ 411	NEW DOORS FITTED IN EXISTING FRAME - EXISTING SOLID PANELS WITHIN EXISTING FANLIGHT ABOVE DOORS TO BE REMOVED AND REPLACED WITH CLEAR FD30 FIRE GLAZING WITHIN A SUITABLE CERTIFIED (LORIENT OR SIMILAR) FIRE GLAZING BEAD SYSTEM TO ACHIEVE FD30.
D1.01.102C	STUDIO	102	EXISTING	1965 X 2165	TIMBER PANNELLED	EXISTING	FACE FIXED					14.12.2023 - AMENDED TO RETAIN EXISTING TIMBER PANNELLED DOOR. REFURBISHED AND REPAINTED. INCLUDE FOR NEW PUSH PLATE AND D PULL HANDLE TO BOTH DOOR LEAVES.
D1.01.103A	WC	103	A	810 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.01.103B	WC	103	A	810 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.01.103C	WC	103	A	810 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.01.103D	WC	103	A	810 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.01.103E	WC	103	A	1010 X 2110	LAMINATE	NEW STUD					L20/ 410	
D1.01.104A	STUDIO	104	EXISTING	2470 X 2805	LAMINATE	EXISTING	FACE FIXED		FD30S *		L20/ 255	~~DOOR TO BE UPGRADED AS PER NBS SPECIFICATION~~ REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118 NOTE: REQUIRMENT FOR ENVIROGRAPH INTUMESCENT CLEAR LAQUER TO DOOR AND FRAME HAS BEEN **OMITTED** AS AGREED WITH BUILDING CONTROL AND HOARE LEA
D1.01.104B	STUDIO	104	EXISTING	2470 X 2805	LAMINATE	EXISTING	FACE FIXED		FD30S *		L20/ 255	~~DOOR TO BE UPGRADED AS PER NBS SPECIFICATION~~ REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017118 NOTE: REQUIRMENT FOR ENVIROGRAPH INTUMESCENT CLEAR LAQUER TO DOOR AND FRAME HAS BEEN **OMITTED** AS AGREED WITH BUILDING CONTROL AND HOARE LEA
D1.01.105	OFFICE	105	C	850 X 2100	LAMINATE	EXISTING	CONCEALED CLOSER	Access control via magnetic lock and swipe card		CLEAR	L20/ 410	
D1.01.106	STUDIO	106	L - EXTG FRAME	1800 X 2805	TIMBER PANNELLED	EXISTING	FACE FIXED					14.12.2023 - AMENDED TO PROVIDE NEW SOLID CORE TIMBER PANNELED DOOR TO MATCH D1.01.102C & D1.01.104B. See Note ** INCLUDE FOR NEW PUSH PLATE AND D PULL HANDLE TO BOTH DOOR LEAVES.
D1.01.107	STUDIO	107	C	1010 X 2110	LAMINATE	NEW STUD	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	
D1.01.108A	STUDIO	108	E	1065 X 3100	LAMINATE	EXISTING	CONCEALED CLOSER		~~FD30S~~	CLEAR	L20/ 410	**REFER TO DRAWING 1002B-CAA-ZZ-GF-DR-A-017609 FOR FULL DETAILS OF DOOR REQUIRMENTS**
D1.01.108C	STUDIO	108	E	1065 X 3100	LAMINATE	EXISTING	CONCEALED CLOSER		~~FD30S~~	CLEAR	L20/ 410	**REFER TO DRAWING 1002B-CAA-ZZ-GF-DR-A-017610 FOR FULL DETAILS OF DOOR REQUIRMENTS**
D1.01.109	STUDIO	109	C	800 X 2060	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	
D1.01.110	STUDIO	110	C	930 X 2065	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	
D1.01.111	STUDIO	111	J - EXTG FRAME	1426 X 2050	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S *	CLEAR	L20/ 411	NEW DOORS FITTED IN EXISTING FRAME - EXISTING SOLID PANELS WITHIN EXISTING FANLIGHT ABOVE DOORS TO BE REMOVED AND REPLACED WITH CLEAR FD30 FIRE GLAZING WITHIN A SUITABLE CERTIFIED (LORIENT OR SIMILAR) FIRE GLAZING BEAD SYSTEM TO ACHIEVE FD30.
D1.01.112	CORRIDOR	112	SEE NOTE COLUMN	2780 x 3600 (Frame height to be 3200)		EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017111
D1.01.113	CORRIDOR	113	SEE NOTE COLUMN	2780 x 3600 (Frame height to be 3200)		EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	REFER TO DRAWING FOR FURTHER DETAILS - 1002B-CAA-ZZ-GF-DR-A-017111
D1.01.115	CLEANERS CUPBOARD	113	A	940 X 1990	LAMINATE	EXISTING			FD30S		L20/ 410	
D1.01.151	STAIRCASE 1	151	C	940 X 2140	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	
D1.01.154A	STAIRCASE 4	154	E	3650 X 5450	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S	CLEAR	L20/ 410	THIS DOOR AND SCREEN HAS BEEN OMITTED
D1.01.154B	STAIRCASE 4	154	H (SEE NOTES)	2085 X 2815	LAMINATE	EXISTING	CONCEALED CLOSER		FD60S	CLEAR	L20/ 410	NOTE: DOOR TYPE TO EXCLUDE SIDELIGHTS.
D1.01.154C	STAIRCASE 4	154	B	1610 X 2110	LAMINATE	NEW STUD			FD30S		L20/ 410	

ALL STRUCTURAL OPENINGS ARE TO BE MEASURED ON SITE PRIOR TO PURCHASE AND INSTALLATION.

SEE NOTE 2

L20/410 - DENOTES NEW FULL DOORSET
L20/411 - DENOTES NEW DOOR FITTED TO EXISTING FRAME

MEZZANINE LEVEL DOOR SCHEDULE

DOOR REF.	ROOM NAME	ROOM NO.	DOOR TYPES	STRUCTURAL OPENING WxHmm	DOOR FINISH	WALL TYPE	CLOSER	DOOR ACCESS (SEE NOTE 01)	FIRE RATING	VISION PANEL	NBS SPEC	NOTES
D1.GM.001e	OFFICE	GM01	C - EXTG FRAME	950 X 2150	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S *	CLEAR	L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.
D1.GM.002e	OFFICE	GM02	C - EXTG FRAME	950 X 2150	LAMINATE	EXISTING	CONCEALED CLOSER		FD30S *	CLEAR	L20/ 411	NEW DOOR FITTED IN EXISTING FRAME.

REFER TO CPW DRAWINGS & SPECIFICATIONS FOR LOCATIONS AND TYPES OF ACCESS CONTROL

Rev.	Description	Date
C10	AMENDMENTS TO DOORS D1.GF.014 AND D1.GF.43 AS AGREED WITH THE LPA AND DETAILED ON DRAWING 1003B-CAA-ZZ-GF-DR-A-017116_A_C03_Heritage Doors Upgrade	06.08.2024
C09	CONSTRUCTION RECORD	03.05.2024
C08	DOOR SCHEDULE UPDATED IN LINE WITH CLARIFICATIONS PROVIDED AT THE SITE MEETING 14.12.24 AND C+A EMAIL 20.12.24. DOOR D1.B1.017B ADDED TO SCHEDULE TO REFLECT FIRE STRATEGY DRAWING AND NEWLY FORMED ACCESS. DOOR D1.01.154B NOTE ADDED TO REMOVE SIDELIGHTS FROM DOOR TYPE	08.01.2024
C07	Door References re-added from Revision C05 as follows: **D1.01.151** **D1.01.154A - note this door was historically omitted** **D1.01.154B**	21.11.2023
C06	DOOR SCHEDULE UPDATED WITH AMENDMENTS IN GREEN **AS FOLLOWS:** **D1.GF.501A - NBS REFERENCE CORRECTED.** **DOORS D1.GF.007B, C, D ADDED TO SCHEDULE.** **DOORS D1.GF.035A, B, C & D - CLARRIFICATION NOTE FOR IRONMONGERY ADDED.** **D1.01.103A, B, C, D, & E ADDED TO SCHEDULE.**	05.10.2023
C05	DOORS D1.GM01e & D1.GM.002e ADDED	31.08.2023
C04	DOOR SCHEDULE UPDATED WITH AMENDMENTS IN BLUE	26.06.2023
C03	DOOR OF GF.001, AMENDED TO BE A TYPE J NEW DOOR AND SCREEN	16.05.2023
C02	DOOR SCHEDULE UPDATED WITH AMENDMENTS IN RED	13.03.2023
C01	CONSTRUCTION ISSUE	31.08.2022
P3	DOORS D1.GF.019, D1.GF.019c, D1.GF.006, D1.01.112 + D1.01.113 AMENDED FROM BEING CRITTALL DOORS TO LLOYD NORMALL	28.10.2021
P2	GENERALLY UPDATED & ADDITIONAL EXPLANATORY NOTES ADDED	27.09.2021

Cassidy+Ashton
www.cassidyashton.co.uk
Architecture + Building Surveying + Town Planning

7 East Cliff, Preston, Lancashire, PR1 3JE T: 01772 258 358
Cassidy + Ashton Group Limited, Reg No. 2041 4EB
St Andrews Business Centre, Mold, Flintshire, CH7 1XB T: 01352 708 240

Client
Manchester Metropolitan University

Project
Grosvenor Lifecycle Refurbishment Project

Drawing Title
Ground and First Floor Door Schedule

Drawn by	BL	Checked by	NA	Date	11/08/21
Suitability		PLANNING		Scale @ A1	1 : 20

C+A JOB NO.	PROJECT - ORIGINATOR - VOL. - LEVEL - TYPE - ROLE - NUMBER	REV.
10034	1002B-CAA-ZZ-ZZ-SH-A-017112	C10