

Window Schedule - West				
Mark	Height (mm)	Width (mm)	Required	Description
Level 00				
00-020	983	1015	Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	
00-021	983	1015	Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	
Level 01				
01-019	2330	672	Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	
Level 02				
02-020	2300	1900	Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	
02-021	1200	700	Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	
02-022	2150	1035	Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	


External Door Schedule					
Mark	Height	Width	Comments	Count	Phase Created
EXD-G-C01	2720	2100	Slimline Automatic Door Controls with PIR sensor linked to access management system / Failsafe open on sound of Fire alarm	1	New Construction
EXD-3.03	2300	950		1	New Construction
EXD-3.04	2100	1000		1	New Construction
EXD-3.07	1300	1510		1	New Construction
EXD-3.10	2100	910		1	New Construction
EXD-3.13				1	New Construction
EXD-G-C04	2100	1777	Replace glazed infill panels with vacuum glazing system	1	Existing
EXD-G-C03	2110	1810	New access control	1	Existing
EXD-3.01	2100	1000		1	Existing
EXD-G-001	2720	2100	Replace glazed infill panels with vacuum glazing system	1	Existing
a					
EXD-1-058	2500	2219	Replace glazed infill panels with vacuum glazing system	1	Existing
EXD-3.02	2400	1200		1	Existing



Window - Historic Components Description

- (01) Frame (painted black) - Original Timber Casements (painted white) - Replacement as sample
(02) Fixed window - unsure whether original casement or not
(03) Outside Scope

All replacement external glazing to be Fineo Heritage - Traditional Light - 13mm as product data sheet installed to manufacturer's recommendations.

 Frames to have planted rebated beads externally and internally, new Fineo Heritage Glazing + airtightness system to frame perimeter

 New timber casements to match existing. Glazing replaced with Fineo Heritage, frames refurbished and airtightness applied as spec - **fixed sashes**

Please refer to drawing 3216-RBUM-ARC-XX-ZZ-SH-A-3216 for details of replacment casements and airtightness system



1 Proposed Glazing Window Alterations_West Elevation
1 : 100

Notes:

- This drawing is copyright.
- Do not scale dimensions from this drawing.
- This drawing is to be read in conjunction with all other relevant drawings.
- All discrepancies on this drawing are to be reported to the architect.
- Do not modify any element of this drawing.
- Use drawing only for purpose(s) issued.
- This drawing may contain colour.

Scale Bar

0 1m 3m 5m

Scale: 1:100

North Point

Key Plan

DRAFT

The following external model files are included within this drawing:

C1	2024/08/21	Remaining windows and details issued for Construction	AB	RM
P12	2024/08/07	Windows connected to letter of comfort	AB	RM
P11	2024/08/07	Window Schedules updated	AB	RM
P10	2024/05/15	Change Control 03/04/05	AB	RM
P9	2024/04/26	LBC comments.	AB	RM
P8	2024/03/21	Wall heights adjusted in wellbeing and acc shower, window description added.	AB	RM
P7	2023/12/15	Fire Stopping details issued to Building Control and Fire Engineer	AB	RM
P6	2023/12/01	Listed Building Consent Submission.	AB	RM
P5	2023/11/24	Stage 4 Issue for Costing	MC	RM
P4	2023/10/06	Stage 4 Issue for Costing	AB	RM
P3	2023/08/04	Drawings issued for LBC Application	AB	RM
P2	2023/07/21	Preliminary Issue to Heritage Consultant	AB	RM
P1	2023/06/02	Stage 3 Preliminary Issue for costing	AB	RM
Rev	Date	Revision Notes	Drawn	Review

MANCHESTER
1824
The University of Manchester

ARCADIS

Project
Rutherford Building

Drawing Title
Window + External Door Schedule_West Elevation

Job Number 141532	Date FEB'23	Security Classification	Drawn By MTW
Scale@A1 As indicated	Purpose CONSTRUCTION	Reviewed By RM	
Drawing Number 3211-RBUM-ARC-XX-ZZ-SH-A-3211	Revision C1		