



Renovation works		
REFERENCE	DESCRIPTION	Count
GNOTE 01	Existing doors to be upgraded with concealed fire/acoustic seals added within the lining rebates and to the threshold Doors to be locked.	11
GNOTE 02	Partition walls / doors to be upgraded to be in accordance with fire strategy drawings, risers to be fire stopped accordingly.	9
GNOTE 03	Existing doors to be upgraded with concealed fire/acoustic seals added within the lining rebates and to the threshold	22
GNOTE 04	Screen frame to be sealed around perimeter with intumescent sealant, glazing to be replaced by 30min fire integrity/insulation with intumescent seals within frame rebate.	2
GNOTE 05	Existing doors to be upgraded with concealed fire/acoustic seals added within the lining rebates and to the threshold Doors to be locked Panic fire bar to be installed Museum side.	2
GNOTE 06	Existing terrazzo floor to be repaired, concrete repairs may be required prior to carrying out the works	1
GNOTE 07	Paint on timber cladding to be removed, timber to be returned to original natural poished timber finish	2

[illegible]