



1:120 PLAN OF AFTON MANOR & RAILTON AVENUE ALLEYWAY @ A3

KEY TO TREES

Number	Species	Girth	Proposed Works
T1	Oak	80cm stump	No work
T2	Lime	70cm Forks at 3 & 4.5m	Remove dead branches from mid-canopy level on SW side of canopy. Remove epicormic growth below forks (to 4.5m above ground level)
T3	Young multi stemmed Lime	40cm	Remove epicormic growth to 4m from ground level
T4	Small Lime		Remove lateral limb at 6m height approx. 175mm dia, overhanging alleyway to SW. To be taken back to main trunk. Remove epicormic growth to 4m above ground level.
T5	Sycamore	50cm girth	No work
T6	Lime	70cm girth	Remove side branches approx. 75mm girth to 4m above ground level.
T7	Sycamore	40 cm girth	Tree to be felled to ground level, tree supressed by adjacent T10. Imbalanced crown with branches mainly to southwest of trunk
T8	Ash	40 cm girth	Large lateral limb, approx. 300mm dia. overhanging neighbouring properties to the W. To be taken back to 2m from main trunk
T9	Sycamore	70cm girth Forks at 5m	Remove deadwood on south and epicormic growth below 3m from ground
T10	Holly	20cm girth Multistem	No work
T11	Oak	70cm	No work
*	Leylandii cypress	Between 6-8m high	Fell to ground level. Overshadowed by adjacent trees.

