

House Number	Road	Tree number	Species	Height	Specification 1	Specification 2
16	Meadowbank	228	Hawthorn	5	Crown lift to 5.2m over road, 3.5m over pavement	Deadwood
op 4	Meadowbank	235	Cherry	10	Crown reduce by 30% (including crown lift to 5.2m over road, 3.5m over pavement)	
2	Meadowbank	153	Lime	16	Crown lift 6m all round	
s/o 71	Claude Road	30	Hawthorn	6	Crown lift to 5.2m over road, 3.5m over pavement	
70	Claude Road	25	Cherry	6	Crown lift to 5.2m over road, 3.5m over pavement (including remove branches growing over acer)	
2	South Drive	16	Acer	11	Crown lift to 5.2m over road, 3.5m over pavement including clear street light	Part crown reduce to clear building by at least 3m
9	South Drive	9	Hawthorn	5	Crown lift to 5.2m over road, 3.5m over pavement	
1	East Meade	277	Bird Cherry	6	Crown lift to 5.2m over road, 3.5m over pavement	
7	The Thorns	288	Cockspur Thorn	4	Crown lift to 5.2m over road, 3.5m over pavement	Remove epicromic growth
2	East Meade	327	Sycamore	14	Crown lift to 5.2m over road, 3.5m over pavement including clear street light	
s/o 15	East Meade	298	Pyrus	7	Crown lift to 5.2m over road, 3.5m over pavement	Remove epicromic growth
s/o 17	East Meade	316	Beech	18	Crown lift to 6m all round	
12	Southgate	310	Oak	16	Crown lift to 6m all round	Part crown reduce to clear building by at least 3m
36	South Drive	263	Rowan	6	Fell and replant due to extensive deadwood and dieback	Grind
26	South Drive	267	Purple plum	6	Crown lift to 5.2m over road, 3.5m over pavement	
59	South Drive	212	Bird cherry	7	Crown lift to 5.2m over road, 3.5m over pavement including clear street light	Part crown reduce to clear building by at least 3m
16	South Meade	344	Norway maple	18	Crown lift to 6m all round	Part crown reduce to clear building by at least 3m
s/o 7	The Meade	333	Cherry	7	Crown lift to 5.2m over road, 3.5m over pavement including clear street light	Part crown reduce to clear building by at least 3m
51	Brookburn Rd	85	Sorbus	5	Crown lift to 5.2m over road, 3.5m over pavement	Deadwood
94	Claude Road	62	Lime	18	Crown lift to 6m all round	Deadwood
92	Claude Road	63	Robinia	16	Crown lift to 6m all round including remove bottom 150mm diameter limb from over road	Deadwood
86	Claude Road	66	Robinia	16	Sonic tomograph of main stem due to presence of ganoderma wood decay fungus	
84	Claude Road	67			Grind stump	Replant
80	Claude Road	69	Lime	10	Crown lift to 5.2m over road, 3.5m over pavement	
s/o 8	The Willows	140	Lime	9	Crown lift to 5.2m over road, 3.5m over pavement	Deadwood
s/o 40	Meadowbank	137	Robinia	11	Crown lift to 5.2m over road, 3.5m over pavement	Deadwood
10	West Meade	162	Alder	11	Crown lift to 5.2m over road, 3.5m over pavement including clear street light	Part crown reduce to clear building by at least 3m