



General Notes:

All proposed tree locations are subject to co-ordination with drainage layout and subject to modification depending on the location of underground services and utilities. Drainage engineer to co-ordinate services layout in conjunction with the landscape plan to avoid conflict as much as possible. Allowance to be made of tender stage for the possible requirement for root barriers once the drainage layout is confirmed. CA to be informed immediately once this is available.

PLANTING SCHEDULES:

Trees	Name	Abb.	Form	Girth (cm)	Height (cm)	Clear stem (cm)	Root	Quantity
Acer campestre 'Siretwise'	AcS	Standard Extra Heavy	14-16	425-600	175-200	RB	6	
Betula pendula	Bp	Standard Extra Heavy	12-14	350-425	175-200	RB	3	
Betula utilis 'Jacquemontii'	BuJ	Standard Extra Heavy	18-20	min 450	min 200	RB	2	
Carpinus betulus 'Frans Fontaine'	CbFF	Standard Extra Heavy	14-16	425-600	175-200	RB	4	
Pinus catteriana 'Chanticleer'	PcC	Standard Extra Heavy	18-20	min 450	min 200	RB	2	
Prunus 'Sunset Boulevard'	PSB	Standard Extra Heavy	16-18	350-425	175-200	RB	4	
Tilia cordata 'Ranchol'	TcR	Standard Extra Heavy	16-18	350-425	175-200	RB	4	

Ornamental Shrub Planting:								
Name	Abb	Height (cm)	Root	Container	Habit	Density	Quantity	
Euonymus fortunei Emerald & Gold	EEG	30-40D	C	SL	Bushy	4/m ²	66	
Hebe rakodensis	Hr	30-40	C	SL	Bushy	4/m ²	148	
Hebe 'Green Globe'	HGG	30-40	C	SL	Bushy	4/m ²	232	
Hebe 'Yield Edge'	HRE	30-40D	C	SL	Bushy	4/m ²	148	
Lonicera nitida Malgreen	LNM	30-40D	C	SL	Bushy	5/m ²	223	
Prunus laurocerasus 'Otto Luyken	PIOL	30-40	C	SL	Bushy	4/m ²	85	
Sarcococca confusa	Sc	20-30	C	SL	Bushy	4/m ²	30	
Viburnum davidii	Vd	20-30	C	SL	Bushy	5/m ²	49	
Viburnum lino Eve Price	VIEP	30-40	C	SL	Bushy	4/m ²	140	

Specimen Shrub Planting:							
Name	Abb	Height (cm)	Root	Container	Habit	Quantity	
Amelanchier lamarckii	Al	250-300	RB	/	Multi Stem	2	
Phormium cookianum 'Tricolor'	PcT	/	C	10-12L	Triple Crown	6	
Phormium 'Yellow Wave'	PYW	/	C	10-12L	Triple Crown	3	

Hedge Planting	Name	Abb	Height (cm)	Root	Specification	Centre Spacing	Quantity
Prunus laurifolia	Pl	80-100	RB	Bushy	Clipped sides	50cm centres, 40cm between rows	435

Note:
* Hedge plants to be planted in doubled staggered rows at centres noted above. Maintained at 1.2m high
* Any plants found not to be in accordance with the specification above after post completion site inspection will be replaceable at contractors expense in accordance with substitutions paragraph of specification on drawing.
** Contractor to ensure numbers on plant schedules match numbers on drawing before placing order for plants.

SOFT LANDSCAPE SPECIFICATION NOTES

NOTE: All soft landscape works to be carried out in accordance with BS4428:1989.

SUBSOIL

Subsoil should be broken up to relieve compaction and aid drainage prior to topsoiling to the following depths:

- For light and non cohesive subsoils: 300mm
- For stiff clay and cohesive subsoils: 450mm

Immediately before spreading topsoil, remove stones larger than 50mm.

TOPSOIL

Existing site won topsoil to be reused for soft landscape areas if sufficient quantities are available and the topsoil meets the criteria for multipurpose topsoil as defined in table 1 of BS3882:2015 specification for Topsoil.
If imported topsoil is required it is to be supplied and spread by the main contractor to the approval of the Landscape contractor, in accordance with BS 3882:2015. To be a natural sandy loam, of medium texture, with a pH between 5.5 and 7.8, not more than slightly stony and free of pernicious weeds. Subsoil to be well broken up prior to top-soiling to relieve compaction.
Topsoil depths should be:

Areas for Ornamental Shrub Planting: minimum 400mm
Areas for cultivated turf: minimum 150mm

Note: Contractor to provide soil testing declaration of analysis certification and sample for inspection & approval prior to delivery of any topsoil to site and post planting as evidence that the correct soil has been used

CULTIVATION

Weeds to be prevented from seeding or becoming established by applying a suitable herbicide and allowing the correct time to elapse, as directed by the manufacturer.
Compacted soil to be broken up to a depth of 100mm, with any stones, grass tufts or rubbish larger than 50mm in any direction to be removed, leaving a regular and even surface.
Suitable slow release fertiliser to be supplied and spread @ 50g/m² to all planted areas.

CLIMATIC CONDITIONS

Topsoiling should be carried out in the driest conditions possible - cultivation to be carried out when the soil is moist, friable and not waterlogged or frozen. Topsoil should not be handled during or after heavy rainfall or when it is wetter than the plastic limit as defined by BS 3882. Planting should not take place in waterlogged conditions or when the ground is frozen.

SOIL AMELIORANT

Peat-free compost to be spread over ornamental shrub beds @ minimum 50mm depth prior to cultivation.

TREES

All trees within shrub beds to be planted in separate pits in accordance with tree planting detail:

79-E1529-VEC-XX-XX-DR-L-Ss.45.35.05.64-0001-A5 - Tree Pit Detail - Soft

79-E1529-VEC-XX-XX-DR-L-Ss.45.35.05.64-0002-A5 - Tree Pit Detail - Cells

All plant material to comply with BS 3733 Part 1:1992, be obtained from a nursery certified by the HTA and transported to site in accordance with the HTA Plant Handling Guide: 1996.
All trees to be planted to the original root collar and secured in place with underground guying system in accordance with tree planting detail. All trees to be fitted with aeration and irrigation system in accordance with tree planting detail.

If the trees are to be planted outside of the planting season (late October - Late March) then containerised stock to be used in lieu of root ball to the same specification- allowance to be made for this at tender stage if required once construction timetable is known and CA informed immediately.

PROPOSED ORNAMENTAL SHRUB PLANTING

All shrubs to be positioned as shown on the drawing and to the density and specification noted in the plant schedule.

Planting holes to be 150mm wider than the root spread, have the base ground thoroughly broken up before planting and backfilled with peat free compost.

All shrubs to be equally spaced throughout the planting areas to the specified density in a staggered arrangement unless otherwise noted in the planting schedule.

FORMAL HEDGE PLANTING

Areas to receive hedge planting shall be cleared of all vegetation and cultivated as described above. Rotavate areas to a minimum depth of 300mm to form an open textured free draining growing medium. Remove all stones and other debris larger than 50mm in any one direction and remove all litter and vegetation matter prior to planting. Hedge plants to be spaced out and arranged in accordance with the notes for each species - refer to hedge planting schedule opposite.

GRASSED AREAS

Turfed areas should be laid in accordance with BS 3949:1998: Recommendations for Turf for general purposes and BS 4428:1989 General Landscape Operations.

Height of initial growth: 100mm

Height of first cut: 50mm

Height of growth: The height of growth must not exceed 100mm at any time.

Frequency: Cut as and when necessary to a height of 25mm, using a rotary mower and remove all arisings.

Timing: When grass reaches scheduled height of maximum growth and is reasonably dry.

Application: At the time of each cut, 10m of grass edges round the base of trees, manholes etc and remove arisings. Sweep all adjoining hard areas clear of cuttings and remove.

Weeding: Keep the sward substantially free of broad leaved weeds by applying a suitable selective herbicide.

Fertilizer: March application: 15:10:10 Spring turf fertilizer at 35g/m².

September application: 5:10:10 Autumn turf fertilizer at 50g/m².

SUBSTITUTIONS:

Upon submission of evidence that certain materials, including plant materials, are not available at the time of the landscape contract, the Landscape Contractor may be permitted to substitute other materials and plants in exceptional circumstances during the contract with an agreed adjustment of prices.

All substitutions shall be of nearest equivalent species and variety to the original specified but shall be subject to approval by the Landscape Architect before any change is made.

TIMES OF YEAR FOR PLANTING:

Soft landscape works to be carried out during the first possible planting periods following completion of the building and associated engineering works to car park and access roads in accordance with the times of year for planting notes below:

- Native and ornamental trees: During dormant winter period - Late October to late March (only if planted in the planting season otherwise containerised stock to be used).
- Bare root native transplants: During dormant winter period - Late October to April.
- Container grown ornamental and specimen shrubs: At any time if ground and weather conditions are favourable.

MULCH

75mm depth of 8-35mm ornamental bark mulch (peat-free) to be supplied and spread to all planting areas. Finished mulch level to be installed and maintained at 25mm below any adjacent kerbs or paving surfaces.

MAINTENANCE

All planting areas to be maintained to a high standard by the contractor for 12 months after practical completion, to ensure the landscape scheme is successful, and discourage decline of the area.

Minimum frequency of maintenance visits:

December / January / February & March - 1No. visit each month

April to November - 2No. visits each month.

Generally, during the first 12months:

- All planting beds to be re-limed and kept weed free through hand weeding and application of an approved herbicide where appropriate.
- All litter to be picked and removed from landscape areas.
- Mulch to be topped up as required to maintain the specified thickness.
- The condition of all trees is to be regularly checked, with ties and stakes adjusted or replaced as necessary.
- Shrubs / hedges to be pruned at appropriate times of year for each species to promote healthy growth and desirable ornamental features.
- Grass lawn areas to be cut and maintained in accordance with specification note above.
- All arisings to be removed from site.
- Any defects or plant losses occurring during the first 12 months defects period to be replaced at the contractors expense.

Following the initial 12 month establishment period the ongoing landscape management will be the responsibility of an commercial landscape maintenance contractor under a landscape maintenance contract.

GENERAL WATERING

All soft landscaping to be subject to a watering regime which is absolutely essential to ensure the continued success of the scheme, particularly during the initial 12 month establishment period. The watering frequency should be as necessary to ensure the continued thriving of all grass, hedges, trees and ornamental planting but as a minimum should follow the maintenance regime as set out above and be carried out at the time of each maintenance visit. During dry periods it may be necessary to increase watering visits to once per week. If the planting is looking dry please contact Landscape Architect to arrange the extra maintenance visits if necessary. The soil should be checked for dryness using either a soil moisture sensor or by inserting a spade into the ground to a depth of 500mm to observe the appearance of the soil. If the soil is moist there is no need to water but if it is bone dry then watering procedure should be carried out immediately. Water supply should be from potable mains water or an approved alternative. The full depth of topsoil should be wet without loosening or damaging plants. Any compacted soil should be broken up sufficiently to allow water to reach the rootzone.

WATERING TREES

Trees to be watered in accordance with BS 8545:2014 Tree - From Nursery to Independence.

Trees should be watered via the installed irrigation / aeration pipes around the base of the trees stem in accordance with the manufacturer's instructions to ensure the water reaches the roots of the tree. Below is a suggested watering regime but this should be used as a guide only and may require modification in times of drought or flood, dependant on the ground conditions at the time, which should be monitored as above:

- March - October: 40 litres to be poured into irrigation pipe on every maintenance visit

SOFT LANDSCAPE KEY:

Existing trees to be removed
In order to facilitate the proposed development.

Existing trees and vegetation to be retained
Retained and protected during construction and landscape works in accordance with BS3882:2012 guidance

Proposed trees in soft landscape
Refer to plant schedule for species & specification
Refer to Drawing No. 79-E1529-VEC-XX-XX-DR-L-Ss.45.35.05.64-0001-A5 for Tree Pit Detail - Soft

Proposed trees with structural cell systems
Refer to plant schedule for species & specification
Refer to Drawing No. 79-E1529-VEC-XX-XX-DR-L-Ss.45.35.05.64-0002-A5 for Tree Pit Detail - Cells

Proposed specimen shrub planting
Refer to plant schedule for species & specification

Proposed ornamental shrub planting
Refer to plant schedule for species & specification

Proposed formal hedge planting
Refer to plant schedule for species & specification
To be maintained at 1.2m high

Proposed close mown grass area
To be high quality amenity turf

Proposed ornamental bark mulch surface finish
• 75mm of ornamental bark mulch in accordance with BS8545
• 2014 recommendations
• 500mm overrun margin

Proposed hard landscape
To architects specifications

REV	DATE	DESCRIPTION	DRAW	CHE
-----	------	-------------	------	-----

C01	18.12.23	MANCHESTER TOWN	18	18
-----	----------	-----------------	----	----

Client:
ALDI - Aldi Stores Ltd.

Aldi Foodstore

Project Address:
**VICTORIA AVENUE EAST
MANCHESTER
M1 7SN**

Drawing Title:
LANDSCAPE PLAN

Job No.:
79-E1529 VECTOR XX

Client Ref:
EN_32_35_80-0001

Drawn By:
HS

Checked By:
DW

Date:
18.12.23

Scale:
1:200

Rev:
A0

Level:
XX

Drawn By:
DR

Client Ref:
L

VECTOR Project No: 14223

vector
design concepts

LANDSCAPE DESIGNERS
4 ST JOHNS NORTH, WAKEFIELD, WF1 3QA. TEL 01924 332054
www.vectordc.co.uk