

C18 - Summary of changes

- Curtins Western Road layout added: 20200-CUR-XX-XX-DR-C-95510-P03 (levels in abeyance)
- 3 trees in arrival space adjusted to avoid drainage pipes
- Singal crossing retained in current location on Central Drive

LEGEND

1. Main Arrival Space
2. Building (with Roof Plan)
3. FM Yard & Plant Rooms
4. Existing Staff Car Parks
5. Gardens, Roof Gardens & Courtyards
6. Perimeter Landscape Treatment

KEY

NBS		
Q22.107J	P1A	FM Service Yard (Macadam)
Q22.175J	P1B	Black Macadam Footpaths
Q22.175J	P1B	1.5m width Macadam Maintenance MEWP Path to Building Perimeter with upstand kerb
Q22.176J		Coloured Macadam (buff) to Private Courtyards & Gardens
Q22.178J		C19 - Buff macadam changed to RBG Coloured Macadam (Buff) to Main Arrival Space (Vehicular Load)
Q23.220	P6	C19 - Buff macadam changed to RBG Ground Level Resin Bound Gravel Surfacing Aztec Gold & Tuscan Barley Butter
Q23.225	P6A	Roof Garden Resin Bound Gravel Surfacing Aztec Gold & Butterscotch
Q23.165J	P8	White Decorative Loose Gravel, Pebbles & Cobbles to Visual Courtyards
Q25.121J	P9	Concrete Stepping Stone Soft Ground with Sedum Planting Around
Q30.400		Grass Lawns to Arrival Space, Gardens & Courtyards
Q30.400		Wildflower & Grass Seed Mix to Perimeter Areas
Q25.185J	P12	Vehicle Overrun Edge Reinforcement at Arrival Space nom 640mm wide
Q31		Low/Ground Cover Native & Ornamental Perimeter Planting
Q31		Sensory Ornamental Planting Within Courtyards, Gardens & Arrival Space with Specimen Shrubs & Grasses
Q31		Screen Hedge to Inside of Security Fence Single row
Q40.150 Q31	F5	Native Hedge - Double Staggered Row with Post & Wire Fence (F5) to Centre-line
Q31.440 Q37.400		300mm Sedum Edge to Building at Ground Level Inner Courtyards/Gardens Only
Q31		Native / Ornamental Trees
Q31.520A		Arrival Space Seating Niches with Feature Pines See Tree pit detail TP2/0411 on Drg 0411
Q31		Bamboo / Medium Feature Shrub to Gardens & Courtyards
Q31		Low Level Feature Shrubs to Gardens, Courtyards & Roof Gardens
D41.211J	W1	Gabion wall (height varies)
Q10.195J	W2	Low Ribbon Wall / Seating Walls to Arrival Space Seating Niches & Planting Beds
D41.520A		PL1 Timber Sleeper Raised Planter
Q10.196J		PL2 Powder Coated Steel raised planters (450mm high) to Cafe Terrace
Q10.197J		PL3 Powder Coated Steel raised planters (450mm high) to Roof Gardens
Q40.125A Q40.560A	F1	4.0m Security Weld-mesh Fencing to Gardens, Courtyards & Section 136 Compound
Q40.125A Q40.560A	F3	2.4m Security Weld-mesh Fencing to FM Yard Compounds
Q40.310J	F4	2.4m Timber palisade Fence to PICU Garden & FM Yard
Q40.311	F4A	4m Timber Acoustic Fence to FM Yard
Q40.150	F5	1.2m Post & Wire Fence to Centre-line of Hedge
L37.110 L37.150		Step with Handrail to Part M Requirements
		Proposed 0.5m Contours
		Lighting as M&E drawings - Bollards, on Posts & Fence mounted (building mounted lighting not shown)

GROUP 1 FURNITURE

Q50.190A Q50.196	Stainless Steel Bollards Drop Bollard Variant
Q50.210	Cycle Stands
Q50.219A Q50.220A	B1A Curved Segment Timber Bench to Arrival Space B2 Linear Bench to Arrival Space
Q50.220C Q50.225A	B4 Timber Bench's with Arm & Backrest B5 Solid Bench's (coloured)
Q50.225B	B6 Coloured Stools/Tub Seats
Q50.240	Litter Bins to Arrival Space

GROUP 2 FURNITURE

	External Gym Equipment to be Supplied by GMMHT
	Refuse Collection Bins to be Supplied by GMMHT

GROUP 3 FURNITURE

	Dining Tables & Picnic Benches to be Supplied by GMMHT

GMMHT trust to provide own fitness equipment that will be located and fixed in various gardens by contractor. Exact equipment to be positioned on detailed plans.

NOTES:

DO NOT SCALE. Use figured dimensions only. The contractor is requested to check all dimensions before the work is put in hand. Copyright of this drawing belongs solely to Iteriad Ltd ©. This drawing must only be used for the purpose for which it is supplied and its contents must not be reproduced for any purpose without written permission. Areas indicated, or areas calculated from this drawing should be used for valuation purposes or as the basis for development contracts. Iteriad Ltd is a limited liability company registered in England and Wales. Number 7966573

NOTES:
Based on GDA Building floor plans:
NMGNPH-GDA-VV-00-DR-A-0001 - Lower GF
NMGNPH-GDA-VV-01-DR-A-0001 - Upper GF

To be read in conjunction with Landscape Series GA's:
NMGNPH-ITR-00-XX-DR-L-0010
NMGNPH-ITR-XX-XX-DR-L-0100 (Lower GL West)
NMGNPH-ITR-XX-XX-DR-L-0200 (Upper GL East)
NMGNPH-ITR-XX-XX-DR-L-0300 (Roof Gardens)
NMGNPH-ITR-XX-XX-DR-L-0037 Kerbing & Edging Plan
NMGNPH-ITR-XX-XX-DR-L-0038 Fencing & Balustrade Plan
NMGNPH-ITR-XX-XX-DR-L-0039 RBG Colours Key Plan

Construction Details series:
NMGNPH-ITR-XX-XX-DR-L-0400

NBS Specification:
NMGNPH-ITR-VV-XX-SP-L-2001

Schedules:
NMGNPH-ITR-VV-XX-SH-L-1000 (Planting)
NMGNPH-ITR-VV-XX-SH-L-1001 (Components)

REV	DETAILS	DRAWN BY	CHECKED BY	CHECKED DATE
C20	La-yby changed to black Macadam	AP	KH	17.06.24
C19	Buff macadam changed to RGB	AP	KH	10.06.24
C18	Western road added	AP	KH	16.05.24
C17	9Nr arrival space trees relocated as shown	AP	KH	09.05.24
C16	RBG colours & additional bin locations confirmed, plus minor as built updates	AP	KH	05.03.24
C15	Sliding gate and bins tore locations update	AP	KH	13.02.24
C14	Woostone paving omitted	AP	KH	01.02.24
C13	Updates as agreed with IHP 17.01.24	AP	KH	18.01.24
C12	MEWP path/gate adjustments	AP	KH	09.01.24
C11	Bellmouth as MFT updated	AP	KH	19.12.23
C10	FM yard updates	AP	KH	29.11.23
C09	FM yard updates	AP	KH	09.11.23
C08	4m Acoustic fence to FM yard added	AP	KH	10.10.23
C07	Lighting as 21084_DWG_EX_0000_R09	AP	KH	29.09.23
C06	Various updates	AP	KH	04.09.23
C05	Fire exit compounds added	AP	KH	12.07.23
C04	F2 fence substituted with F1 fence	AP	KH	06.07.23
C03	General updates, notes added	AP	KH	08.02.23
C02	ACO omitted & steps added	AP	KH	12.10.22
C01	Issued for construction, roof gardens changed to rubber, PROW uptdated S136 compound fence height > to 4m	AP	KH	25.08.22
P15	Updated to latest floor & roof plans	AP	KH	25.05.22

CLIENT

Greater Manchester MH NHS FT

MASTERPLANNERS/LANDSCAPE ARCHITECTS

iteriad
Studio 2 Cragwood Cottages, Ecclerigg, Windermere, Cumbria LA23 1LQ
T: (+44) 15394 43018
E: studio@iteriad.com
W: www.iteriad.com

PROJECT TITLE

North View

DRAWING TITLE

OVERALL LANDSCAPE SITE PLAN WITH ROOF PLAN

SCALE	DRAWN BY	DATE
1:500@A1	AP	29.09.20

PURPOSE	STATUS
For Construction	S5

JOB/DRAWING NUMBER: NMGNPH-ITR-00-XX-DR-L-0010 REVISION: C20