



- Location A: Acer Campestre Louisa Redshine
Location B: Acer Campestre Louise Redshine
Location C: Acer Campestre Fastigiata

1. All newly planted trees are to be thoroughly watered immediately after planting (twice within the first 48 hours) and during any prolonged periods of dry weather.
2. Once planted, trees should be inspected on an annual basis for signs of poor condition or damage.
3. Any weeds found growing around the newly planted trees should be removed, annually in subsequent years after planting.
4. Tree ties should be inspected annually and adjusted if required. Tree ties and stakes should be removed within three years of planting unless establishment is deemed to be unusually slow.
5. New bark mulch should be applied around the base of each tree to a depth of no less than 75mm, each year for at least the first three years (to conserve water close to the soil and inhibit weed growth).

[illegible] Proposed Locations
for New Trees

MANCHESTER
1824
The University of Manchester

Manchester Academy
UoM Students' Union

Directorate of Estates and Facilities
Beyer Building | Oxford Road
Manchester | M13 9PL

For Planning

Designed		Date	Signed
Drawn	LP	Date MARCH 24	Signed
Checked		Date	Signed
Approved		Date	Signed
Scale:	1:1250	Datum:	AOD
Original Size:	A2	Grid:	OS
Suitability Code:		Project Number:	PN8231

Bus Bay Alterations

Proposed Tree Locations Plan



www.arcadis.com

Drawing Number:

8231 06

Revision:

—