

NOTE - All samples of planting stock to be approved by landscape architect prior to procurement and planting. Nursery to submit photographic evidence of stock quality, allow for nursery visit to tag trees.

TREES									
Code	**Species**	**Common Name**	**Quant. (no.)**	**Habit**	**Tree girth (cm)**	**Tree height (m)**	**Size notes**	**times transplanted**	**Root**
Evergreen Trees									
Qi	Quercus ilex	Holly Oak - Evergreen	**2**	specimen, from extra wide spacing	30-35cm	4-4.5m	Semi-mature, with 2.2m clear stem, underground guyed	4 x Transplant	wire rootballed
Pn'A'	Pinus nigra 'Austriaca'	Austrian Pine	**7**	specimen, from extra wide spacing	4-4.5m	4-4.5m	Semi-mature, with 2.2m clear stem, underground guyed	4 x Transplant	wire rootballed
Bu	Osmanthus aquifolium	Holly olive	**3**	Multistem specimen, from extra wide spacing	-	3-3.5m	Multi-stem, timber staked	4 x Transplant	wire rootballed
Deciduous Trees									
Al	Amelanchier lamarckii	Snowy Mespilus	**6**	Multistem specimen, from extra wide spacing	-	3.5-4m	Multi-stem, timber staked	4 x Transplant	wire rootballed
Ls	Liquidambar styraciflua	American Sweetgum	**1**	specimen, from extra wide spacing	30-35cm	5m	Semi-mature, with 2.2m clear stem, underground guyed	4 x Transplant	wire rootballed
Pm	Prunus maackii 'Amber Beauty'	Manchurian Cherry	**6**	Multistem specimen, from extra wide spacing	-	3-3.5m	Multi-stem, timber staked	4 x Transplant	wire rootballed
Bu'J'	Betula utilis var. Jacquemontii	Himalayan Birch	**7**	specimen, from extra wide spacing	25-30cm	4-4.5m	Semi-mature, with 2.2m clear stem, underground guyed	4 x Transplant	wire rootballed

TREE IMAGES


Amelanchier lamarckii


Osmanthus aquifolium


Liquidambar styraciflua


Pinus nigra 'Austriaca'


Quercus Ilex


Prunus maackii 'Amber Beauty'


Betula pendula var. Jacquemontii

© THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY FROM THE OWNER.

NOTES:
1. Do not scale from this drawing.
2. Always work to noted dimensions.
3. All dimensions are in millimetres unless otherwise stated.
4. All setting out, levels and dimensions to be agreed on site.
5. The dimensions of all materials must be checked on site before being laid out.
6. This drawing must be read with the relevant specification clauses and detail drawings.
7. Order of construction and setting out to be agreed on site.

KEY

BOUNDARY KEY

Red Line Planning Boundary

Phase 1 Boundary

Slot Site Boundary

SOFTWORKS

Trees - Proposed
Refer to schedule for details.

Shrub and Herbaceous planting areas
Refer to schedule for details.

Hedges
Refer to planting plan / schedule for details.

Stratacell Tree Pit System
Refer to drawing HSS-PLA-XX-XX-DR-L-6000 for details.

Refer to drawing VIA-PLA-XX-XX-DR-L-2003/2004 for planting plan / schedule.

Refer to NBS clauses Q28 / Q31.

REVISION NOTES

1. Southern planter omitted.
2. Trees to the south of building adjusted to sit over viaduct pillars.
3. Climbing plants omitted from hoarding line to slot site.

Revision	Date	Description	Drawn	Apprvd.
D4-C02	31.01.24	For construction	TF	KR
D4-C01	04.02.22	For construction	TF	KR
S1-P09	04.11.21	Stage 4+	TF	KR
S2-P09	15.10.21	Tree schedule updated	TF	KR
S2-P08	25.08.21	Planning	TF	KR
S2-P07	17.06.21	For information	TF	KR
S1-P06	10.06.21	Draft Tender	TF	KR
P04	05.11.20	Planning Issue	TF	KR
P03	07.09.20	Design Development	CS	KR
P02	07.09.20	Stage 3 Issue	CS	KR
P01	18.06.20	Planning Issue	TF	KR

Planit I.E. Limited
E: info@planit-ie.com **W:** planit-ie.com
MANCHESTER
2 Back Grafton St , Altrincham, WA14 1DY
T: 0161 928 9281
LONDON
Unit 6 Waterside, 44-48 Wharf Road, London, N1 7UX
T: 0207 253 5678
LIVERPOOL
Tempest 5.3, 12 Tithebarn Street, Liverpool, L2 2DT
T: 0151 363 1230

Client ASK

Project Viadux, Greater Bridgewater Street Stair and Lift

Drg Title Softworks - Phase 1

Created on	Created by	Approved by
18-06-20	TF	KR

Scale	Size	Workstage
1:200	A1	Stage 5

Drg No.	Suitability	Revision
VIA-PLA-XX-XX-DR-L-2000	D4	C01

© Planit I.E. Limited