

LARGE STREET TREE SPECIES	GRADE	GIRTH	HEIGHT	SPECIFICATION	NUMBER OF PLANTS
Prunus 'Amanogawa'	HEAVY STANDARD	12-14CM			10
Prunus avium 'Plena'	HEAVY STANDARD	12-14CM	450/650	2.1 CLEAR STEM MIN 5 BREAKS	24
Prunus sargentii rancho	HEAVY STANDARD	12-14CM			15
Prunus 'Sunset Boulevard'	HEAVY STANDARD	12-14CM	450/650	2.1 CLEAR STEM MIN 5 BREAKS	9
Prunus 'Tai Haku'	HEAVY STANDARD	12-14CM	450/650	2.1 CLEAR STEM MIN 5 BREAKS	6
Pyrus calleryana 'Chanticleer'	HEAVY STANDARD	12-14CM	450/650	2.1 CLEAR STEM MIN 5 BREAKS	19
Liquidambar styraciflua	HEAVY STANDARD	12-14CM			5
Salix chrysocoma	HEAVY STANDARD	12-14CM			1
Sorbus aria 'Lutescens'	HEAVY STANDARD	12-14CM	450/650	2.1 CLEAR STEM MIN 5 BREAKS	14
Sorbus aucuparia 'Joseph Rock'	HEAVY STANDARD	12-14CM	450/650	2.1 CLEAR STEM MIN 5 BREAKS	9
SMALL STREET/GARDEN TREES SPECIES	**GRADE**	**GIRTH**	**HEIGHT**	**SPECIFICATION**	**NUMBER OF PLANTS**
Amelanchier canadensis	HEAVY STANDARD	12-14CM			2
Amelanchier lamarckii (multi stem)	HEAVY STANDARD	12-14CM	1.75-2.0m high	MIN 5 BREAKS	3
Amelanchier lamarckii (standard)	HEAVY STANDARD	12-14CM	1.75-2.0m high	1.5M CLEAR STEM MIN 5 BREAKS	3
Betula doorenbos	HEAVY STANDARD	12-14CM			1
Cercis canadensis 'Forest Pansy'	HEAVY STANDARD	12-14CM	1.2 - 1.5m high	1.5M CLEAR STEM MIN 5 BREAKS	3
Magnolia x soulangeana	HEAVY STANDARD	12-14CM	1.75-2.0m high	1.5M CLEAR STEM MIN 5 BREAKS	2
NATIVE TREE SPECIES	**GRADE**	**GIRTH**	**HEIGHT**	**SPECIFICATION**	
Acer campestre	HEAVY STANDARD	12-14CM	300/350	1.5M CLEAR STEM MIN 5 BREAKS	1
Betula pendula	HEAVY STANDARD	12-14CM	300/350	1.5M CLEAR STEM MIN 5 BREAKS	4
ORNAMENTAL SHRUBS					
SPECIES	**SIZE**	**ROOT CONDITION**			
Aucuba crotonifolia	3L POT	CONTAINERISED			285
Carex 'Ice Dance'	3L POT	CONTAINERISED			141
Ceanothus repens	3L POT	CONTAINERISED			421
Choisya 'Aztec Gold'	3L POT	CONTAINERISED			690
Cistus Corbariensis	3L POT	CONTAINERISED			279
Echinacea purpurea	3L POT	CONTAINERISED			6
Euonymus fortunei 'Emerald N Gold'	3L POT	CONTAINERISED			323
Geranium 'Johnson Blue'	3L POT	CONTAINERISED			21
Pieris japonica 'Little Heath'	3L POT	CONTAINERISED			727
Potentilla 'Kath Dykes'	3L POT	CONTAINERISED			319
Rudbeckia 'Goldsturm'	3L POT	CONTAINERISED			76
Skimmia japonica	3L POT	CONTAINERISED			261
Viburnum davidii	3L POT	CONTAINERISED			1312
Weigela 'Foliis Purpureis'	3L POT	CONTAINERISED			560
ORNAMENTAL HEDGE SPECIES	**SIZE**	**ROOT CONDITION**			
Fagus sylvatica	1+2 TRANSPLAT	BARE ROOT			1060
Pittosporum 'Irene Paterson'	3L POT	CONTAINERISED			1382
Buxus Sempervirens	3L POT	CONTAINERISED			629

SR NATIVE HEDGE MIX					
Total Length On Site	**Nursery Grade**	**Height**	**Total No. Plants**		
290			**1450**	**% Mix**	**No Of Plants**
Major Species					
Crataegus monogyna	Bareroot 1 + 1 Transplant	1.2-1.5m		60	870
Prunus spinosa	Bareroot 1 + 1 Transplant	1.2-1.5m		20	290
Corylus avellana	Bareroot 1 + 1 Transplant	1.2-1.5m		7.5	109
Ilex aquifolium	3L Pot	0.6-0.8m		7.5	109
Minor Species					
Prunus padus	Bareroot 1 + 1 Transplant	1.2-1.5m		2.5	36
Rosa canina	Bareroot 1 + 1 Transplant	1.2-1.5m		2.5	36

Planted at 5 plants/m in double staggered row.

SCRUB PLANTING MIX					
TOTAL AREA	**Nursery Grade**	**Height**	**TOTAL**		
270			**270**		
Planted on a 1m Grid Staggered			**%MIX**		**NUMBERS**
Alnus glutinosa	Bareroot 1 + 2 Transplant	1.2-1.5m	10	MIN 3 BREAKS, BUSHY	**27**
Ilex aquifolium	2L Pot	40/60cm	20	MIN 5 BREAKS, BUSHY	**54**
Viburnum opulus	Bareroot 1 + 2 Transplant	1.2-1.5m	15	MIN 5 BREAKS, BUSHY	**41**
Prunus spinosa	Bareroot 1 + 2 Transplant	1.2-1.5m	15	MIN 3 BREAKS, BUSHY	**41**
Corylus avellana	Bareroot 1 + 2 Transplant	1.2-1.5m	10	MIN 5 BREAKS, BUSHY	**27**
Crategus monogyna	Bareroot 1 + 2 Transplant	1.2-1.5m	25	MIN 5 BREAKS, BUSHY	**68**
Prunus avium	12-14cm Girth Heavy Standard	350/400cm	5	Standard 1.5 M Clear Stem	**14**

Squareyard

Landscape Architecture - Urban Design - Masterplanning

Email - studio@yd2.co.uk
Web - www.yd2.co.uk
Tel - 07514 281 452

Address:
Suite 10 - Hardman Business Centre,
New Hall Hey Road,
Rossendale

GENERAL NOTES:

1. DIMENSIONS GOVERN
2. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS NOTED OTHERWISE ON THE DRAWINGS
3. ALL DIMENSIONS SHALL BE VERIFIED ON SITE PRIOR TO ANY CONSTRUCTION
4. YD2 SHALL BE NOTIFIED OF ANY DISCREPANCIES

DRAWING NOTES:

REV	DESCRIPTION	DRAWN	CHECKED	DATE
T1	ISSUED TO DISCHARGE CONDITION 30	MG	AV	15/03/2024
T2	WILDFLOWER MIX UPDATED - PATHS ADDED	MG	AV	13/06/2024

PROJECT TITLE
BENNETT STREET

DRAWING TITLE
COMPOSITE PLANT SCHEDULE

SCALE @ A1
1:1000

DATE
MAR 2024

PROJECT NUMBER
YD2_22_13

DRAWING No.
YD2_CD_LP010

REVISION
T2