

Indicative - fabric not on measured survey
Rainwater Pipe

1. Existing full height ducts to be carefully removed.
2. Plastic and lead rainwater pipes to be replaced with cast iron.
3. In-line slate vents at circa 1500-1750mm centres.
4. Wider lead lined gutter - pending access.
5. Existing RWP locations to be confirmed on site once safe access made.

**77-79 Mosley St,
Manchester**

scheme	1995
drwg no.	P(152)
revision	A

scale	I:100@A3
date first drawn	
drawn	HW

www.ateliermb.co.uk
t 0161 236 0051
e architect@ateliermb.co.uk