The implementation of no waiting double yellow lines in location shown on Wembley Road to be promoted through the Traffic Regulation Order making process, with any subsequent Traffic Regulation Order (which may differ to that shown) implemented as part of the S278 process

No waiting double yellow lines to be provided on site access road over identified lengths

Provision of H Bar markings to be investigated as part of the detailed design process

As agreed with TfGM, existing bus stop to be relocated approximately 55 metres to the north and take the form of a 160mm upstand with flag pole

Green dotted line shows 2.4 x 52 metre visibility splays at proposed access based on 34mph design speed

The implementation of no waiting double yellow lines in location shown on Wembley Road to be promoted through the Traffic Regulation Order making process, with any subsequent Traffic Regulation Order (which may differ to that shown) implemented as part of the S278 process

Proposed new dropped crossing point with tactile paving and bollards to both sides to prevent parking on the footway

Rev.	Date	Revision Details	Drawn	Check	App.
B	08.03.24	Amended bus stop location	SFB	SFB	PRC
A	29.02.24	Update to notes	SFB	SFB	PRC

Jactin House
24 Hood Street
Ancoats
Manchester
M4 6WX
T: 0161 327 1931
E: info@cbotransport.co.uk
W: www.cbotransport.co.uk

Client	Kellen Homes and GMYF
Project	Land at Mount Road, Gorton, Manchester
Drawing Title	Access Drawing: Wembley Road

Drawn	Checked	Approved
SFB	PRC	PRC
Scale / Size		**Date**
1:500 @ A3		15.02.24
Status	**Drg No**	**Rev**
Information	CBO-0767-004	B