

Our ref: 29399 work spec and plan BLC
Date: 08.03.2024

Client: Gaynor Davis
Address: Boat Lane Court
Brett Street
Northenden
M22 4EZ

Tel No: 0161 945 7064
Email:

ARBORICULTURAL SERVICES TREEWORX LTD

Haresteads Farm
Lyme Park
Disley
Cheshire
SK12 2NT
Office Tel: 01625 850320
0161 456 0989
Fax: 01625 879401
e-mail: rk@treeworkers.com

Work Specification and Plan.

Tree no	No./ Qty	Species	Location	Action 1	Comments
G1	X	Mix	Boundary	ROH DWD	Reduce the car park overhang back to previously cut to points, remove hanging branches and deadwood over the car park and path (from Boat Lane Court trees only)
G2	X	Mix	Boat Lane boundary	RCP	Sycamore, 2 cherry and birch prune back to maintain a 5m clearance from the building (minor reduction)
T3	1	Copper beech	Rear	RCP	Remove the low secondary branches extending furthest towards the building
T4	1	Prunus	Rear	RCP	Minor reduction back from the building
G5	X	Mix	Rear	RCP	A lime, 2 cherry and a birch, trim where needed to maintain previously cut to building clearance distance
T6	1	Lime	Rear	POL	A mature tree pollarded in the past with many inclusions, rather than wait for a leader to split out, I have suggested pollarding the tree, down to say 6m, so 2m above the previous boling, 1m stubs can be left.
T7	1	Cherry	Front entrance	RCP	Minor pruning back from the building

All debris arising from our operation will be removed unless otherwise stated.

Conservation Area.

The manager is subject to various resident and neighbour complaints and concerns about the sites trees, the proposed work is (apart from T6) routine pruning to maintain the trees distance from the buildings and parked cars, secondary branches only and cutting back to points we have taken them back to previously. G5 and T6 have the added input of the neighbours in the new properties, minor pruning of G5 is suggested to appease them without spoiling the tree's appearance.

T6 a lime, has been topped 20 or 30 years ago at around 4m in height, easily visible on Streetview the multiple competing leaders all sprout from inclusions, there is an inevitability about this tree's collapse that can be delayed 'indefinitely' by regular pollarding, it should assuage neighbours and residents as well, the height cut to needs to preserve some privacy between properties, the anticipated regrowth will enhance this.

