

KEY					
	Existing tree or vegetation to be retained & protected in line with Arboricultural proposals	 Tarmac/rubber crumbs surfacing eg. Trafficflex kerbs porous paving, 35mm deep wearing course. Clown colour, laid on 100mm deep MOT Type 1 (Type 1X) sub base with PCC pin kerb as edge restraint	 Cyclone shelter eg SFD Herensay 4m Shelter Ref: SFD114, powder coated finish RAL 9007 with 3m hoop Budget Scooter Rack galvannead finish & fixing kit Ref: SFD8999S feed to weaving course		
	Existing tree or vegetation to be removed in line with Arboricultural proposals	 Bark mulch surfacing 50mm deep with filled timber edge restraint	 Cycle Shelter eg SFD Herensay 4m Shelter Ref: SFD114, powder coated finish RAL 9007 with 3m hoop Budget Scooter Rack galvannead finish & fixing kit Ref: SFD4205 feed to weaving course		
	Native Tree Species Semi mature Tree, set in soft landscaping with timber stake support underground gey system	 Hoggin/sealed surface Self binding gravel surface, golden colour with PCC pin kerb flush as edge restraint	 Raised planting bed 400-600mm high timber sleeper bed filled with imported topsoil, grave drainage layer & waterproof membrane		
	Small Ornamental Tree Mullein*/ Feathered tree set in soft landscaping with timber stake support underground gey system	 Block paving eg Tobiemore Antoro concrete block, 220x55x50mm, Carbon/Patinum/Steel mix (60%/30%/30%) laid in a stretcher bond pattern with PCC pin kerb flush as edge restraint	 Bench eg Second Lute Products Wastes Ltd Recycled Plastic Edge Bench, 180L x 450H x 430W, Black/Brown colour finish, surface mounted fixings to suppliers recommendations		
	Grass Turf or grass seed laid on minimum 150mm imported topsoil (to be hard wearing amenity quality)	 Non permeable Tarmac - Pedestrian To engineers specifications with PCC pin kerb flush as edge restraint	 Bench eg Second Lute Products Wastes Ltd Recycled Plastic Curved Edge Bench, 180L x 450H x 430W, Black/Brown colour finish, surface mounted fixings to suppliers recommendations		
	Sports Pitch Turf laid on minimum 150mm imported topsoil, line painting applied for football in accordance with Sport England guidance <i>"Natural Turf for Sport, 2011"</i>	 Permeable Tarmac - Pedestrian To engineers specifications with PCC pin kerb flush as edge restraint	 Litter Bin eg Brimmo Buton Litter Bin, Ref: BX4G0 2563, powder coated finish Sky Blue RAL 5015 with bolt down fittings		
	Ornamental shrub planting A mix of evergreen/deciduous grasses/perennials & shrubs to provide habitat for birds and insects and/or striking year-round display.Planted in 450mm imperial pots for minimum ornamental bark chipping dressing	 Non permeable Tarmac - Vehicular To engineers specifications with PCC kerb, 100mm upstand & drop kerbs where necessary	 Willow Tunnel with self binding gravel surface & pin kerb edge		
	Wildflower mix 1 Low maintenance indigenous grasses & wildflowers mix, biannually mowed to maintain species diversity, sown into existing soils	 MUGA Sports pitch surfacing Open textured porous macadam, to conform to Sport England guidance note: "Artificial Surfaces for Outdoor Sport".	 Log piles & seating constructed from felled timbers		
	Wildflower mix 2 Low maintenance indigenous grasses & wildflowers mix, biannually mowed to maintain species diversity, sown into existing soils	 Permeable, aggregate / dynamic ECB approved system finish & tuffed carpet to battling zone on.	 Existing levels retained		
	Native hedge species mix Whips/transplants/container grown plants planted in triple staggered rows @450cm centres with suitable sapling guards placed in	 Artificial grass surface with permeable sub base & timber edge restraint	 Proposed level		



-

saville LANDSCAPE DESIGN
Hatherlow House Remley Stockport Cheshire SK6 3DY

T : 0161 400 7333		E : info@sevillelandscape.co.uk	
M : 07502 260793		W : www.sevillelandscape.co.uk	
CLIENT			
Conlon Construction Ltd			
PROJECT TITLE			
Olive Primary School			
DRAWING TITLE			
Landscape General Arrangements			
STATUS			
CONSTRUCTION			
SCALE	SHEET SIZE	DRAWN	CHECKED
1:200	A0	KAS	=
			DATE
			Aug23
PROJECT NO.		DRAWING NO.	REV.
406		02	E