


Manhole Number	Cover Level	Connections	Pipe				Manhole Size	Types	
Coordinates	Depth To Soffit		Code		Inverts	Diams		Manhole Type & Features	Cover Type, Size & Opening Size
S100	97.340		OF RG	TANK ROAD GULLY	96.20 95.90	225 150	1800	Shallow Manhole With Double Steps and Benching	750x600 Eccentric Opening
E. 385956.651	1.290							Box Cut Out As Per UU Detail	600x600 Eccentric
N. 404164.236			0	S 1.000	95.45	600		STND/19/004	D400 Cover

Manhole Number	Cover Level	Connections	Pipe			Manhole Size	Types	
Coordinates	Depth To Soffit		Code	Inverts	Diams		Manhole Type & Features	Cover Type, Size & Opening Size
S101	97.760		1 S 1.000 DO PRIV RG ROAD GULLY	95.40 95.85 95.85 95.85	600 150 150 150	1800	Type 4 with Double Steps	750x600 Eccentric Opening
E. 385969.630	1.760							600x600 Eccentric D400 Cover
N. 404161.808			0 S 1.001	95.40	600			

Manhole Number	Cover Level	Connections	Pipe			Manhole Size	Types	
Coordinates	Depth To Soffit		Code	Inverts	Diams		Manhole Type & Features	Cover Type, Size & Opening Size
S102	97.920		1 DO DO	S 1.001 PRIV PRIV	95.32 95.77 95.77	600 150 150	Type 4 with Double Steps	750x600 Eccentric Opening
E. 385990.352	1.970							600x600 Eccentric D400 Cover
N. 404158.044			0	S 1.002	95.32	600		



CONSTRUCTION ISSUE

ALL COVER & INVERT LEVEL INFORMATION HAS BEEN TAKEN FROM AVAILABLE TOPOGRAPHICAL SURVEY DATA OR UNITED UTILITIES AND CCTV REPORT. EXISTING PUBLIC WATER SEWERS ARE TO BE ABOVE GROUND PROBED, ROUTED AND INTERNALLY SURVEYED WITH ALL INFORMATION PASSED TO CARLEY DAINES AND PARTNERS FOR REVIEW PRIOR TO COMMENCEMENT ON SITE

NOTES			
0m 1m 2m 1: 20 scale bar SITE LOCATION CHAIN ROAD, BLACKLEY, MANCHESTER. M9 ORD. EASTINGS: 386000; NORTHINGS: 404140.			
1. ALL DRAINAGE WORKS HAVE BEEN DESIGNED AND ARE TO BE CONSTRUCTED IN ACCORDANCE WITH BUILDING REGULATIONS DOCUMENT H A "SEWERS FOR ADOPTION (6TH EDITION) SUPPLEMENT GUIDELINES AND STANDARD DETAILS" 2. ALL CLAY PIPE WORK SHALL BE EXTRA STRENGTH GLASSWARE TO BS EN 295:1991 PART 1 3. ALL PRECAST CONCRETE PIPEWORK SHALL BE TO THE CLASS STATED ON THE DRAWINGS IN ACCORDANCE WITH BS EN 13181:2002. ALL MANHOLES AND CHAMBERS SHALL BE TO BS EN 1917:2002 4. THE CONTRACTOR MAY ELECT TO USE REINFORCED PVC PIPES AS COVERED BY BS 4660:2000 & B.S EN 1460-1. STRUCTURED WALL UPVC PIPES TO COMPLY WITH WS-A-35-01. (BY PRIOR AGREEMENT WITH ADOPTING AUTHORITY) MAX PIPE LENGTH TO BE 3.0M 5. ALL LIES RELATE TO TOPOGRAHICAL SURVEY DATA 6. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER RELEVANT DRAWINGS 7. PLOT DRAINAGE CONNECTIONS TO SEWERS MUST BE 150MM DIAMETER AND UNLESS OTHERWISE STATED LAID TO THE INVERT SHOWN 8. ALL INSPECTION CHAMBERS TO BE 450mm DIAMETER POLYPROPYLENE WITH A MAXIMUM DEPTH OF 1200mm FOR THE STANDARD UNIT & A MAXIMUM DEPTH OF 3000mm WHEN A 250mm REDUCING RING IS USED. 9. ALL PILOT DRAINAGE RUNS TO BE 100mm DIAMETER AT A NOMINAL FALL OF 1:80 UNLESS NOTED OTHERWISE. 10. KIDDING EYES AT START OF EACH DRAINAGE RUN 11. ALLOW FOR 5.0M OF /%20 DRAINAGE CHANNEL PER PROPERTY AT HIGHWAY BOUNDARY. 12. SURFACE WATER FROM PLOT PARKING AREAS MUST NOT DISCHARGE ONTO THE HIGHWAY 13. PILOT DRAINAGE RUNS TO BE KEPT WITHIN THE CURTLAGGE OF THE PLOT THEY SERVE WHEREVER POSSIBLE 14. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ENSURING THAT ANY EXISTING INVERT LEVELS INDICATED ON DRAWINGS ARE CORRECT BEFORE THE WORKS ARE COMMENCED 15. ALL CONNECTIONS TO ADAPTABLE SEWERS SHALL BE MANUFACTURED JUNCTION PIPES. SADDLE CONNECTIONS WILL NOT BE PERMITTED UNLESS SPECIFIED 16. ALL SEWERS FOR ADOPTION WITH GREATER THAN 1.20M COVER IN ROADS OR 0.9M COVER IN FIELDS SHALL HAVE CLASS 5 GRANULAR BED AND SURROUND 17. ANY SEWER WITH LESS THAN 1.2M COVER IN ROADS OR 0.9M COVER IN FIELDS SHALL HAVE A MINIMUM OF 150MM ST4 CONCRETE SURROUND 18. FLEXIBILITY SHALL BE MAINTAINED BY THE PROVISION OF FLEXICELL OR SIMILAR APPROVED JOINT FILLER BREAKS IN THE CONCRETE SURROUND AT EACH PIPE JOINT 19. IT IS THE RESPONSIBILITY FOR THE CONTRACTOR TO CHECK ALL ON SITE EXISTING GROUND LEVELS PRIOR TO COMMENCING AND IF THERE ARE ANY DISCREPANCIES THE CONTRACTOR MUST REPORT TO THE ENGINEER IMMEDIATELY 20. CONTRACTOR TO CONFIRM THE COVERING LEVEL, INVERT LEVEL & MANHOLE SIZE FOR THE EXISTING MANHOLE PRIOR TO CONTRACT START DATE. 21. ALL DRAINAGE SHOWN IN THIS DRAWING IS BASED ON ESTIMATES AND IS ALL SUBJECT TO A FURTHER DETAILED DESIGN STAGE AND IS SUBJECT TO CHANGE.			
B	25/05/22	ISSUED FOR CONSTRUCTION.	
A	06/05/22	COVER SIZES REVISED FOLLOWING UU ENGINEERS COMMENTS.	
-	25/02/22	INITIAL ISSUE FOR S104 APPROVAL	
REV.	DATE	DESCRIPTION	
CLIENT			
GREAT PLACES HOUSING GROUP BOWKER SADLER ARCHITECTURE			
Carley Daines and Partners Limited Consulting Civil and Structural Engineers			
11 Bridgewater Road Walkden Worsley Manchester M28 3JE Tel 0161 799 2720 Fax 0161 790 3474 E-mail email@carleypartners.co.uk			
TITLE			
CHAIN ROAD BLACKLEY, MANCHESTER			
SECTION 104 DRAWINGS MANHOLES SCHEDULES AND FLOW CONTROL DETAIL			
Drawn	AM	Checked	DM
Date	25/02/2022	Date	25/02/2022
Scale	1:20		@ A1
Drawing No.	21-B-12851-206		B