



Industrial Estate

THIS DRAWING IS BASED ON PLANNING
LAYOUT PROVIDED BY CLIENT
DRAWING NUMBER:- KH006/A-100
REVISION:- O

PLEASE NOTE THAT THIS DRAWING IS ISSUED FOR INFORMATION/TENDER
PURPOSES ONLY UNTIL TECHNICAL APPROVAL HAS BEEN GRANTED.
ANY WORK UNDERTAKEN PRIOR TO TECHNICAL APPROVAL BEING GRANTED IS AT THE CLIENTS RISK

1. **GENERAL**
1. All adoptable sewers and associated works are to comply fully with 'Design and Construction Guidance'.
2. All highway works are to be adoptable standards and to comply fully with the Local Authority specification.
3. All private drainage works are to comply fully with all part H of the Building Regulations
4. All existing invert levels to be checked by the Contractor at the site of the works and any discrepancies notified to REFA.
5. All levels are based on topographical survey information provided by the relevant.
6. All materials to bear the relevant B.S. Kitemark and comply fully with the specifications.
7. All concrete & concrete products must use Sulphate resistant cement (unless the site investigation report proves that sulphate attack from soils and groundwater will not occur)
8. All opening notices etc. as required under Highways acts etc. are to be obtained prior to commencement of works.
9. All works are to be inspected by LA, NHBC or Relevant Water Authority as applicable.

C.D.M. REGULATIONS 2015

In line with the above regulations we are obliged to inform the Client of their responsibilities under section DGM 15/1, and residual risks that may be involved in the construction of these works. All design work has been carried out with Health and Safety aspects given full consideration. Wherever possible risks have been eliminated from the design, however due to the very nature of this type of work it is not possible to remove all the risks from the design.

We would also respectfully remind the Client of his obligations to take all reasonable steps in ensuring that only competent Contractors who have a valid safety policy are employed.

They should also provide satisfactory responses at all times as to the manner in which they will deal with the elements of risk involved in this type of work and in particular those highlighted by REFA below:-

1. Support / treatment for ALL excavation work.
2. Guarding to edges of excavations to prevent people, materials and vehicles falling into excavation.
3. Guarding of excavations outside working hours to prevent unauthorised access.
4. Undermining to adjacent roads or structures.
5. Confined space operations.
6. Dealing with existing services.
7. Traffic management on existing highways.
8. Procedure to be followed in event of accident or emergency.
9. Method of working where contaminated ground is present on site.
10. Confirmation will be required that all operatives are adequately trained, copies of relevant training certificates to be supplied.

The above list is by no means exhaustive but it does highlight operations that present a risk to contractors and the general public.
For clarification on any item please contact REFA.

D	APARTMENT BLOCK FFL'S UPDATED	Rw	29.11.21
C	REVISED FOLLOWING CLIENTS COMMENTS	Rw	06.11.23
B	TO PLANNING LAYOUT REV D REVISED FOLLOWING MCC COMMENTS	Rw	19.10.23
A	TO PLANNING LAYOUT REV M FFL'S REVISED	Rw	13.07.22
rev	Revision details	RevBy	Date


**worksafe
designer**
www.smasltd.com

as recognised by

SSIP
 SAFETY
 SCHEMES IN
 PROCUREMENT

Drawing Stage		Drawing Status	
☐	Draft	☐	Tender
☒	Issued	☐	Construction
☐		☒	Approval
☐		☐	As Built

Client

**KELLEN HOMES
LIMITED**

Job title

**BENNETT STREET
MANCHESTER**

Drawing title

**FLOOD WATER
EXCEEDANCE PLAN**

REFA

45 Bridgeman Terrace
Wigan, Lancs
WN1 1TT
Tel: - (01942) 826020
Fax: - (01942) 230816

CONSULTING ENGINEERS
CIVIL • STRUCTURAL
GEOTECHNICAL • ENVIRONMENTAL

Date 20.06.23	Scale 1:500	Drawn AS
DRAWING No	22122/101/2	Rev D

(C) This drawing is the property of REFA and should not be copied, used or its contents divulged without prior written consent.