

Crabtree Lane, Clayton

Flood Risk Assessment

Chancerygate Manchester Limited



Quality Control

Prepared by	Checked by	Approved by
Rishad Mannil Senior Engineer	Ismail Laher Director	Ismail Laher Director

Revision History

Revision	Revision date	Details	Authorized	Name	Position
Final	15.12.23	Submission for Full Planning	IL	Ismail Laher	Director

Prepared for:

Chancerygate Manchester Limited

Prepared by:

I&L Consulting Ltd.
29-31 Castle Street, High Wycombe, Buckinghamshire, HP13 6RU

This document has been prepared by I&L Consulting Limited (I&L) for sole use of our client (the “Client”) in accordance with generally accepted consultancy principles, the budget for fees and the terms of reference agreed between I&L and the Client. Any information provided by third parties and referred to herein has not been checked or verified by I&L, unless otherwise expressly stated in the document. No third party may rely upon this document without the prior and express written agreement of I&L.

Table of Contents

1.	Introduction.....	4
2.	Planning Policy and Evidence	6
3.	Site Description	9
4.	Existing Flood Risk.....	11
5.	Flood Risk from the Proposed Development.....	15
6.	Conclusion.....	23
Appendix A Topographical & Utility Survey Plans.....		24
Appendix B United Utility Public Sewer Map.....		25
Appendix C Proposed Development Plan		26
Appendix D Proposed Drainage Strategy Layout		27
Appendix E Hydraulic Calculations		28

Figures

Figure 1: Site Location Plan.....	9
Figure 2: EA Flood Map for Planning (Source: https://flood-map-for-planning.service.gov.uk/)	11
Figure 3: Surface Water Flood Risk Map (Source: https://flood-warning-information.service.gov.uk/).....	12
Figure 4: Groundwater Flood Risk Map (Source: The Manchester City, Salford City and Trafford Councils Level 2 Hybrid)	12
Figure 5: Reservoir Flood Risk Map. (Source: https://flood-warning-information.service.gov.uk/)	13

Tables

Table 1: Collected Data.....	5
Table 2: Summary of flood risk to the Site	14
Table 3: Existing/Proposed Surface Water Runoff reduction.....	15
Table 4: Pollution Mitigation Assessment for the site.....	17
Table 5: Assessment of Suitability of SuDS at the site as the drainage hierarchy	18
Table 6: Management and Maintenance Strategy	21
Table 7: Summary of flood risk to the development.....	22

1. Introduction

I&L Consulting Limited (I&L) was commissioned by the Applicant, Chancerygate Manchester Limited, to undertake a Flood Risk Assessment (FRA) for a proposed industrial development located in a predominantly employment area on Crabtree Lane in Clayton, Manchester. The site lies within the authority of Manchester City Council (MCC).

The relevant national planning guidance is set out by the National Planning Policy Framework (NPPF, updated in 2023). An FRA must assess all sources of flood risk both to the proposed development itself and the potential impact on people and property elsewhere within the catchment.

1.1 Study Aims and Objectives

The overall objective of this study was to carry out an FRA that meets the requirements of the NPPF and MCC flood risk policies. These consider surface water runoff management and the specific needs of the Environment Agency (EA), MCC and United Utilities. The study is required to assess all aspects of flood risk to the proposed development, the potential impacts of the development on people and property elsewhere within the catchment and identify possible mitigation measures to ensure that the development is safe in the event of a flood. To achieve this aim, the following key actions were undertaken:

- Obtain flood data from the EA and MCC.
- Review topographical and flood risk data to identify the existing flood risk posed to the site from all sources.
- Assess the residual flood risk post-development.
- Consider the vulnerability of the users and the development, taking account of the vulnerability classification;
- Assess the safety of the route of access/egress from the site in a flood event;
- Identify suitable mitigation measures to protect the development site against flooding; and
- The production of a conceptual surface water drainage strategy for the proposed development.

1.2 Scope of Works

In order to meet the above objectives, the following scope of work and tasks were undertaken:

- **Task 1: Data Collection.** I&L Consulting collected relevant available information on the nature of the flooding at the site. The Applicant and their consultant team have provided information about the site and proposed development layout and design.
- **Task 2: Identification of Current and Post-Development Flood Risk.** The existing and post-development flood risk posed to the site was assessed from the data that was collected in Task 1. The assessment identifies the flood risk from all potential sources of flooding and includes consideration of the impact of climate change on flood risk.
- **Task 3: Assessment of Site Safety.** I&L Consulting considered whether flood resilience measures needed to be undertaken and the safety of the route of access/egress from the site.

1.3 Data Collected

Table 1 lists the data that has been collected as part of this assessment. Comments on the source and the nature of the data are also provided.

Table 1: Collected Data

Purpose	Data and Source	Comments
Identification of site location	Ordnance Survey Map	Identifies the position of the site and local hydrological features
Identification of flood risk	Environment Agency Flood Map	Risk of flood from tidal and fluvial sources
	Topographical Survey	Existing site levels and topography
	Development details (drawings for existing site and proposed development)	Information on the layout of the proposed development
	Strategic Flood Risk Assessment (SFRA)	Reports that identify existing flood risk information within the area and considerations for development.
Identification of the existing drainage network	Sitewide Drainage Plan	Asset plans and drainage drawings identify public and private sewers nearest to the site.
Identification of ground conditions	British Geological Society (BGS)	Identifies the type of aquifer, groundwater level, permeability and geotechnical information
	BH Logs and site investigation reports	

2. Planning Policy and Evidence

2.1 National Planning Policy Framework (2023)

The NPPF sets out what needs to be taken into account by developers to assess whether a proposed development is likely to be at risk of flooding or has the potential to increase flood risk elsewhere. Within the recently published NPPF (2023), the principles relating to flood risk management remain mostly unchanged from the 2021 version.

The overall objective of the NPPF is to steer development towards areas of lowest flood risk. NPPF policy aims to ensure flood risks have been taken into account and appropriate measures put in place to ensure that:

- The development is safe;
- Where possible, the flood risk overall is reduced;
- Increased flood risk does not occur elsewhere; and
- Appropriate mitigation measures are employed to deal with these effects and risks.

Paragraph 167 and footnote 55 of the NPPF outlines that a site-specific flood risk assessment is required for proposals of 1 hectare or greater in Flood Zone 1; all proposals for new development (including minor development and change of use) in Flood Zones 2 and 3, or in an area within Flood Zone 1 which has critical drainage problems (as notified to the local planning authority by the Environment Agency); and where proposed development or a change of use to a more vulnerable class may be subject to other sources of flooding.

The EA Flood Map shows the site to be located within Flood Zone 1 and less than 1 ha.

The NPPF considers the vulnerability of different forms of development to flooding; and classifies the proposed development as 'Less Vulnerable'.

2.2 Manchester City Council - Core Strategy 2012-2027

The proposed development is not subject to any specific designations according to the Development Plan.

FLOOD RISK POLICY EN14

Policy EN 14

Flood Risk

- In line with the risk-based sequential approach contained within PPS25, development should be directed away from sites at the greatest risk of flooding, and towards sites with little or no risk of flooding; this should take account of all sources of flooding identified in the Manchester-Salford-Trafford Strategic Flood Risk Assessment (SFRA).
- In addition to the requirements for site-specific Flood Risk Assessments (FRAs) set out in PPS25, an appropriate FRA will also be required for all development proposals, including changes of use, on sites greater than 0.5ha within Critical Drainage Areas (CDAs) and Canal Hazard Zones identified in the SFRA.
- All new development should minimise surface water run-off, including through Sustainable Drainage Systems (SUDS) and the appropriate use of Green Infrastructure. Developers should have regard to the surface water run-off rates in the SFRA User Guide. In CDAs, evidence to justify the surface water run-off approach / rates will be required.
- The City of Manchester contains many sections of rivers which are culverted or 'hidden'; where these are indicated in the SFRA beneath the proposed development site, further investigation will be required and the development proposal should take this into account; where feasible and appropriate development should seek to open up culverted/hidden rivers to reduce the associated flood risk and danger of collapse, taking advantage of opportunities to enhance biodiversity and Green Infrastructure.

WATER QUALITY POLICY EN17

Policy EN 17

Water Quality

With reference to the Manchester-Salford-Trafford SFRA and other relevant documents:

- Development should avoid any adverse impact on water quality, including during the construction phase, and wherever possible should seek to enhance water quality, both chemical and ecological;
- Development should minimise surface water run-off from development and associated roads, and maximise the use of appropriate sustainable drainage systems, to minimise groundwater contamination, and to avoid pollutants reaching watercourses;
- Development close to a watercourse should also ensure that waste or litter cannot enter the watercourse from the site;
- Development should, where feasible and appropriate, seek to open up any culverted or hidden watercourse beneath the site to improve the ecological status of that watercourse.

2.3 Manchester City, Salford City and Trafford Councils Level 2 Hybrid SFRA: March 2011

A review of this document shows that the proposed site lies outside of any areas identified to be at risk from flooding. The site is located within the 'Conurbation Core' Critical Drainage Area as mapped out by JBA Consulting.

2.4 Manchester City Council Local Flood Risk Management Strategy: Adopted March 2014

A review of the maps contained within this document shows that the proposed site lies outside of any areas identified to be at risk from surface water flood, any recorded flooding incidents and in an area low risk from groundwater flooding.

2.5 Manchester City Council Preliminary Flood Risk Assessment: May 2011


A review of this document shows that the proposed site lies outside of any areas identified to be at risk from surface water flood, any recorded flooding incidents and in an area low risk from groundwater flooding.

2.6 Climate Change

Predicted future change in peak river flows caused by climate change are provided by the EA within their online guidance¹. The UK has been split into a series of regionalised 'River Basin Districts'. These River Basin Districts are further split into Management Catchments, for which a range of climate change projections have been applied.

The Proposed Development falls within the Irwell Management Catchment. The extract below identifies the relevant peak rainfall allowances from this Management Catchment.

¹ Environment Agency, Flood risk assessments: climate change allowances: <https://www.gov.uk/guidance/flood-risk-assessments-climate-change-allowances#table-1>



When determining the appropriate allowance for use in an FRA the anticipated lifespan of the development should be considered. This Proposed Development is expected to have a design life which goes beyond 2060.

The EA guidance is to use the central allowance for the 2070s epoch (2061 to 2125), which gives values of 30% for the 3.3% (30yr) and 30% for the 1% (100yr) rainfall events. The value of **45%** has been used in the surface water calculations appended to this report as required by MCC.

3. Site Description

The proposed development site which is the subject of this Flood Risk Assessment (FRA) is situated in a small industrial estate off the A662 Ashton New Road, Clayton situated east of central Manchester. The development will be accessed off Crabtree Lane which runs along the western boundary of the site.

The proposed development will consist of two blocks of terraced industrial units and a single industrial unit with associated parking and HGV turning areas. The total development site is generally flat with a total site area of 0.9Ha.

The existing site is brownfield with a large warehouse building occupying most of the site and associated external areas of parking and storage to the front and rear of the site.

An underground utility scan of the site has identified separate foul and surface water drainage networks with drainage gully's draining external areas of the site. The survey also identified a combined sewer located in Crabtree Lane, see **Appendix A**.

The United Utilities asset map shows a combined sewer located in Crabtree Lane to the west of the site with a length of combined sewer entering the site, see **Appendix B**.

The proposal would be to drain the developed Sites surface water runoff separately from the foul by gravity and discharge at a restricted rate using flow control to the existing combined public sewer network, see **Appendix D**.

The site location plan is shown in Figure 1 below.



Figure 1: Site Location Plan

3.1 Topography and Hydrological Setting

Environment Agency (EA) river mapping shows that the nearest 'main river' is the River Medlock which lies approximately 1.1km to the north of the site. The Ashton Canal lies approximately 50m to the south of the site.

The topographic survey (**Appendix A**) indicates that the site levels generally lie between 84.90 and 83.60 m AOD with the floor level of the existing building at 84.65m AOD.

3.2 Geology and Hydrogeology

A Phase I & II Ground Investigation Report dated July 2023 has been completed by TRC. Results from the site-specific intrusive investigations can be summarised as follows:

Stratum	From		To		Thickness (m)
	m bgl	m aOD ¹	m bgl	m aOD ¹	
Made Ground	0.00	84.00	2.00 - 4.20	82.00 – 79.80	2.00 – 4.20
Till	2.00 – 4.20	82.00 – 79.80	>15.45	<68.55	>13.25

Ground conditions

The site is generally covered in Asphalt and concrete over made ground of 4.2m thick. The Made Ground is predominantly granular and comprises either dark grey / black silty gravelly sand or grey very sandy gravel. Below this Made Ground there is Superficial deposits of Till. The base was not confirmed but a maximum depth of 15.45m bgl was recorded. The Till predominately comprises soft to very stiff brown sandy slightly gravelly clay or toward the west boundary loose to very dense brown silty sand or loose to very dense brown silty sandy gravel.

Hydrogeology

Groundwater was encountered 4m bgl in the made Ground and 15.30m bgl within the Till. Subsequent resting levels were recorded between 2.2m bgl and 6.48m bgl.

The nearest surface water feature is the Ashton Canal approximately 50m to the south of the site.

Till is classified as a Secondary Undifferentiated Aquifer. The underlying bedrock is classified as a Secondary (B) Aquifer.

The site is not located within a Source Protection Zone (SPZ).

4. Existing Flood Risk

This section of the report identifies the existing risks from the different forms of flooding identified in NPPF.

4.1 Fluvial & Tidal Flooding

The EA has produced Flood Zone maps for much of England and Wales. The current displayed map is reproduced as Figure 2 below and shows the site to lie in Flood Zone 1 (low risk).




Figure 2: EA Flood Map for Planning (Source: <https://flood-map-for-planning.service.gov.uk/>)

On the coast storm surges and high tides can threaten low lying coastal areas and can be sometimes large and rapid enough to overtop defence works, causing significantly more damage than river flooding. Tidal flooding is not considered a risk to the site due to the inland location of the development.

Therefore, flood risk from fluvial and tidal sources to the site is considered to be low.

4.2 Surface Water Flooding

Surface water flooding occurs when rainfall is unable to infiltrate into the ground and/or inundates substandard engineered drainage networks and accumulates on the surface. This flooding mechanism can occur almost anywhere but is likely to be of particular concern in any topographical low spot, or where the pathway for runoff is restricted by terrain or man-made obstructions.

The risk of flooding from surface water is presented in the GOV.UK online map at a strategic scale. It can be seen from the surface water flood map in Figure 3 that the site is shown to have an isolated area to the east at low risk of flooding. On review of the surveys (**Appendix A**) this is due to an un-drained low-lying area within the site.




Figure 3: Surface Water Flood Risk Map (Source: <https://flood-warning-information.service.gov.uk>)

The surface water from the proposed development will provide a betterment to the existing case by capturing all surface water runoff from roofs and external hardstanding. Peak flows shall also be reduced thereby eliminating this surface water flooding. The site will therefore be at a low risk from surface water flooding.

4.3 Groundwater Flooding

The Manchester City, Salford City and Trafford Councils Level 2 Hybrid SFRA includes a groundwater vulnerability map. The site is shown to be in an area outside of Groundwater flood risk.




Figure 4: Groundwater Flood Risk Map (Source: The Manchester City, Salford City and Trafford Councils Level 2 Hybrid)

FFLs will also be set at least 150mm above existing ground levels. We would therefore expect the risk from groundwater flooding at this site to be low.

4.4 Sewer Flooding

A sewer flood is often caused by surface water drains discharging into the combined sewer systems. Sewer capacity is exceeded in large rainfall events causing the backing up of floodwaters within properties or discharging through manholes. Most adopted surface water drainage networks are designed to the criteria set out in Sewers for Adoption. One of the design parameters is that sewer systems be designed such that no flooding of any part of the site occurs in a 1 in 30-year rainfall event. By definition a 1 in 100-year event would exceed the capacity of the surrounding sewer network as well as any proposed drainage.

To ensure that sewer and surface water flooding is not exacerbated; surface water must be considered within the design of the site. This ensures that any additional surface water and overland flows are managed correctly, to minimise flood risk to the site and the surrounding area.

The site will have new separate surface and foul water networks up until the final connection into the existing public combined sewer. A non-return/backflow valve shall be placed at the downstream end of the foul network to prevent surcharge of the foul network. Surface water discharge from the site shall also be restricted therefore significantly improving the current situation.

Therefore, the risk of sewer flooding to the site is considered low.

4.5 Artificial Sources of Flooding

The EA Flood Risk from Reservoirs mapping indicates that the site is located outside of an area of potential risk from flooding. There has been no loss of life in the UK from reservoir flooding since 1925.



Figure 5: Reservoir Flood Risk Map. (Source: <https://flood-warning-information.service.gov.uk>)

Therefore, the risk from this type of flooding can be considered low.

4.6 Summary of Existing Flood Risk

The flood risk from fluvial & tidal flooding, surface water flooding, sewer flooding and groundwater is assessed to be low.

The flood risk to the site is summarised in Table 2.

Table 2: Summary of flood risk to the Site

Type of Flooding	Source of Flooding	Existing Flood Risk
Fluvial and Tidal	River Medlock & Ashwater Canal	Low
Surface Water	Runoff from the site and surrounding land	Low
Sewers	Surrounding public drainage systems	Low
Ground Water	Underlying geology	Low
Artificial Sources	Reservoir	Low

5. Flood Risk from the Proposed Development

The proposed development will consist of two blocks of terraced industrial units and a single industrial unit with associated parking and HGV turning areas. The total development site is generally flat with a total site area of 0.9Ha.

The proposed development drawing is included in **Appendix C**.

5.1 Fluvial and Tidal Flooding

The site is located within Flood Zone 1 and at low risk of fluvial flooding. The proposed development work would not have any impact on fluvial or tidal flooding. Therefore, the risk of flooding from fluvial and tidal sources has been assessed to remain low.

5.2 Surface Water Flooding

The existing site is 75% impermeable and the utility scan shows positive drainage points serving the existing site, see **Appendix A**. There is no existing surface water restriction in place for the existing impermeable portion of the site.

The surface water flood maps (Figure 3, above), shows the site is at low risk of localised surface water flooding due to an un-drained low-lying area within the site. The surface water from this development will provide a betterment to the existing case by capturing all surface water runoff from roofs and areas of external hardstanding. Peak flows shall also be reduced thereby eliminating surface water flooding.

5.3 Proposed Drainage Strategy

Discharge to ground. The site consists of Made Ground comprising gravel and sands to depths of 4m over Superficial deposits of Till comprising stiff clay. Due to the thickness of Made Ground and the cohesive nature of the superficial geology the subsoils are not conducive to infiltration.

Discharge to watercourse. The nearest surface water feature is the Ashton Canal approximately 50m to the south of the site. This option is not viable.

Discharge to sewer. A combined public sewer exists within the site and along Crabtree Lane to the west. Current discharge is to the public combined sewer.

Calculations have been undertaken to assess runoff rates for various storm durations for the existing impermeable 7,032m² (0.7ha) site, see **Appendix E**. The proposed new development will be restricted to 50% reduction of the existing site 1yr 30min return period storm, thereby creating a significant betterment on the existing situation.

A comparison is provided in Table 3 below showing the percentage reduction in runoff rate proposed.

Table 3: Existing/Proposed Surface Water Runoff reduction

Storm Event	Existing(l/s)	Proposed(l/s)	Reduction (%)
Surface Water Runoff			
1yr Storm	40.4	20.2	50%
2yr Storm	47.6	20.2	58%
30yr storm	90.9	20.2	78%
100yr Storm	118.6	20.2	83%
100yr Storm + 45%CC	172.0	20.2	88%

As can be seen the proposed controlled runoff will equate to a 83% reduction from the existing scenario for the 100yr storm event. The drainage has been designed to accommodate all storms up to and including the 100yr event, including a 45% allowance for climate change. **Appendix D** shows the proposed drainage strategy, and the **Appendix E** shows the corresponding drainage calculations.

The surface water drainage network for the proposed development is in line with the principles of integrated Construction Industry Research and Information Association (CIRIA) Sustainable Drainage System SuDS and source control methods to convey surface water runoff flows from the site as well as national and local standard.

- The site is a Brownfield site with existing drainage in place and no formal restrictions on discharge rates. The existing site is 75% impermeable.
- The proposal is to limit the discharge from the redeveloped site to 50% reduction of the existing site 1yr 30min return period storm for all return periods, including climate change allowances.
- Appropriate attenuation to be provided onsite;
- The onsite surface water drainage design will follow the principles listed in the Approved Document Part H of the Building Regulations and Sewers for Adoption 7th Edition. The Building Regulations established a hierarchy for surface water disposal which encourages a SuDS approach;
- No surcharge for the 1:1year rainfall event except for the outfall pipe which may surcharge due to restriction.
- Onsite surface water sewers shall be designed to a 1 in 30 year no flooding standard in accordance with BS EN 752: 2017. There will be no flooding of buildings or off-site areas during a 1 in 100-year return period storm event including climate change allowance.
- Any onsite flooding in the 1:100+45% event, will be directed into a safe place or mitigation measures to be provided on site for any flooding over 5m³.

The proposed drainage network and attenuation requirements are modelled using industry standard hydraulic modelling software included in **Appendix E**. The controlled discharge will be made via the existing outfall of the site.

The proposed drainage layout is included in **Appendix D**.

Therefore, the risk of surface water flooding from the proposed development will remain low.

Assessment of Surface Water Management Options

For sustainable management of surface water run-off from a new development, the use of SuDS is recommended. Table 5 provides a comparison of the different kinds of SuDS systems and their suitability for use at the development site.

5.4 Water Quality

Table 26.2 of the CIRIA C753 SuDS Manual identifies that the pollution hazard level associated with the land uses within the Proposed Development as being 'Medium'. On a scale from 0 – 1, 'Commercial Yard & delivery areas' are deemed to have the following pollution hazard indices:

- Total suspended solids = 0.7
- Metals = 0.6
- Hydrocarbons = 0.7

The SuDS Manual confirms that in England and Wales, where the destination of runoff is to a watercourse then surface water indices should be used for the surface water discharge (Table 26.3 of The SuDS Manual).

The proposed surface water drainage strategy discharges to an existing outfall to an overflow ditch/watercourse. Therefore, the use of the surface water indices approach is deemed to be appropriate.

In terms of pollution control the site it is proposed that the commercial yard and delivery areas are to be protected by Class 1 bypass petrol interceptor. The pollution mitigation assessment is summarised in Table 4 below. The pollution removal characteristics of the pollution control features are based on data in CIRIA C753 and data provided by the product manufacturers.


Table 4: Pollution Mitigation Assessment for the site

Type of SuDS component	Total suspended solids (TSS)	Metals	Hydrocarbons
Class 1 Bypass Petrol Interceptor (Kingspan or similar)	0.8*	0.6*	0.8*
Total	0.4	0.6	0.8

*based on SPEL products

The results in Table 4 show that there is a minor residual impact associated with the Total Suspended Solids. However, whilst Pollution Mitigation Index data is not provided in CIRIA C753 for gullies/catch pit manholes, it is anticipated that sumps at the base of the gullies and catch pits will provide a positive improvement that would mitigate the residual impact for the Total Suspended Solids.

Table 5: Assessment of Suitability of SuDS at the site as the drainage hierarchy

SUDS Group	Technique	Image	Description	Advantages	Disadvantages	Suitable for Use at Site
Retention	Balancing Pond		Provides both storm water attenuation and treatment. Run-off from each rain event is detained and treated in the pool. The retention time promotes pollutant removal through sedimentation.	Good removal of pollutants, can be used where groundwater is vulnerable, good community acceptability, high ecological, and amenity benefits.	No reduction in run-off volume, land take may limit use in high density sites.	✗ Not feasible for proposed development
	Sub-surface Storage		Oversized pipes, tank systems and modular geocellular systems that can be used to create a below ground storage structure.	Modular and flexible, dual usage (infiltration/storage, high void ratios), can be installed beneath trafficked and soft landscaped areas.	No water quality treatment.	✓ Sub-surface storage is feasible and recommended.
Wetland	Shallow wetland		Wetlands provide storm water attenuation and treatment. They comprise shallow ponds and marshy areas, covered in aquatic vegetation. Wetlands detain flows for an extended period to allow sediments to settle and to remove contaminants. They can provide significant ecological benefits.	Good pollutant removal and if lined can be used where groundwater is vulnerable. Good community acceptability, ecological and amenity benefits.	Land take is high, requires base flow, little reduction in run-off volume, not suitable for steep sites.	✗ Not feasible for proposed development
	Extended detention wetland					
	Pond wetland					
	Pocket wetland					
	Submerged gravel wetland					
	Wetland channel					
Infiltration	Infiltration trench		Surface water run-off can be discharged directly to ground for infiltration by soakaways, basins, or trenches. A prerequisite is that both groundwater and ground conditions are appropriate to receive the quality and quantity of water generated.	Reduces the volume of run-off, effective at pollutant removal, contributes to groundwater recharge, simple and cost-effective, easy performance observation.	Requires appropriate pre-treatment, basins require a large flat area, offset from foundations.	✗ Subsoils not conducive to infiltration.
	Infiltration basin					
	Soakaway					

SUDS Group	Technique	Image	Description	Advantages	Disadvantages	Suitable for Use at Site
	Porous paving		Block or porous paving allows run-off to infiltrate through to subbase layer. Water can then be infiltrated into ground or conveyed into storage or drainage systems.	Reduces the volume of run-off and if designed for infiltration contributes towards groundwater recharge. Easy to install and retrofit. Simple to manage. If lined can be used where groundwater is sensitive.	Not suitable for heavily trafficked areas or adoptable roads. Requires regular sweeping to prevent clogging with dirt.	✗ Parking areas are at risk of overrun by HGVs and/or are on gradients.
	Permeable paving					
Filtration	Surface sand filter		Structures designed to treat surface water run-off through filtration using a sand bed filter medium. The filters can be designed with or without infiltration. Temporary storage of run-off is achieved through ponding above the filter layer. They are used where particularly high pollutant removal is required.	Flexibility of design, efficient in removing pollutants, suitable for retrofits and in tightly constrained urban locations.	Not for high sediment content, detention times can support algae growth, minimum hydraulic head of 1.2m required, possible odour problems, high capital and maintenance cost.	✗ Not feasible for proposed development
	Sub-surface sand filter					
	Perimeter sand filter					
	Bioretention/filter swale		Vegetated strips of land designed to accept run-off as overland sheet flow between a hard-surfaced area and a receiving system.	Landscaping features, effective in removing pollutants, flexible layout to fit into landscape, suited for highly impervious areas, good retrofit, capability, effective pre-treatment option.	Requires landscaping and management, large land required, not suitable for steep sites; no significant attenuation or reduction of flows.	✗ Not feasible for proposed development
	Filter trench/drain		Shallow excavations filled with rubble or stone that create temporary subsurface storage for filtration of storm water run-off.	Hydraulic benefits achieved with filter trenches, trenches can be incorporated into site landscaping and fit	High clogging potential without effective pre-treatment, limited to small catchments,	✗ Not feasible for the proposed development

SUDS Group	Technique	Image	Description	Advantages	Disadvantages	Suitable for Use at Site
			Receive lateral inflow from an adjacent impermeable surface.	well beside roads and car parks.	high cost of replacing filter material.	
Detention	Detention basin		Surface storage basins that provide flow control through attenuation. Normally dry and in certain situations the land may also function as a recreational facility	Cater for a wide range of rainfall events, can be used where groundwater is vulnerable, potential for dual land use, easy to maintain.	Land take, little reduction in run-off volume, detention depths constrained by levels.	✗ Not feasible for proposed development
	Enhanced dry swale		Swales are linear vegetated drainage features in which surface water can be stored or conveyed. They can be designed to allow infiltration, where appropriate.	Incorporate into landscaping, good removal of pollutants, reduces run-off rates and volumes, low cost.	Not suitable for steep areas, significant land take, not suitable in areas with roadside parking.	✗ Not feasible for proposed development
	Enhanced wet swale					
Conveyance	Conveyance swales		Formal linear drainage features in which surface water can be stored or conveyed. They can be incorporated with water features such as ponds or waterfalls where appropriate.	Negate the need for underground pipework. Can provide some attenuation. Possible reduction in run-off volume via plant uptake and infiltration.	Potential trip/wheel hazard, disable access issues.	✗ Not feasible for proposed development
	Rills					
Source control	Green/brown roof		Multi-layered system that covers the roof of a building with vegetation cover/landscaping over a drainage layer. Designed to intercept and retain precipitation, reducing the volume of run-off and attenuating peak flows.	Mimics greenfield state of building footprint for high density developments, good removal of pollutants, ecological benefits, insulates buildings, sound absorption.	Additional weight, not appropriate for steep roofs, maintenance of roof vegetation.	✗ Not feasible for proposed development

5.4.1 Maintenance of SuDS

The on-site drainage will be managed by the site management company who will be responsible to maintain any on-site services including drainage. The off-site private drainage is managed by a management company managing the business park.

Table 6: Management and Maintenance Strategy

Drainage Feature	Regular Maintenance	Occasional/Remedial Maintenance	Monitoring
Drainage channels/Gullies	- Inspections will include gratings; covers including their locking bolts; sumps and sump buckets; exposed concrete surround and adjacent surfacing. - Check for accumulation of debris and silt and cleaned as necessary - Gratings, frames and all associated locking parts to be checked for damage. - Exposed concrete and adjacent surfacing to be checked for cracking and general damage. - Check condition of inlet and outlet pipes, flow controls, baffles and isolation structures	- Channel/Slot cleaning will be by flushing with water or high-pressure jetting (no boiling water or cleaning agent will be used). All silt buckets and sumps will be cleaned out replaced back into the units ensuring they are correctly fitted. - All channel surfaces and joints will be checked and repaired as necessary. - Repair/rehabilitation of inlets, outlet, as required.	Inspect every 4 months or after large storm.
Manholes/Inspection Chambers	- Check for accumulation of debris and silt and clean as necessary. - Covers and frames to be checked for damage. - Exposed concrete and adjacent surfacing to be checked for cracking and general damage. - Check condition of inlet and outlet pipes, flap valves, baffles etc.	- Clean as necessary. - All manhole and inspection chamber covers and frames to be replaced as necessary. - Repair exposed concrete and surfacing as necessary - Repair/rehabilitation of inlets, outlet, overflows and vents, as required.	Inspect every 6 months or after large storm.
Attenuation Tank	- Check for accumulation of debris and silt and clean as necessary. - Check condition of inlet and outlet pipes and ventilation structures	- Clean as necessary. - Repair/rehabilitation of inlets and outlet, as required.	Inspect every 6 months or after large storm.

5.5 Sewer Flooding

The site will have new separate surface and foul water networks up until the final connection into the existing public combined sewer. A non-return/backflow valve shall be placed at the downstream end of the foul network to prevent surcharge of the foul network. Surface water discharge from the site will also be restricted therefore significantly improving the current situation.

Therefore, the risk of sewer flooding to the site post development work would remain unchanged.

5.6 Groundwater Flooding

The proposed development is likely to be constructed using PAD foundations and unlikely to impact the groundwater below the site.

Therefore, the risk from groundwater flooding will be remain as low.

5.7 Artificial Sources of Flooding

The proposed development work will not have an impact on artificial sources of flood risk.

5.8 Summary of Flood Risk from the Proposed Development

The flood risk to and from the proposed development has been assessed to remain low from all sources.

The flood risk to the development is summarised in Table 7.

Table 7: Summary of flood risk to the development

Type of Flooding	Source of Flooding	Flood Risk	Proposed Mitigation
Fluvial and Tidal	River Medlock & Ashwater Canal	Low	Not required
Surface Water	Runoff from the site and surrounding land	Low	Proposed restriction to discharge rates which has a significant reduction on runoff rates and volumes from the site.
Sewers	Surrounding public combined drainage systems	Low	None
Ground Water	Underlying geology and groundwater levels	Low	Development levels raised.
Artificial Sources	none	Not applicable	

6. Conclusion

The existing flood risk to the development area from all sources has been assessed from a review of all available data. Future climate change has also been considered. Using the proposed development plan, the extent of the flood risk has been determined for the site as well as the effect that the development might have on flood risk elsewhere.

The assessment can be summarised as follows:

- The site is located in Flood Zone 1, low risk.
- The site is at low risk of flooding from all sources.
- The proposed development is classified as 'Less Vulnerable' and suitable for this location.
- The proposed development work would not increase the risk of flooding from any sources.
- The proposed development is outside of any area identified within Preliminary and Strategic FRAs for the City and surrounding areas.
- A drainage strategy is proposed in consideration with the local and national standard and would not increase the flood risk.
- The site is a Brownfield site with existing drainage in place and no formal restrictions on discharge rates. The existing site is 75% impermeable. The proposal is to limit the discharge from the redeveloped site to 50% reduction of the existing site 1yr 30min return period storm for all return periods, including climate change allowances.
- A geotechnical assessment by TRC has shown that due to the thickness of Made Ground and the cohesive nature of the superficial geology encountered during the investigations the subsoils would not be conducive to infiltration.
- In conclusion, the proposed development work will not increase the risk of flooding to the site or surrounding areas in accordance with the provisions of relevant national and local planning policies.



Appendix A Topographical & Utility Survey Plans


UTILITY LINETYPES

Air Line	
British Telecom	
British Telecom Overhead	
CCTV / Cable Television	
Communication Cable	
Drainage - Combined Water	
Drainage - Foul Water	
Drainage - Storm Water	
Drainage - Unknown Water	
Drainage - Trade Effluent Water	
Drainage - Combined Water - Assumed/TFR	
Drainage - Foul Water - Assumed/TFR	
Drainage - Storm Water - Assumed/TFR	
Drainage - Unknown Water - Assumed/TFR	
Drainage - Trade Effluent Water - Assumed/TFR	
Drainage - Approximate Pipe Size/Extents	
Earth Cable	
Empty Duct	
Electric & Comms	


Electric Low Voltage	
Electric High Voltage	
Electric - Unknown Voltage	
Electric Overhead	
Fibre Optic	
Fuel Line	
Gas Line	
Gauge Line	
GPR Line	
Heating Pipes	
Offset Fills	
Oil Pipe	
Rising Main	
Telecom	
Traffic Light Signals	
Trench Scar	
Unknown	
Vapour Recovery	
Vent Line	
Water	

UTILITY SURVEY INFORMATION

Contracted Survey Area	
Depth to Top of Service (m)	0.40d
End of Trace	 EOT
Head of Run	HoR
Weak Signal	WS
Taken From Records	TFR
Off Survey Area	OSA
Back Drop	BD
Silt Level	SL
Above Ground	A/G
Unable to Locate	UTL
Unable to Survey	UTS
Unable to Raise (cover)	UTR
Unable to Trace	UTT
Unable to Survey	
Chamber Extents	

Assumed Route	AR
Assumed Connection	ACP
Sound Connection	S/C
Sonde Stopped	S/S
No Visible Access	NVA
No Visible Exit	NVE
No Visible Pipes	NVP
No Visible Services	NVS
No Depth Indicated	NDI
Base Level	BL
High Level	HL
Top of Pipe / Top of Valve	T.o.P / T.o.V
Landing Level	LL
Rubble Level	RL
Approximate Location	
GPR Anomaly	
Multiple Services Route	

Appendix B United Utility Public Sewer Map




Appendix C Proposed Development Plan



Scale 1:250



SCALE 1:250



KEY

9 Level Access Doors

	Electric Charging Spaces x18 All remaining spaces to be future proofed for 100%
---	--

Grass roof Cycle Shelter for 14 Cycles
Each unit contains 2 internal cycle spaces
(18 Cycles)
OVERALL 32 Cycle space provision

 Existing 2.4m High Metal Palisade Fence

**Proposed 2.4m High Metal Paladin Fence
(Colour black)**

 Pedestrian and Vehicle gates in 2.4m high paladin style (Colour black)

- • • Retractable/drop down bollards 900mm high

Indicative retaining wall position
Where required retaining walls will have knee
clamp guarding to the top to prevent falls.

 Private Means of Access - No works in this area.

58 no. Car parking spaces (inc. 9 accessible)

Schedule of Accommodation Units 1-4

Schedule of Accommodation Unit 5	
1	1.1
2	2.1
3	3.1
4	4.1
5	5.1
6	6.1
7	7.1
8	8.1
9	9.1
10	10.1
11	11.1
12	12.1
13	13.1
14	14.1
15	15.1
16	16.1
17	17.1
18	18.1
19	19.1
20	20.1
21	21.1
22	22.1
23	23.1
24	24.1
25	25.1
26	26.1
27	27.1
28	28.1
29	29.1
30	30.1
31	31.1
32	32.1
33	33.1
34	34.1
35	35.1
36	36.1
37	37.1
38	38.1
39	39.1
40	40.1
41	41.1
42	42.1
43	43.1
44	44.1
45	45.1
46	46.1
47	47.1
48	48.1
49	49.1
50	50.1
51	51.1
52	52.1
53	53.1
54	54.1
55	55.1
56	56.1
57	57.1
58	58.1
59	59.1
60	60.1
61	61.1
62	62.1
63	63.1
64	64.1
65	65.1
66	66.1
67	67.1
68	68.1
69	69.1
70	70.1
71	71.1
72	72.1
73	73.1
74	74.1
75	75.1
76	76.1
77	77.1
78	78.1
79	79.1
80	80.1
81	81.1
82	82.1
83	83.1
84	84.1
85	85.1
86	86.1
87	87.1
88	88.1
89	89.1
90	90.1
91	91.1
92	92.1
93	93.1
94	94.1
95	95.1
96	96.1
97	97.1
98	98.1
99	99.1
100	100.1

Schedule of Accommodation Units 6-9	
Unit 6	Unit 7
Unit 8	Unit 9

Schedule of Accommodation TOTAL	
--	--

P.04	Rear boundary revised to suit features.	JC	JC	15.12.23
------	---	----	----	----------

Former Walkers Site, Crabtree Lane

Information Container LOD:	LOD 100
----------------------------	---------

THIS DRAWING IS TO BE USED FOR THE STATED PURPOSE ONLY AND SHOULD NOT BE USED FOR ANY OTHER



RIBA PoW Stage: 3 - Spatial Coordination

RIBA PoW Stage: 3 - Spatial Coordination

RIBA PoW Stage:	3 - Spatial Coordination
-----------------	--------------------------

Document Suitability: S1
Drawn / Checked: JWC / JC

Date: 02/11/2023
Scale: 1:250 A1

UMC Project Number: 23168

Document Reference: Drawing no: Revision:

Appendix D Proposed Drainage Strategy Layout

STRATEGY

1. THIS DRAWING SHOULD ONLY USED TO SUPPORT A PLANNING APPLICATION AND MAY FORM PART OF A FLOOD RISK ASSESSMENT. IT FORMS AN INTENDED STRATEGY THAT WILL BE DEVELOPED IN MORE DETAIL.
2. DO NOT USE THIS DRAWING FOR DETAILED COST ESTIMATES OR TENDER PURPOSES.

PRE-DEVELOPMENT:
3. THE EXISTING SITE IS PRE-DEVELOPED AND DISCHARGES INTO A PUBLIC COMBINED SEWER VIA 1NO. Ø225mm PIPE.

PROPOSAL:
4. THE NEW DEVELOPMENT SHALL BE RESTRICTED TO 20.2% THIS IS BASED ON 50% REDUCTION OF THE EXISTING M1-30 STORM EVENT.

5. TOTAL ATTENUATION FOR 100Yr+45% CLIMATE CHANGE STORM EVENT STORED BELOW GROUND = 353m³.

HYDRAULIC DESIGN:
6. THE SURFACE WATER NETWORK, FLOW CONTROL AND ATTENUATION HAS BEEN DESIGNED USING MICRODRAINAGE SOFTWARE WITH FSR RAINFALL DATA.

FINAL DRAINAGE CONNECTIONS:
7. DISCHARGE POINTS SHOWN MAY NEED TO BE FURTHER INVESTIGATED IN TERMS OF LOCATING AND INVERT LEVELS.


8. APPROVAL SHALL BE OBTAINED FOR INTENDED DISCHARGE INTO THE PUBLIC SEWER.

MAINTENANCE:
9. THE NETWORK AND ALL ANCILLARY COMPONENTS SHALL RECEIVE REGULAR MAINTENANCE AS OUTLINED IN SEPARATE SCHEDULE.


AREAS:
SITE AREA 0.910 ha
EXISTING IMPERMEABLE AREA 0.703 ha
PROPOSED IMPERMEABLE AREA 0.839 ha

LEGEND

- SITE BOUNDARY (0.91ha)
- EXISTING COMBINED PUBLIC SEWER
- NEW STORM WATER RUN
- NEW FOUL WATER RUN
- PI PETROL INTERCEPTOR
SERVICE YARD AND OTHER VEHICULAR
ACCESSED AREAS TO PASS THROUGH
PETROL INTERCEPTOR BEFORE
DRAINING TO TANK.



P1	12.12.23	PRELIMINARY ISSUE	RM	IL
Rev.	Date	Description	Technician	Reviewer



Project	CRABTREE LANE CLAYTON	DRAINAGE PLANNING STRATEGY
Drawing Set	DRAINAGE	PRELIMINARY
Scale	1:250 @ A1 1:500 @ A3	
Project Number	23-026-I&L	
Drawing Number	D00	
Revision	P1	

Appendix E Hydraulic Calculations

Crabtree Lane, Clayton - Existing Site Runoff Calculation



Date: 11-Dec-23

By: SH

DESIGN PARAMETERS

Total Site Area	9,103 m ²
Roof & Externals	7,032 m ²
Existing Permeable	2,071 m ²
Total Impermeable area	7,032 m²
Runoff Coefficient	95% <i>assuming no loss to depression storage</i>

RAINFALL

In accordance with 'Design and analysis of Urban Storm Drainage – Wallingford Procedure Volume 4 – The Modified Rational Method'.

UK Sustainable Drainage Tool M5-60 =

20 mm

Figure A.1 (vol. 4 Modified Rational Method)

r = 0.42

Figure A.2 (vol. 4 Modified Rational Method)

Storm	Z1	Rainfall (mm)
M5-5	0.39	8
M5-10	0.53	11
M5-15	0.65	13
M5-30	0.8	16
M5-60	1	20
M5-120	1.2	24
M5-240	1.4	28
M5-360	1.6	32
M5-600	1.8	36
M5-1440	2.2	44

Storm	Z2	Rainfall (mm)	Rainfall Intensity (mm/hr)	Qmax (L/s)	Volume (m3)
M1-5	0.62	5	58.0	107.7	32.3
M1-10	0.61	6	38.8	72.0	43.2
M1-15	0.62	8	32.2	59.8	53.8
M1-30	0.68	11	21.8	40.4	72.7
M1-60	0.72	14	14.4	26.7	96.2
M1-120	0.78	19	9.4	17.4	125.1
M1-240	0.78	22	5.5	10.1	145.9
M1-360	0.78	25	4.2	7.7	166.7
M1-600	0.78	28	2.8	5.2	187.6
M1-1440	0.78	34	1.4	2.7	229.3

Storm	Z2	Rainfall (mm)	Rainfall Intensity (mm/hr)	Qmax (L/s)	Volume (m3)
M2-5	0.79	6	73.9	137.2	41.2
M2-10	0.79	8	50.4	93.5	56.1

M2-15	0.80	10	41.4	76.8	69.1
M2-30	0.80	13	25.7	47.6	85.7
M2-60	0.81	16	16.2	30.1	108.2
M2-120	0.82	20	9.8	18.2	131.1
M2-240	0.83	23	5.8	10.7	154.5
M2-360	0.83	27	4.4	8.2	177.9
M2-600	0.84	30	3.0	5.6	201.1
M2-1440	0.84	37	1.5	2.9	248.1

Storm	Z2	Rainfall (mm)	Rainfall Intensity (mm/hr)	Qmax (L/s)	Volume (m3)
M30-5	1.46	11	136.9	254.0	76.2
M30-10	1.49	16	95.0	176.4	105.8
M30-15	1.51	20	78.6	145.9	131.3
M30-30	1.53	24	49.0	90.9	163.5
M30-60	1.54	31	30.9	57.3	206.2
M30-120	1.54	37	18.4	34.2	246.2
M30-240	1.52	43	10.6	19.8	284.6
M30-360	1.50	48	8.0	14.9	321.5
M30-600	1.49	53	5.3	9.9	357.2
M30-1440	1.45	64	2.7	4.9	425.6

Storm	Z2	Rainfall (mm)	Rainfall Intensity (mm/hr)	Qmax (L/s)	Volume (m3)
M100-5	1.86	15	174.3	323.4	97.0
M100-10	1.93	20	122.5	227.3	136.4
M100-15	1.96	25	101.8	188.9	170.0
M100-30	2.00	32	63.9	118.6	213.6
M100-60	2.03	41	40.6	75.3	271.2
M100-120	2.01	48	24.2	44.8	322.9
M100-240	1.99	56	13.9	25.8	371.5
M100-360	1.95	62	10.4	19.3	416.0
M100-600	1.91	69	6.9	12.8	460.3
M100-1440	1.83	80	3.3	6.2	536.7

Storm +25% climate change	Rainfall (mm)	Rainfall Intensity (mm/hr)	Qmax (L/s)	Volume (m3)
M100-5 +45%	21.1	252.7	468.9	140.7
M100-10 +45%	29.6	177.6	329.6	197.8
M100-15 +45%	36.9	147.6	274.0	246.6
M100-30 +45%	46.4	92.7	172.0	309.7
M100-60 +45%	58.9	58.9	109.2	393.3
M100-120 +45%	70.1	35.0	65.0	468.2
M100-240 +45%	80.6	20.2	37.4	538.7
M100-360 +45%	90.3	15.0	27.9	603.2
M100-600 +45%	99.9	10.0	18.5	667.4
M100-1440 +45%	116.5	4.9	9.0	778.3

Summary of Results for 30 year Return Period

Half Drain Time : 68 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	82.308	0.308	0.0	20.0	20.0	90.8	O K
30 min Summer	82.385	0.385	0.0	20.1	20.1	113.4	O K
60 min Summer	82.438	0.438	0.0	20.1	20.1	128.9	O K
120 min Summer	82.463	0.463	0.0	20.1	20.1	136.2	O K
180 min Summer	82.455	0.455	0.0	20.1	20.1	134.1	O K
240 min Summer	82.437	0.437	0.0	20.1	20.1	128.6	O K
360 min Summer	82.389	0.389	0.0	20.1	20.1	114.6	O K
480 min Summer	82.343	0.343	0.0	20.1	20.1	101.1	O K
600 min Summer	82.303	0.303	0.0	20.0	20.0	89.3	O K
720 min Summer	82.270	0.270	0.0	19.7	19.7	79.5	O K
960 min Summer	82.221	0.221	0.0	19.2	19.2	65.1	O K
1440 min Summer	82.177	0.177	0.0	16.2	16.2	52.3	O K
2160 min Summer	82.146	0.146	0.0	12.6	12.6	43.1	O K
2880 min Summer	82.129	0.129	0.0	10.4	10.4	38.0	O K
4320 min Summer	82.108	0.108	0.0	7.8	7.8	31.8	O K
5760 min Summer	82.096	0.096	0.0	6.3	6.3	28.2	O K
7200 min Summer	82.087	0.087	0.0	5.3	5.3	25.6	O K
8640 min Summer	82.080	0.080	0.0	4.6	4.6	23.7	O K
10080 min Summer	82.075	0.075	0.0	4.1	4.1	22.2	O K
15 min Winter	82.348	0.348	0.0	20.1	20.1	102.6	O K
30 min Winter	82.438	0.438	0.0	20.1	20.1	128.9	O K
60 min Winter	82.501	0.501	0.0	20.1	20.1	147.4	O K
120 min Winter	82.519	0.519	0.0	20.1	20.1	152.8	O K
180 min Winter	82.500	0.500	0.0	20.1	20.1	147.3	O K
240 min Winter	82.467	0.467	0.0	20.1	20.1	137.5	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
15 min Summer	65.439	0.0	100.9	17
30 min Summer	43.443	0.0	134.4	31
60 min Summer	27.653	0.0	172.1	52
120 min Summer	17.113	0.0	213.2	86
180 min Summer	12.792	0.0	239.1	120
240 min Summer	10.359	0.0	258.2	154
360 min Summer	7.651	0.0	286.1	220
480 min Summer	6.171	0.0	307.7	282
600 min Summer	5.219	0.0	325.3	344
720 min Summer	4.550	0.0	340.4	402
960 min Summer	3.662	0.0	365.2	514
1440 min Summer	2.694	0.0	402.8	750
2160 min Summer	1.978	0.0	444.5	1104
2880 min Summer	1.588	0.0	475.7	1472
4320 min Summer	1.164	0.0	522.4	2204
5760 min Summer	0.933	0.0	559.2	2936
7200 min Summer	0.785	0.0	588.3	3672
8640 min Summer	0.682	0.0	613.1	4400
10080 min Summer	0.605	0.0	634.3	5136
15 min Winter	65.439	0.0	113.2	17
30 min Winter	43.443	0.0	150.7	31
60 min Winter	27.653	0.0	192.9	58
120 min Winter	17.113	0.0	238.8	92
180 min Winter	12.792	0.0	267.9	132
240 min Winter	10.359	0.0	289.3	168

Summary of Results for 30 year Return Period

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
360 min Winter	82.389	0.389	0.0	20.1	20.1	114.7	O K
480 min Winter	82.320	0.320	0.0	20.0	20.0	94.2	O K
600 min Winter	82.264	0.264	0.0	19.7	19.7	77.7	O K
720 min Winter	82.223	0.223	0.0	19.2	19.2	65.6	O K
960 min Winter	82.184	0.184	0.0	16.9	16.9	54.2	O K
1440 min Winter	82.148	0.148	0.0	12.9	12.9	43.7	O K
2160 min Winter	82.123	0.123	0.0	9.6	9.6	36.1	O K
2880 min Winter	82.108	0.108	0.0	7.7	7.7	31.7	O K
4320 min Winter	82.090	0.090	0.0	5.7	5.7	26.6	O K
5760 min Winter	82.080	0.080	0.0	4.6	4.6	23.6	O K
7200 min Winter	82.073	0.073	0.0	3.8	3.8	21.4	O K
8640 min Winter	82.068	0.068	0.0	3.4	3.4	19.9	O K
10080 min Winter	82.063	0.063	0.0	3.0	3.0	18.6	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
360 min Winter	7.651	0.0	320.5	236
480 min Winter	6.171	0.0	344.7	298
600 min Winter	5.219	0.0	364.5	356
720 min Winter	4.550	0.0	381.3	406
960 min Winter	3.662	0.0	409.2	520
1440 min Winter	2.694	0.0	451.2	752
2160 min Winter	1.978	0.0	497.9	1112
2880 min Winter	1.588	0.0	532.8	1472
4320 min Winter	1.164	0.0	585.3	2204
5760 min Winter	0.933	0.0	626.3	2936
7200 min Winter	0.785	0.0	659.0	3672
8640 min Winter	0.682	0.0	686.7	4400
10080 min Winter	0.605	0.0	710.7	5136

I&L Consultants (Dubai)		Page 3
29-31 Castle Street High Wycombe Buckinghamshire, HP13 6RU	23-026-Crabtree Lane, Clayton Storage Calculations Tank 30Yrs	
Date 12/12/2023 15:40 File 23-026-Tank 30yrs.SRCX	Designed by SH Checked by IL	
Innovyze	Source Control 2020.1.3	

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	30	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	18.000	Shortest Storm (mins)	15
Ratio R	0.357	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+0

Time Area Diagram

Total Area (ha) 0.833

Time (mins)		Area
From:	To:	(ha)
0	4	0.833

Model Details

Storage is Online Cover Level (m) 84.200

Cellular Storage Structure

Invert Level (m)

82.000

Safety Factor

2.0

Infiltration Coefficient Base (m/hr)

0.00000

Porosity

0.95

Infiltration Coefficient Side (m/hr)

0.00000

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	310.0	0.0	1.200	310.0	0.0	1.201	0.0	0.0

Hydro-Brake® Optimum Outflow Control

Unit Reference

MD-SHE-0197-2020-1200-2020

Design Head (m)

1.200

Design Flow (l/s)

20.2

Flush-Flo™

Calculated

Objective

Minimise upstream storage

Application

Surface

Sump Available

Yes

Diameter (mm)

197

Invert Level (m)

82.000

Minimum Outlet Pipe Diameter (mm)

225

Suggested Manhole Diameter (mm)

1500

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.200	20.2	Kick-Flo®	0.829	16.9
Flush-Flo™	0.379	20.1	Mean Flow over Head Range	-	17.2

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	6.8	0.800	17.6	2.000	25.7	4.000	35.9	7.000	47.1
0.200	18.4	1.000	18.5	2.200	27.0	4.500	38.0	7.500	48.7
0.300	19.9	1.200	20.2	2.400	28.1	5.000	40.0	8.000	50.2
0.400	20.1	1.400	21.7	2.600	29.2	5.500	41.9	8.500	51.7
0.500	19.9	1.600	23.1	3.000	31.3	6.000	43.7	9.000	53.2
0.600	19.5	1.800	24.5	3.500	33.7	6.500	45.4	9.500	54.6

I&L Consultants (Dubai)		Page 1
29-31 Castle Street High Wycombe Buckinghamshire, HP13 6RU	23-026-Crabtree Lane, Clayton Storage Calculations Tank 100Yrs+45% CC	
Date 12/12/2023 15:37 File 23-026-Tank 100yr+45%cc.SRCX	Designed by SH Checked by IL	
Innovyze	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Half Drain Time : 152 minutes.

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
15 min Summer	82.603	0.603	0.0	20.1	20.1	177.6	O K
30 min Summer	82.785	0.785	0.0	20.1	20.1	231.1	O K
60 min Summer	82.948	0.948	0.0	20.1	20.1	279.1	O K
120 min Summer	83.037	1.037	0.0	20.1	20.1	305.3	O K
180 min Summer	83.044	1.044	0.0	20.1	20.1	307.4	O K
240 min Summer	83.030	1.030	0.0	20.1	20.1	303.4	O K
360 min Summer	82.978	0.978	0.0	20.1	20.1	287.9	O K
480 min Summer	82.920	0.920	0.0	20.1	20.1	270.9	O K
600 min Summer	82.857	0.857	0.0	20.1	20.1	252.5	O K
720 min Summer	82.785	0.785	0.0	20.1	20.1	231.3	O K
960 min Summer	82.655	0.655	0.0	20.1	20.1	192.9	O K
1440 min Summer	82.451	0.451	0.0	20.1	20.1	132.8	O K
2160 min Summer	82.273	0.273	0.0	19.8	19.8	80.4	O K
2880 min Summer	82.201	0.201	0.0	18.5	18.5	59.3	O K
4320 min Summer	82.158	0.158	0.0	14.0	14.0	46.4	O K
5760 min Summer	82.136	0.136	0.0	11.3	11.3	40.0	O K
7200 min Summer	82.122	0.122	0.0	9.5	9.5	35.8	O K
8640 min Summer	82.111	0.111	0.0	8.2	8.2	32.8	O K
10080 min Summer	82.104	0.104	0.0	7.3	7.3	30.5	O K
15 min Winter	82.680	0.680	0.0	20.1	20.1	200.2	O K
30 min Winter	82.889	0.889	0.0	20.1	20.1	261.9	O K
60 min Winter	83.074	1.074	0.0	20.1	20.1	316.3	O K
120 min Winter	83.189	1.189	0.0	20.1	20.1	350.2	O K
180 min Winter	83.194	1.194	0.0	20.1	20.1	351.7	O K
240 min Winter	83.174	1.174	0.0	20.1	20.1	345.8	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
15 min Summer	122.490	0.0	190.0	18
30 min Summer	82.125	0.0	255.1	32
60 min Summer	52.627	0.0	328.1	62
120 min Summer	32.639	0.0	407.1	118
180 min Summer	24.356	0.0	455.8	148
240 min Summer	19.667	0.0	490.8	180
360 min Summer	14.425	0.0	540.0	248
480 min Summer	11.585	0.0	578.2	318
600 min Summer	9.765	0.0	609.3	388
720 min Summer	8.488	0.0	635.5	454
960 min Summer	6.797	0.0	678.6	578
1440 min Summer	4.962	0.0	742.8	810
2160 min Summer	3.615	0.0	812.5	1148
2880 min Summer	2.883	0.0	864.1	1472
4320 min Summer	2.093	0.0	940.5	2204
5760 min Summer	1.666	0.0	998.7	2936
7200 min Summer	1.394	0.0	1044.9	3672
8640 min Summer	1.205	0.0	1083.6	4400
10080 min Summer	1.065	0.0	1116.7	5096
15 min Winter	122.490	0.0	212.9	18
30 min Winter	82.125	0.0	285.9	32
60 min Winter	52.627	0.0	367.6	60
120 min Winter	32.639	0.0	456.1	116
180 min Winter	24.356	0.0	510.6	166
240 min Winter	19.667	0.0	549.7	190

I&L Consultants (Dubai)		Page 2
29-31 Castle Street High Wycombe Buckinghamshire, HP13 6RU	23-026-Crabtree Lane, Clayton Storage Calculations Tank 100Yrs+45% CC	
Date 12/12/2023 15:37 File 23-026-Tank 100yr+45%cc.SRCX	Designed by SH Checked by IL	
Innovyze	Source Control 2020.1.3	

Summary of Results for 100 year Return Period (+45%)

Storm Event	Max Level (m)	Max Depth (m)	Max Infiltration (l/s)	Max Control (l/s)	Max Σ Outflow (l/s)	Max Volume (m³)	Status
360 min Winter	83.100	1.100	0.0	20.1	20.1	324.0	O K
480 min Winter	83.015	1.015	0.0	20.1	20.1	298.8	O K
600 min Winter	82.922	0.922	0.0	20.1	20.1	271.5	O K
720 min Winter	82.816	0.816	0.0	20.1	20.1	240.3	O K
960 min Winter	82.607	0.607	0.0	20.1	20.1	178.7	O K
1440 min Winter	82.327	0.327	0.0	20.1	20.1	96.4	O K
2160 min Winter	82.189	0.189	0.0	17.4	17.4	55.7	O K
2880 min Winter	82.158	0.158	0.0	14.0	14.0	46.5	O K
4320 min Winter	82.128	0.128	0.0	10.2	10.2	37.7	O K
5760 min Winter	82.111	0.111	0.0	8.2	8.2	32.8	O K
7200 min Winter	82.100	0.100	0.0	6.8	6.8	29.6	O K
8640 min Winter	82.092	0.092	0.0	5.9	5.9	27.2	O K
10080 min Winter	82.086	0.086	0.0	5.2	5.2	25.3	O K

Storm Event	Rain (mm/hr)	Flooded Volume (m³)	Discharge Volume (m³)	Time-Peak (mins)
360 min Winter	14.425	0.0	604.9	268
480 min Winter	11.585	0.0	647.7	344
600 min Winter	9.765	0.0	682.4	420
720 min Winter	8.488	0.0	711.8	494
960 min Winter	6.797	0.0	760.1	614
1440 min Winter	4.962	0.0	832.1	824
2160 min Winter	3.615	0.0	910.0	1124
2880 min Winter	2.883	0.0	967.9	1472
4320 min Winter	2.093	0.0	1053.5	2204
5760 min Winter	1.666	0.0	1118.6	2936
7200 min Winter	1.394	0.0	1170.3	3672
8640 min Winter	1.205	0.0	1213.7	4408
10080 min Winter	1.065	0.0	1251.0	5048

Rainfall Details

Rainfall Model	FSR	Winter Storms	Yes
Return Period (years)	100	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	18.000	Shortest Storm (mins)	15
Ratio R	0.357	Longest Storm (mins)	10080
Summer Storms	Yes	Climate Change %	+45

Time Area Diagram

Total Area (ha) 0.833

Time (mins)	Area
From:	To: (ha)
0	4 0.833

Model Details

Storage is Online Cover Level (m) 84.200

Cellular Storage Structure

Invert Level (m) 82.000
 Safety Factor 2.0

Infiltration Coefficient Base (m/hr) 0.00000
 Porosity 0.95

Infiltration Coefficient Side (m/hr) 0.00000

Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)	Depth (m)	Area (m²)	Inf. Area (m²)
0.000	310.0	0.0	1.200	310.0	0.0	1.201	0.0	0.0

Hydro-Brake® Optimum Outflow Control

Unit Reference MD-SHE-0197-2020-1200-2020

Design Head (m) 1.200

Design Flow (l/s) 20.2

Flush-Flo™ Calculated

Objective Minimise upstream storage

Application Surface

Sump Available Yes

Diameter (mm) 197

Invert Level (m) 82.000

Minimum Outlet Pipe Diameter (mm) 225

Suggested Manhole Diameter (mm) 1500

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.200	20.2	Kick-Flo®	0.829	16.9
Flush-Flo™	0.379	20.1	Mean Flow over Head Range	-	17.2

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	6.8	0.800	17.6	2.000	25.7	4.000	35.9	7.000	47.1
0.200	18.4	1.000	18.5	2.200	27.0	4.500	38.0	7.500	48.7
0.300	19.9	1.200	20.2	2.400	28.1	5.000	40.0	8.000	50.2
0.400	20.1	1.400	21.7	2.600	29.2	5.500	41.9	8.500	51.7
0.500	19.9	1.600	23.1	3.000	31.3	6.000	43.7	9.000	53.2
0.600	19.5	1.800	24.5	3.500	33.7	6.500	45.4	9.500	54.6