SURFACE WATER MANHOLE SCHEDULE

MANHOLE NO.	MANHOLE CO-ORDINATES	COVER LEVEL (m)	DEPTH TO INVERT (m)	MANHOLE SIZE	MANHOLE TYPE	PIPE IN NAME, INVERT LEVEL (m) & DIA	PIPE OUT NAME, INVERT LEVEL (m) & DIA	COVER SIZE (mm) & GRADE	COMMENTS
S01	E:384695.429 N:398902.024	50.750	0.565	300	Mini IC	From RWP, IL=50.185, 100mmØ From RWP, IL=50.185, 100mmØ	To S02, IL=50.185, 100mmØ	450x450 A15	RECESSED COVER
S02	E:384698.972 N:398905.646	50.750	0.645	450	IC	From RWP, IL=50.105, 100mmØ From RWP, IL=50.105, 100mmØ From RWP, IL=50.105, 100mmØ From S01, IL=50.105, 100mmØ	To S03, IL=50.105, 100mmØ	450x450 A15	RECESSED COVER
S03	E:384703.418 N:398901.941	50.750	0.925	450	IC	From S02, IL=49.825, 100mmØ From RWP, IL=49.825, 100mmØ From RWP, IL=49.825, 100mmØ From RWP, IL=49.825, 100mmØ	To S04, IL=49.825, 100mmØ	450x450 A15	RECESSED COVER
S04	E:384708.895 N:398897.548	50.750	1.020	450	IC	From RWP, IL=49.730, 100mmØ From S03, IL=49.730, 100mmØ From RWP, IL=49.730, 100mmØ	To S06, IL=49.730, 150mmØ	450x450 A15	RECESSED COVER
S05	E:384715.690 N:398892.884	50.750	0.970	450	IC	From RWP, IL=49.780, 100mmØ From RWP, IL=49.780, 100mmØ	To S06, IL=49.780, 100mmØ	450x450 A15	RECESSED COVER
S06	E:384714.316 N:398892.782	50.750	1.110	450	IC	From S04, IL=49.640, 150mmØ From RWP, IL=49.640, 100mmØ From S05, IL=49.640, 100mmØ	To S09, IL=49.640, 150mmØ	450x450 A15	RECESSED COVER
S07	E:384702.538 N:398887.015	50.750	0.750	450	IC	From RWP, IL=50.000, 100mmØ From RWP, IL=50.000, 100mmØ	To S08, IL=50.000, 100mmØ	450 B125	
S08	E:384709.082 N:398894.652	50.750	1.750	450	IC	From S07, IL=49.000, 100mmØ From RWP, IL=49.000, 100mmØ	To S09, IL=49.000, 100mmØ	450 B125	
S09	E:384714.468 N:398889.854	50.750	2.450	1050	Type-B	From S08, IL=48.300, 100mmØ From S06, IL=49.600, 150mmØ	To S10, IL=48.300, 225mmØ	600x600 D400	1No BACKDROP
S10	E:384720.017 N:398883.890	50.750	3.250	1050	Type-B	From S09, IL=47.500, 225mmØ	To ATT(1), IL=47.500, 225mmØ	600x600 D400	
S11	E:384713.490 N:398876.017	50.750	3.375	1200	Type-B	From ATT(1), IL=47.375, 225mmØ	To C01, IL=47.375, 150mmØ	600x600 D400	FLOW CONTROL

FOUL WATER MANHOLE SCHEDULE

MANHOLE NO.	MANHOLE CO-ORDINATES	COVER LEVEL (m)	DEPTH TO INVERT (m)	MANHOLE SIZE	MANHOLE TYPE	PIPE IN NAME, INVERT LEVEL (m) & DIA	PIPE OUT NAME, INVERT LEVEL (m) & DIA	COVER SIZE (mm) & GRADE	COMMENTS
F01	E:384696.625 N:398908.418	50.900	0.600	300	Mini IC	From SVP, IL=50.300, 100mmØ From SVP, IL=50.300, 100mmØ From SVP, IL=50.300, 100mmØ	To F02, IL=50.300, 100mmØ	450x450 A15	RECESSED COVER
F02	E:384697.856 N:398907.307	50.900	0.625	450	IC	From SVP, IL=50.275, 100mmØ From F01, IL=50.275, 100mmØ From SVP, IL=50.275, 100mmØ	To F03, IL=50.275, 100mmØ	450x450 A15	RECESSED COVER
F03	E:384701.708 N:398903.945	50.750	0.540	450	IC	From F02, IL=50.210, 100mmØ From SVP, IL=50.210, 100mmØ From SVP, IL=50.210, 100mmØ From SVP, IL=50.210, 100mmØ	To F06, IL=50.210, 100mmØ	450x450 A15	RECESSED COVER
F04	E:384693.862 N:398899.801	50.750	0.570	450	IC	From SVP, IL=50.180, 100mmØ From SVP, IL=50.180, 100mmØ	To F05, IL=50.180, 100mmØ	450x450 A15	RECESSED COVER
F05	E:384699.881 N:398895.739	50.750	0.665	450	IC	From SVP, IL=50.085, 100mmØ From F04, IL=50.085, 100mmØ From SVP, IL=50.085, 100mmØ From SVP, IL=50.085, 100mmØ	To F06, IL=50.085, 100mmØ	450x450 A15	RECESSED COVER
F06	E:384705.038 N:398901.399	50.750	0.760	450	IC	From F03, IL=49.990, 100mmØ From SVP, IL=49.990, 100mmØ From F05, IL=49.990, 100mmØ From SVP, IL=49.990, 100mmØ	To F07, IL=49.990, 100mmØ	450x450 A15	RECESSED COVER
F07	E:384706.503 N:398900.151	50.750	0.785	450	IC	From F06, IL=49.965, 100mmØ From SVP, IL=49.965, 100mmØ From SVP, IL=49.965, 100mmØ	To F08, IL=49.965, 100mmØ	450x450 A15	RECESSED COVER
F08	E:384710.940 N:398896.342	50.750	0.860	450	IC	From SVP, IL=49.890, 100mmØ From F07, IL=49.890, 100mmØ From SVP, IL=49.890, 100mmØ From SVP, IL=49.890, 100mmØ	To F10, IL=49.890, 150mmØ	450x450 A15	RECESSED COVER
F09	E:384700.883 N:398884.676	50.750	0.700	450	IC	From SVP, IL=50.050, 100mmØ	To F10, IL=50.050, 100mmØ	450 B125	
F10	E:384702.116 N:398883.761	50.750	0.965	450	IC	From F09, IL=49.785, 100mmØ From F08, IL=49.785, 150mmØ	To C01, IL=49.785, 150mmØ	450 B125	
F11	E:384719.109 N:398886.844	50.750	0.605	450	IC	From SVP, IL=50.145, 100mmØ From SVP, IL=50.145, 100mmØ	To C01, IL=50.145, 100mmØ	450 B125	

COMBINED WATER MANHOLE SCHEDULE

MANHOLE NO.	MANHOLE CO-ORDINATES	COVER LEVEL (m)	DEPTH TO INVERT (m)	MANHOLE SIZE	MANHOLE TYPE	PIPE IN NAME, INVERT LEVEL (m) & DIA	PIPE OUT NAME, INVERT LEVEL (m) & DIA	COVER SIZE (mm) & GRADE	COMMENTS
C01	E:384710.656 N:398876.650	50.750	3.410	1050	Type-B	From F10, IL=49.600, 150mmØ From F11, IL=49.810, 100mmØ From S11, IL=47.340, 150mmØ	To C02, IL=47.340, 225mmØ	600x600 D400	2No. Backdrops
C02	E:384705.997 N:398871.139	50.450 (TBC)	3.470	1050	Type-B	From C01, IL=46.980 (TBC), 225mmØ		600x600 D400	COVER AND INVERT LEVELS APPROX. ONLY. TO BE CONFIRMED ON SITE.

HOLD
OUTFALL LOCATION & LEVELS TBC

DISCLAIMER NOTES:

- THIS DOCUMENT IS COPYRIGHT OF THE ORIGINATOR AND MUST BE TREATED AS CONFIDENTIAL
- THIS DOCUMENT MUST NOT BE ALTERED, REPRODUCED OR DISTRIBUTED WITHOUT PRIOR WRITTEN CONSENT OF THE ORIGINATOR
- THIS DOCUMENT MUST NOT BE ALTERED - THE ORIGINATOR ACCEPTS NO RESPONSIBILITY FOR ANY DISCREPANCIES ARISING AS A RESULT OF THE ORIGINATORS INFORMATION BEING ALTERED BY OTHERS
- ANY DISCREPANCY MUST BE REPORTED TO THE ORIGINATOR
- DO NOT SCALE THIS DOCUMENT - USE FIGURED DIMENSIONS ONLY
- ALL DIMENSIONS MUST BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY RELATED WORKS
- THIS DOCUMENT MUST BE READ IN CONJUNCTION WITH ALL SUPPORTING DOCUMENTS PRODUCED BY THE ORIGINATOR AND OTHER PROJECT DISCIPLINES
- THE ORIGINATOR ACCEPTS NO RESPONSIBILITY FOR THE ACCURACY OF BACKGROUND INFORMATION PRODUCED BY THIRD PARTIES - THIS MUST BE TREATED AS INDICATIVE ONLY
- USERS OF THIS DOCUMENT ARE RESPONSIBLE FOR CHECKING WHICH REVISION IS CURRENT
- THE DOCUMENT STATUS "INFORMATION" OR "PRELIMINARY", INDICATES THAT THIS DRAWING IS FOR REFERENCE PURPOSES ONLY - THE ORIGINATOR WILL ACCEPT NO RESPONSIBILITY FOR THE COMPLETENESS OF INFORMATION UNDER THIS STATUS
- THE DOCUMENT STATUS "RECORD" OR "AS BUILT" HAS BEEN PREPARED, IN PART, BASED UPON INFORMATION FURNISHED BY OTHERS. WHILE THIS INFORMATION IS BELIEVED TO BE RELIABLE, THE ORIGINATOR ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OF THIS "RECORD" OR "AS BUILT" DOCUMENT OR FOR ANY ERRORS OR OMISSIONS THAT MAY HAVE BEEN INCORPORATED INTO IT AS A RESULT OF INCORRECT INFORMATION PROVIDED TO THE ORIGINATOR. THOSE RELYING ON THE "RECORD" OR "AS BUILT" DOCUMENT ARE ADVISED TO OBTAIN INDEPENDENT VERIFICATION OF ITS ACCURACY

DRAWING NOTES:

CDM REGULATIONS 2015
SIGNIFICANT OR NON-OBVIOUS RISKS AND RISKS WHICH ARE DIFFICULT TO MANAGE ARE IDENTIFIED ON THIS DRAWING USING THE FOLLOWING SYMBOL IDENTIFIED TO THE RIGHT WITH BRIEF ACCOMPANYING TEXT. FOR FURTHER DETAILS OF THE RISKS IDENTIFIED BY DESIGNERS, REFERENCE SHOULD BE MADE TO CDM HAZARD REGISTER.

REV	DESCRIPTION	DATE	BY	CHKD
P03	UPDATED TO SUIT LATEST DRAINAGE REVISIONS	13.12.23	AP	JRS
P02	C02 INVERT LEVEL UPDATED	28.01.22	AS	ED
P01	PRELIMINARY ISSUE	03.11.21	AS	ED

ORIGINATOR:

RIDGE
5TH FLOOR
BELVEDERE HOUSE
12 BOOTH STREET
MANCHESTER, M2 4AW
TEL: 0161 833 9579
WWW.RIDGE.CO.UK

CLIENT:
MULBURY CITY

IN ASSOCIATION WITH:

PROJECT:
GOULDEN STREET

TITLE:
DRAINAGE
MANHOLE SCHEDULE

ENG/TECH:	CSE:	ICSE:	SCALE:	1:100 @ A1
AS	ED	ED	STATUS ISSUE:	09.07.21

STATUS: PRELIMINARY

UNLESS ISSUED FOR CONSTRUCTION - WORKS AT CLIENT/CONTRACTORS RISK

SUITABILITY: S0 - Initial Status or WIP

PROJECT:	ORG:	ZONE:	LEVEL:	TYPE:	ROLE:	NUMBER:	REV:
5015327	RDG	XX	XX	DR	C	0104	P03