

SUDS STRATEGY

Planning Constraints
- Planning guidance followed with SUDS proposed as suitable.
- SUDS proposals:
Phase 1
MI Bid North = attenuation and possible porous paving
MI Bid Mid = rain gardens and porous surfacing
MI Bid south = attenuation
Phase 2
Mid bid = attenuation and possible porous paving
Corner bid = attenuation
Drainage Authority Constraints
- Settlement conditions have been applied to restrict discharge to 50% of existing 1 year brownfield rates. As agreed with UU, total site discharge to Bradford Road sewer = 25L/s
MI Bid North = 6L/s
MI Bid Mid = 25L/s
MI Bid South = 3L/s (not in calculations) only relevant if approved responses of phase 2 drainage.
Corner Bid = 8L/s (or 5L/s if MI Bid south connected separately)
MI Bid Bid connected to basement street at 5L/s as agreed with UU. (greenfield)
Total site discharge = 44L/s
FRA Constraints
- HW Detail design completed in accordance with Civic FRA and drainage strategy documents.
other
- No infiltration yet assumed, ground conditions to be confirmed.

General Notes

Do not scale this drawing. If in doubt, consult with the Engineer

- This drawing is to be read in conjunction with all other relevant Engineers, Architects and Specialist design drawings and specifications.
- All dimensions and levels are in metres unless noted otherwise.
- This drawing is for information purposes and all information displayed is subject to detailed design.
- Cover levels noted are indicative or best design levels. constructed levels should take into account as-built surfacing levels and gradients.
- The Contractor shall be responsible for checking all tie-ins for line and level with existing foul and surface water systems before commencing any works.
- The Engineer shall be notified immediately, in writing, should any errors or discrepancies be found prior to the commencement or continuation of any works. All work is to be carried out in accordance with current British Standards, Building Regulations and NHBC Standards.
- All drainage work is to be strictly in accordance with the requirements of the Building Regulations 2010, Approved Document Part H, "Drainage and waste disposal".
- It is the responsibility of the Contractor to ensure the works at all times in strict accordance with the requirements of the Health and Safety at Work Act 1974, and the C.D.M. Regulations 2015. The Contractor will be deemed to have allowed for full compliance, including full liaison with the Principle Contractor, within his rates.
- All existing land drains encountered on site during construction are to be re-connected.
- Should any departure from the proposed slab or external levels be considered, agreement shall be sought from the Engineer immediately and prior to the commencement or continuation of any works. Proposals should take full account of all restrictions to the slab level.
- Temporary protection to be provided to drainage work during construction as necessary.
- Power supply to separator/treatment units, alarm, panel, vent etc to be provided by contractor in accordance with manufacturers recommendations.
- Topographical survey shown is based upon Survey Solutions drawing 46746MCLS-01
- Architects layout shown is based upon Hodder and Partner Site Layout drawing no 200. This layout may be subject to change and is intended for indicative purposes only.

Specification Notes

- The following types of pipe may be used unless noted or agreed otherwise:
 - Pipes up to 300mm diameter to be Stuctured Walled to BS EN 13476, Polypropylene to BS EN 1852 or PVC-U to BS EN 1401.
 - Pipes 300mm diameter or over to be Concrete to BS 5911.
- Both Clay and Concrete pipes shall be strength class 120 (100/150mm min crushing strength 28kN/m). Thermoplastic pipes shall have a minimum ring stiffness of SM4.
- Pipes which run adjacent to buildings shall be installed in strict accordance with Part H, Clauses 2.23 to 2.25.
- All pipes, chambers and fittings shall be installed, bedded and backfilled in accordance with the manufacturers instructions subject to the following minimum requirements:

Pipe Location	Cover to crown	Clay/Concrete Pipe * Bedding	Plastic Pipe Bedding	Backfill
Roads (HGV)	>1.2m	Class S	Class S (S1or2)	Type 1 Granular
	<1.2m	Class 'A' (Concrete)	Class 'A' (Concrete)	
Drives / car parking	>0.9m	Class S	Class S (S1or2)	Type 1 Granular
	<0.9m	Class 'A' (Concrete)	Class 'A' (Concrete)	
Hard and soft Landscaping	>0.6m	Class S	Class S (S1or2)	Suitable as dug material
	<0.6m	Class 'A' (Concrete)	Class 'A' (Concrete)	

- The first flexible joint in pipes adjoining a manhole shall be a maximum length of 600mm from the inside face of the manhole, connecting to a rocker pipe. The length of the rocker pipe shall be as follows;

Pipe diameter	Length of Rocker pipe
150-600mm	600mm
675-750mm	1000mm
over 750mm	1250mm

- All manholes and inspection chambers situated in areas subject to vehicular loading to have class D400 covers and frames to BS EN124 and those not subject to vehicular loading to have class minimum class 8125 covers and frames.
- Drainage frames must be tied to manhole risers by use of manufacturers ties (eg. Polytype ref FR500 long kit and FR501 black ties). The ground works contractor will be held fully responsible for any accidents due to incorrect fitting or failure to use the correct manufacturers fixing equipment.
- All drains in the vicinity of existing or proposed trees to be constructed in accordance with the requirements of NHBC Practice Note 3.

INFORMATION/PLANNING

P02	24.09.23	Updated to suit full pipe calculations	BD
Rev.	Date	Amendments	By Chkd

Project
Brunswick Mill
Bradford Road
Manchester
Status

FOR
INFORMATION/PLANNING

Scale	Drawn	Checked	Date
1:250	BD	CW	20-07-23

HOWARD WYNNE
Consulting Engineers
Unit 2a, 100 Manton Road, West Bridgford, Nottingham NG2 6EP.

Drawing Title

Drainage Strategy
sheet 2 of 2
Phase 2
Client

ARROWSMITH-
Brunswick Square.

Project/Drawing No.
23178-HW-23-00-DR-C-501

Rev.

P02