



2No. Wall mounted switches to be replaced with new in existing positions using existing screw holes.
All finishes retained as existing.

Temporary remove plasterboard ceiling locally to allow for New boiler flue in existing position and opening fixed using existing fixings to project through existing ceiling and penetration, all finishes retained as existing. Refix ceiling locally on completion.

New freestanding boiler sat on existing retined flagstones as per original boiler.

Wall mounted copper supply pipes as shown in pictures to be retained and connected into.

Wall mounted expansion vessel 2No. to be replaced in existing position using existing fixing positions. All finishes retained as existing.

A 10/11/23 additional notes added

Rev	Date/Intls	Details
-----	------------	---------

© The moral rights of the author are hereby asserted.
This drawing and design is the sole property of Buttress Ltd and must not be reproduced without permission.
Buttress Ltd is Registered in England and Wales: 5363573

Buttress

41 Bengal St
Manchester
M4 6AF

T 0161 236 3303
E contact@buttress.net
W www.buttress.net

Project Title	CSM - Library Flue
Client	Chetham's School of Music
Location	Manchester

Drawing Title	Proposed Plan
---------------	---------------

Date	06/010/23	Scale	1:100
Checked	EK	Orig Paper Size	A1

Status **PLANNING**

Project: Origin: Zone: Level: Type: Disc: Number: Rev

9424 - BA - ZZ - ZZ - DR - A - (02)007 - A