

© THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY FROM THE OWNER.

NOTES:

1. Do not scale from this drawing.
2. Always work to noted dimensions.
3. All dimensions are in millimetres unless otherwise stated.
4. All setting out, levels and dimensions to be agreed on site.
5. The dimensions of all materials must be checked on site before being laid out.
6. This drawing must be read with the relevant specification clauses and detail drawings.
7. Order of construction and setting out to be agreed on site.

KEY

REDLINE PLANNING BOUNDARY

TEMPORARY WORK EXTENTS
Temporary works to be installed as part of Angel Square Public Realm. In place until completion of 3 Angel Square.

SOFTWORKS

TREES - PROPOSED, SEMI MATURE
Refer to softworks schedule

EXISTING TREE RETAINED

PROPOSED ORNAMENTAL PLANTING
Refer to planting schedule
2962-PLA-XX-XX-DR-L-2001

PROPOSED RAIN GARDEN PLANTING
Refer to planting schedule
2962-PLA-XX-XX-DR-L-2001

PROPOSED AMENITY TURF
15-30% of fine leaved ryegrass and 15% smooth stalked meadowgrass.
Remainder of the mixture is made up from strong and slender creeping red fescue and chewings fescue.
Product: Olympic turf
Supplier: Professional lawns or similar approved.

TP — **TREE CODE**
Refer to softworks schedule

Tree Schedule

Abbreviations	Species	Specification	Size: girth (cm)	Size: height (cm)	Rootball	Total No.
Ac	Acer campestre 'streetwise'	semi-mature, with 2.2m clear stem,underground guyed	30-35cm	5.0-7.0m	RB	3
Al	Amelanchier x Lamarckii	RB Mulistem specimen 4-6x transplanted min 3 stong stems 1.5m clear stems. Umbrella pruned	-	4.5-5m	RB	5
Bp	Betula pendula	semi-mature, with 2.2m clear stem,underground guyed	30-35cm	5.0-7.0m	RB	4
Ck	Cornus Kousa	RB Mulistem specimen 4-6x transplanted min 3 stong stems 1.5m clear stems	-	3.5-4m	RB	3
Gt	Gleditsia triacanthos 'Skyline'	semi-mature, with 2.2m clear stem,underground guyed 5x transplanted	30-35cm	5.0-7.0m	RB	4
L t	Liriodendron Tulipifera	semi-mature, with 2.2m clear stem,underground guyed. 6x tr	50-60cm	7.0-9.0m	RB	1
Ms	Magnolia stellata	RB Mulistem specimen 4-6x transplanted min 3 stong stems 1.5m clear stems. Umbrella pruned	-	3.5-4m	RB	2
Mb	Malus baccata 'Street Parade'	semi-mature, with 2.2m clear stem,underground guyed 5x transplanted	25-30cm	5-6m	RB	2
Mb	Malus baccata 'Street Parade'	Tree already secured from national trust funding. Located in NOMA nursery.	-	-	RB	3
PsK	Prunus serrulata 'Kanzan'	Tree already secured from national trust funding. Located in NOMA nursery.	-	-	RB	3
Py	Prunus x yedoensis	Tree already secured from national trust funding. Located in NOMA nursery.	-	-	RB	3
PxS	Prunus x subhirtella	Tree already secured from national trust funding. Located in NOMA nursery.	-	-	RB	2
Qp	Quercus palustris	semi-mature, with 2.2m clear stem,underground guyed 5x transplanted	30-35cm	5.0-7.0m	RB	1
A lam	Amelanchier x Lamarckii	RB Mulistem specimen 4-6x transplanted min 3 stong stems	5-5.5m		RB	1

Revision	Date	Description	Drawn	Apprvd.
P08	19/09/23	NMA	SAB	KR

Planit I.E. Limited
Manchester | London | Liverpool | Leeds | Standish
E: info@planit-ie.com **W:** planit-ie.com

MANCHESTER
2 Back Grafton St ,
Altrincham,
WA14 1DY
T: 0161 928 9281

Client	MEPC
Project	Angel Square Manchester
Drg Title	Softworks

Created on	Created by	Approved by
08.07.22	SAB	KR

Scale	Size	Workstage	Status
1:250	A1	Stage 3	

Drg No.	Suitability	Revision
2962-PLA-XX-XX-DR-L-2000	S4	P08

© Planit I.E. Limited