



Detailed Drainage Design

22 Honor Street, Manchester, M13 0WY

Reference: 412 -Rev - V1

Date: Dec-23

- 1 Introduction
- 2 Site Characteristics
- 3 Discharge Arrangement
- 4 Peak Runoff
- 5 Proposed Sustainable Drainage
- 6 Maintenance and Management Plan

Appendices

- A Distribution Existing and Proposed Areas
- B Site Characteristics
- C Drainage Calculations
- D Drainage System General Arrangement

London Office

5th Floor, 167, 169 Great Portland St,
London W1W 5PF

Oxford Office

Oxford Innospace, Old Music Hall, 106-108
Cowley Road, Oxford, OX4 1JE

info@urban-water.co.uk

Purpose of this report

- 1.1 The purpose of this statement is to accompany the detailed technical drawings and details showing the proposed Surface Water drainage system.

Site Characteristics

- 2.1 The site background is clearly identified through answers to the questions in table 1 below.

Table 1: Site Characteristics . See appendix B for support documentation

TOPIC	QUESTION	ANSWER
Protected species or habitat	Is the site near to designated sites and priority habitats?	No
Flood Plain	Is the site located in the flood plain?	No
Soils and Geology	Soil permeability? - See appendix B for results	No
Space constraints	Space for SuDS components?	No
Topography	Sited on a flat site?	Yes
	Sited on a steep slope (5-15%)	No
	Sited on a very steep slope (>15%)	No
Groundwater	Is the site at groundwater flood risk?	Yes
Contaminated land	Are there contaminated soils on site?	Unknown
Source Protection Zone	Is the site within a SPZ 3?	No
Runoff characteristics	Is the development in a high risk flooding area?	No

Existing and Proposed Site

- 2.2 The distribution of catchment areas for existing and proposed site is as per table 2 below. See appendix A for details

Table 2 : Existing and Proposed catchment areas in hectares

Description	Existing Site	Proposed Site
Impermeable Areas	0.006	0.007
Permeable Areas		
Connected to Drainage	0.000	0.000
Self Draining Areas	0.000	0.000
Areas Draining Away from drainage System	0.005	0.004
Total Development Area	0.011	0.011

- 2.3 It has been assumed that the positively drained areas will have different runoff coefficients depending on the type of surface as follow:

Impermeable Surface	1.0
Permeable Surfaces	0.5
Grass Areas	0.3

Evaluation of Discharge Point

3.1 The SuDS design takes into account Building Regulations Section H3 and the National Planning Practice Guidance. The aim is to discharge surface water run-off as high up the drainage hierarchy, as reasonably practicable:

1. into the ground (infiltration);
2. to a surface water body;
3. to a surface water sewer, highway drain, or another drainage system;
4. to a combined sewer.

3.2 The discharge point has been evaluated following the NPPG and Building regulations. The findings are in table 3 below.

Table 3: Drainage Hierarchy evaluation

Superficial geology classification	The British Geological Society records show that the superficial deposits are Till, Devensian - Diamicton.
Bedrock geology classification	The British Geological Society records of the site show that it is located within the Manchester Marls Formation - Mudstone.
Landis Top Soil Infiltration	The SOILSCAPE's records of the site show that it is located within an area of impeded drainage soils.
Groundwater	The British Geological Survey's flood risk susceptibility maps show that the development has potential for groundwater flooding above ground level. Groundwater levels would tend to vary seasonally and are influenced by ground and meteorological conditions and proximity to water features.
Is infiltration feasible?	Infiltration is not possible on this site due to the findings on groundwater and soils within the site. The groundwater level is likely to be very high on site.
Is a discharge to a watercourse possible?	There are no watercourses in the proximity to the site.
Is a discharge to a surface water sewer possible?	There is no surface water sewer in the proximity to the site.
Is a discharge to a combined sewer possible?	There is a combined water sewer in the proximity to the site. It is possible to connect to the combined water sewer.

Existing and Proposed Peak Run-off Calculations

- 4.1 The current site is a Brownfield. The peak runoff rate for the existing site was calculated as per table 4 and discharge rates as per table 5.

Table 4: Peak run-off rate calculation method for existing site

Method Used	Calculation Method
	Report 124 Flood Estimation for Small Catchments method has been used to estimate the site peak flow rates
✗	This is a brownfield site, runoff rates are calculated in accordance with best practice simulation modelling and using the modified rational method
	This is a brownfield site where the pre-development drainage isn't known. The runoff rates are calculated using the Greenfield model with soil type 5

- 4.2 The runoff flow produced by the development will be controlled as per table 5.

Table 5: Runoff discharge rate control

Control Used	Description of runoff discharge
	Water will be discharged into the ground via a SuDS as described in table 6 below
	The peak discharge rate has been reduced to Greenfield Qbar flow
	The peak discharge rate has been taken as 0.7 l/s as it is not possible to reduce it to the Greenfield Qbar rate
	The peak discharge rate has been reduced to Brownfield pre-development 1 in 1 flow
✗	The peak discharge rate has been reduced by 50% from the existing Brownfield pre-development 1 in 2 flow rate

Run-off flows

- 4.3 The size of the SuDS has been calculated for all events up to the 1 in 100 including an allowance for climate change of 40%. As per tables above, it is proposed to discharge at a rate of 0.55 l/s. See table 6 for values and appendix C for calculations.

Table 6: Peak discharge rates for SuDS

Return Period Event	Discharge Rate (l/s)			Infiltration Rate (m/hr)
	Existing Greenfield	Existing Brownfield	Proposed	
Qbar	0.10	N/A	N/A	0.0000
1 in 1	0.10	0.90	0.55	0.0000
1 in 2	0.10	1.10	0.55	0.0000
1 in 30	0.10	2.10	0.55	0.0000
1 in 30 + CC	N/A	N/A	0.55	0.0000
1 in 100	0.10	2.60	0.55	0.0000
1 in 100 + CC	N/A	N/A	0.55	0.0000

Proposed Sustainable Drainage System

- 5.1 The following sustainable drainage systems have been used for this site. The drainage design uses these drainage system through out the site. See table 7 for details.

Table 7: Proposed Drainage System

SuDS Proposed	Feasible	Proposed
Use of green roofs	No	No
Store rainwater for later use	No	No
Use infiltration techniques, for instance soakaways, permeable surfaces	No	No
Attenuate rainwater in ponds or open water features for gradual release	No	No
Attenuate rainwater by storing in tanks or sealed water features for gradual release	Yes	Yes
Discharge Point Proposed		
Discharge rainwater direct to a watercourse	No	No
Discharge rainwater to a surface water sewer/drain	No	No
Discharge rainwater to the combined sewer	Yes	Yes

- 5.2 The location and details of the SuDS can be seen drainage layouts in appendix D. Calculations are in appendix C.
- 5.3 The drainage calculations demonstrate:
- No flooding occurs for the 1 in 30 storm events.
 - Any flooding for the 1 in 100 year + 40% climate change event can be safely contained on site
- 5.4 The proposed drainage design demonstrates that the development can be sustainably drained to comply with the requirements of the NPPF.

Management of Exceedance Flows

- 5.5 The drainage network has been designed to attenuate surface runoff for all events up to and including the 1% AEP + CC(1 in 100 years). However consideration has been given to what may happen when the design capacity of the surface water drainage network is exceeded. Surface water will flow to the lowest points within the site. The flood risk to the buildings would therefore remain low. See appendix D.

Maintenance and Management plan responsibility

- 6.1 The SuDS will be maintained by The Owner the property

Maintenance and Management plan for proposed SuDS

- 6.2 The maintenance and Management Plan Guidance from the SuDS Manual, CIRIA C753 (CIRIA, 2015) is to be followed for the effective maintenance of the proposed SuDS techniques outlined above. The maintenance for SuDS structures are as follow:

INLETS, OUTLETS, CONTROLS AND INSPECTION CHAMBERS	
Regular Maintenance	Frequency
Inlets, outlets and surface control structures	
Inspect surface structures removing obstructions and silt as necessary. Check there is no physical damage.	Monthly
Strim vegetation 1m min. surround to structures and keep hard aprons free from silt and debris	Monthly
Inspection chambers and below ground control chambers	
Remove cover and inspect ensuring water is flowing freely and that the exit route for water is unobstructed. Remove debris and silt. Undertake inspection after leaf fall in autumn	Annually
Occasional Maintenance	
Check topsoil levels are 20mm above edges of baskets and chambers to avoid mower damage	As necessary
Remedial work	Frequency
Unpack stone in basket features and unblock or repair and repack stone as design detail as necessary.	As required
Repair physical damage if necessary.	As required

Operation and maintenance requirements for attenuation storage tanks		
Maintenance schedule	Required action	Typical frequency
Regular maintenance	Inspect and identify any areas that are not operating correctly. If required, take remedial action	Monthly for 3 months, then annually
	Remove debris from the catchment surface (where it may cause risks to performance)	Monthly
	For systems where rainfall infiltrates into the tank from above, check surface of filter for blockage by sediment, algae or other matter; remove and replace surface infiltration medium as necessary.	Annually
	Remove sediment from pre-treatment structures and/or internal forebays	Annually, or as required
Remedial actions	Repair/rehabilitate inlets, outlet, overflows and vents	As required
Monitoring	Inspect/check all inlets, outlets, vents and overflows to ensure that they are in good condition and operating as designed	Annually
	Survey inside of tank for sediment build-up and remove if necessary	Every 5 years or as required

Appendix A

Drawing Scale Bar		Drawing Scale Bar	
Drawing scale	Line length	Drawing scale	Line length
1:5	= 0.25 metres	1:200	= 10.0 metres
1:10	= 0.5 metres	1:250	= 12.5 metres
1:20	= 1.0 metres	1:500	= 25.0 metres
1:25	= 1.25 metres	1:1000	= 50.0 metres
1:50	= 2.5 metres	1:1250	= 62.5 metres
1:100	= 5.0 metres	1:2500	= 125 metres
Measure length of line above for checking of scale			

GENERAL NOTES

KEY	
	PERMEABLE AREAS
	IMPERMEABLE AREAS
	STUDY AREA

Rev	Details	Date	By	Chd

Drawing Status: **PRELIMINARY**




Client:


Project:
22 Honor Street, Manchester, M13 0WY

Drawing:
Existing and Proposed Areas
Permeable and Impermeable

Print Size:	Project No:	Drawing No:	Revision:
A1	0412	002	P1



EXISTING SITE 1:50




PROPOSED SITE 1:50


Appendix B






GEOLOGY - BEDROCK - MANCHESTER MARLS FORMATION - MUDSTONE




GEOLOGY - SUPERFICIAL DEPOSITS - TILL, DEVENSIAN - DIAMICTON







SITE SURFACE WATER FLOOD RISK




High risk means a chance of flooding greater than 3.3% (1:30)
 Medium risk means a chance of flooding of btw 1% (1:100) and 3.3%
 Low risk means a chance of flooding of btw 0.1% (1:1000) and 1%
 Flooding from surface water is difficult to predict as rainfall location and volume are difficult to forecast. In addition, local features can greatly affect the chance and severity of flooding



Over 900mm 300 to 900mm Below 300mm

MAGIC RESULTS



Site Check Results

Site Check Report Report generated on Tue Nov 21 2023

You selected the location: Centroid Grid Ref: SJ86569548

The following features have been found in your search area:

Aquifer Designation Map (Bedrock) (England)

Typology

Secondary B

Aquifer Designation Map (Superficial Drift) (England)

Typology

Secondary (undifferentiated)

Source Protection Zones merged (England)


No Features found

OK


Cancel

Export to CSV

Print



GROUND WATER FLOOD RISK



Flood map for planning

Your reference
<Unspecified>

Location (easting/northing)
386564/395487

Created
21 Nov 2023 21:23

Your selected location is in flood zone 1, an area with a low probability of flooding.

You will need to do a flood risk assessment if your site is **any of the following:**

- bigger than 1 hectare (ha)
- In an area with critical drainage problems as notified by the Environment Agency
- identified as being at increased flood risk in future by the local authority's strategic flood risk assessment
- at risk from other sources of flooding (such as surface water or reservoirs) and its development would increase the vulnerability of its use (such as constructing an office on an undeveloped site or converting a shop to a dwelling)

Notes

The flood map for planning shows river and sea flooding data only. It doesn't include other sources of flooding. It is for use in development planning and flood risk assessments.

This information relates to the selected location and is not specific to any property within it. The map is updated regularly and is correct at the time of printing.

Flood risk data is covered by the Open Government Licence **which** sets out the terms and conditions for using government data. <https://www.nationalarchives.gov.uk/doc/open-government-licence/version/3/>

Use of the address and mapping data is subject to Ordnance Survey public viewing terms under Crown copyright and database rights 2022 OS 100024198. <https://flood-map-for-planning.service.gov.uk/os-terms>

Flood map for planning

Your reference
<Unspecified>


Location (easting/northing)
386564/395487

Scale
1:2500

Created
21 Nov 2023 21:23

-  Selected area
-  Flood zone 3
-  Flood zone 2
-  Flood zone 1
-  Flood defence
-  Main river
-  Water storage area

0 20 40 60m



SSSI Impact Risk Zones - to assess planning applications for likely impacts on SSSIs/SACs/SPAs & Ramsar sites (England)

1. DOES PLANNING PROPOSAL FALL INTO ONE OR MORE OF THE CATEGORIES BELOW? 2. IF YES, CHECK THE CORRESPONDING DESCRIPTION(S) BELOW. LPA SHOULD CONSULT NATURAL ENGLAND ON LIKELY RISKS FROM THE FOLLOWING:

All Planning Applications

Infrastructure

Wind & Solar Energy

Minerals, Oil & Gas

Rural Non Residential

Residential

Rural Residential

Air Pollution

Combustion

Livestock & poultry units with floorspace > 500m², slurry lagoons & digestate stores > 4000m².
General combustion processes >50MW energy input. Incl: energy from waste incineration, other incineration, landfill gas generation plant, pyrolysis/gasification, anaerobic digestion, sewage treatment works, other incineration/ combustion.

Waste

Composting

Discharges

Water Supply

Notes 1

Notes 2

GUIDANCE - How to use the Impact Risk Zones

[/Metadata_for_magic/SSSI IRZ User Guidance MAGIC.pdf](#)

Aquifer Designation Map (Bedrock) (England)

Typology

Secondary B

Aquifer Designation Map (Superficial Drift) (England)

Typology

Secondary (undifferentiated)

Areas of Outstanding Natural Beauty (England)

No Features found

Limestone Pavement Orders (England)

No Features found

Local Nature Reserves (England) - points

No Features found

Local Nature Reserves (England)

No Features found

Moorland Line (England)

No Features found

National Nature Reserves (England) - points

No Features found

National Nature Reserves (England)

No Features found

National Parks (England)

No Features found

Ramsar Sites (England) - points

No Features found

Ramsar Sites (England)

No Features found

Proposed Ramsar Sites (England) - points

No Features found

Proposed Ramsar Sites (England)

No Features found

Sites of Special Scientific Interest Units (England) - points

No Features found

Sites of Special Scientific Interest Units (England)

No Features found

Sites of Special Scientific Interest (England) - points

No Features found

Sites of Special Scientific Interest (England)

No Features found

Special Areas of Conservation (England) - points

No Features found

Special Areas of Conservation (England)

No Features found

Possible Special Areas of Conservation (England) - points

No Features found

Possible Special Areas of Conservation (England)

No Features found

Special Protection Areas (England) - points

No Features found

Special Protection Areas (England)

No Features found

Potential Special Protection Areas (England) - points

No Features found

Potential Special Protection Areas (England)

No Features found

Biosphere Reserves (England) - points

No Features found

Biosphere Reserves (England)

No Features found

Less Favoured Areas (England)

No Features found

Nitrate Vulnerable Zones 2017 Designations (England)

No Features found

Wild Bird General Licence Protected Sites Condition Zone (England)

No Features found

Source Protection Zones merged (England)

No Features found

Rida Reports

4
Beanacre Road,
Hook Norton,
OX15 5UA

FAO:

How to contact us:

United Utilities Water Limited
Property Searches
Haweswater House
Lingley Mere Business Park
Great Sankey
Warrington
WA5 3LP

Telephone: 0370 7510101

E-mail: propertysearches@uuplc.co.uk

Your Ref: [0412] 22 Honor Street, Manchester, M13 0WY
Our Ref: UUPS-ORD-532416
Date: 22/11/2023

Dear Sirs

Location: 20 HONOR STREET, MANCHESTER, M13 0WY

I acknowledge with thanks your request dated 20/11/2023 for information on the location of our services.

Please find enclosed plans showing the approximate position of United Utilities' apparatus known to be in the vicinity of this site.

The enclosed plans are being provided to you subject to the United Utilities terms and conditions for both the wastewater and water distribution plans which are shown attached.

If you are planning works anywhere in the North West, please read United Utilities' access statement before you start work to check how it will affect our network. <http://www.unitedutilities.com/work-near-asset.aspx>.

I trust the above meets with your requirements and look forward to hearing from you should you need anything further.

If you have any queries regarding this matter please [contact us](#).

Yours Faithfully,



Karen McCormack
Property Searches Manager


TERMS AND CONDITIONS - WASTEWATER AND WATER DISTRIBUTION PLANS

These provisions apply to the public sewerage, water distribution and telemetry systems (including sewers which are the subject of an agreement under Section 104 of the Water Industry Act 1991 and mains installed in accordance with the agreement for the self construction of water mains) (UUWL apparatus) of United Utilities Water Limited "(UUWL)".

TERMS AND CONDITIONS:

- This Map and any information supplied with it is issued subject to the provisions contained below, to the exclusion of all others and no party relies upon any representation, warranty, collateral contract or other assurance of any person (whether party to this agreement or not) that is not set out in this agreement or the documents referred to in it.
- This Map and any information supplied with it is provided for general guidance only and no representation, undertaking or warranty as to its accuracy, completeness or being up to date is given or implied.
- In particular, the position and depth of any UUWL apparatus shown on the Map are approximate only. UUWL strongly recommends that a comprehensive survey is undertaken in addition to reviewing this Map to determine and ensure the precise location of any UUWL apparatus. The exact location, positions and depths should be obtained by excavation trial holes.
- The location and position of private drains, private sewers and service pipes to properties are not normally shown on this Map but their presence must be anticipated and accounted for and you are strongly advised to carry out your own further enquiries and investigations in order to locate the same.
- The position and depth of UUWL apparatus is subject to change and therefore this Map is issued subject to any removal or change in location of the same. The onus is entirely upon you to confirm whether any changes to the Map have been made subsequent to issue and prior to any works being carried out.
- This Map and any information shown on it or provided with it must not be relied upon in the event of any development, construction or other works (including but not limited to any excavations) in the vicinity of UUWL apparatus or for the purpose of determining the suitability of a point of connection to the sewerage or other distribution systems.
- No person or legal entity, including any company shall be relieved from any liability howsoever and whensoever arising for any damage caused to UUWL apparatus by reason of the actual position and/or depths of UUWL apparatus being different from those shown on the Map and any information supplied with it.
- If any provision contained herein is or becomes legally invalid or unenforceable, it will be taken to be severed from the remaining provisions which shall be unaffected and continue in full force and affect.
- This agreement shall be governed by English law and all parties submit to the exclusive jurisdiction of the English courts, save that nothing will prevent UUWL from bringing proceedings in any other competent jurisdiction, whether concurrently or otherwise.

Wastewater Symbolology



All point assets follow the standard colour convention: **red** – combined **brown** - foul
blue – surface water **purple** - overflow

Manhole	Side Entry Manhole
Head of System	Outfall
Extent of Survey	Screen Chamber
Rodding Eye	Inspection Chamber
Inlet	Bifurcation Chamber
Discharge Point	Lamp Hole
Vortex	T Junction / Saddle
Penstock	Catchpit
Washout Chamber	Valve Chamber
Valve	Vent Column
Air Valve	Vortex Chamber
Non Return Valve	Penstock Chamber
Soakaway	Network Storage Tank
Gully	Sewer Overflow
Cascade	Ww Treatment Works
Flow Meter	Ww Pumping Station
Hatch Box	Septic Tank
Oil Interceptor	Control Kiosk
Summit	
Drop Shaft	Change of Characteristic
Orifice Plate	



Water for the North West

SEWER RECORDS

Address or Site Reference


20 HONOR STREET,
MANCHESTER,
M13 0WY

Scale: 1:1250
Date: 22/11/2023

Printed by: Property Searches

The position of the underground apparatus shown on this plan is approximate only and is given in accordance with the best information currently available. United Utilities Water will not accept liability for any loss or damage caused by the actual position being different from those shown.

Crown copyright and database rights 2023
Ordnance Survey 100022432. Unauthorised
reproduction will infringe these copyrights.



Appendix C

Simulation Settings

Rainfall Methodology	FSR	Drain Down Time (mins)	240
FSR Region	England and Wales	Additional Storage (m ³ /ha)	20.0
M5-60 (mm)	17.000	Check Discharge Rate(s)	✓
Ratio-R	0.400	1 year (l/s)	0.1
Summer CV	0.950	2 year (l/s)	0.1
Winter CV	0.950	30 year (l/s)	0.1
Analysis Speed	Normal	100 year (l/s)	0.1
Skip Steady State	x	Check Discharge Volume	x

Storm Durations

15 | 30 | 60 | 120 | 180 | 240 | 360 | 480 | 600 | 720 | 960 | 1440

Return Period (years)	Climate Change (CC %)	Additional Area (A %)	Additional Flow (Q %)
1	0	0	0
2	0	0	0
30	0	0	0
30	40	0	0
100	0	0	0
100	40	0	0

Pre-development Discharge Rate

Site Makeup	Greenfield	Growth Factor 30 year	1.70
Greenfield Method	IH124	Growth Factor 100 year	2.08
Positively Drained Area (ha)	0.011	Betterment (%)	0
SAAR (mm)	879	QBar	0.1
Soil Index	4	Q 1 year (l/s)	0.1
SPR	0.47	Q 2 year (l/s)	0.1
Region	10	Q 30 year (l/s)	0.1
Growth Factor 1 year	0.87	Q 100 year (l/s)	0.1
Growth Factor 2 year	0.93		

Simulation Settings

Rainfall Methodology	FSR	Drain Down Time (mins)	240
FSR Region	England and Wales	Additional Storage (m ³ /ha)	20.0
M5-60 (mm)	17.000	Check Discharge Rate(s)	✓
Ratio-R	0.400	1 year (l/s)	0.9
Summer CV	0.950	2 year (l/s)	1.1
Winter CV	0.950	30 year (l/s)	2.1
Analysis Speed	Normal	100 year (l/s)	2.6
Skip Steady State	x	Check Discharge Volume	x

Storm Durations

15 | 30 | 60 | 120 | 180 | 240 | 360 | 480 | 600 | 720 | 960 | 1440

Return Period (years)	Climate Change (CC %)	Additional Area (A %)	Additional Flow (Q %)
1	0	0	0
2	0	0	0
30	0	0	0
30	40	0	0
100	0	0	0
100	40	0	0

Pre-development Discharge Rate

Site Makeup	Brownfield	Betterment (%)	0
Brownfield Method	MRM	Q 1 year (l/s)	0.9
Contributing Area (ha)	0.006	Q 2 year (l/s)	1.1
PIMP (%)	100	Q 30 year (l/s)	2.1
CV	0.950	Q 100 year (l/s)	2.6
Time of Concentration (mins)	6.00		

Design Settings

Rainfall Methodology	FSR	Maximum Time of Concentration (mins)	30.00
Return Period (years)	2	Maximum Rainfall (mm/hr)	50.0
Additional Flow (%)	0	Minimum Velocity (m/s)	1.00
FSR Region	England and Wales	Connection Type	Level Inverts
M5-60 (mm)	17.000	Minimum Backdrop Height (m)	0.200
Ratio-R	0.400	Preferred Cover Depth (m)	1.200
CV	0.950	Include Intermediate Ground	✓
Time of Entry (mins)	6.00	Enforce best practice design rules	✓

Adoptable Manhole Type

Max Width (mm)	Diameter (mm)	Max Width (mm)	Diameter (mm)
374	1200	749	1500
499	1350	900	1800

>900 Link+900 mm

Max Depth (m)	Diameter (mm)	Max Depth (m)	Diameter (mm)
1.500	1050	99.999	1200

Circular Link Type

Shape	Circular	Auto Increment (mm)	75
Barrels	1	Follow Ground	x

Available Diameters (mm)

100 | 150

Nodes

Name	Area (ha)	T of E (mins)	Cover Level (m)	Diameter (mm)	Easting (m)	Northing (m)	Depth (m)
Drainage Channel	0.004	6.00	48.394	150	3.459	-5.072	1.300
S01			48.422		10.046	0.029	1.577
S01	0.004	6.00	48.426	450	9.936	11.855	0.532
Flow Control			48.345	450	10.102	-4.791	1.620
Outfall			48.228	450	10.067	-10.021	1.553

Links

Name	US Node	DS Node	Length (m)	ks (mm) / n	US IL (m)	DS IL (m)	Fall (m)	Slope (1:X)	Dia (mm)	T of C (mins)	Rain (mm/hr)
1.000	S01	S01	5.000	0.600	47.894	46.845	1.049	4.8	100	6.02	50.0
1.001	S01	Flow Control	12.000	0.600	46.845	46.725	0.120	100.0	100	6.28	50.0
1.002	Flow Control	Outfall	5.000	0.600	46.725	46.675	0.050	100.0	100	6.39	50.0
2.000	Drainage Channel	Flow Control	6.649	0.600	47.094	46.981	0.113	58.8	100	6.11	50.0

Name	Vel (m/s)	Cap (l/s)	Flow (l/s)	US Depth (m)	DS Depth (m)	Σ Area (ha)	Σ Add Inflow (l/s)	Pro Depth (mm)	Pro Velocity (m/s)
1.000	3.566	28.0	0.7	0.432	1.477	0.004	0.0	11	1.457
1.001	0.769	6.0	0.7	1.477	1.520	0.004	0.0	23	0.511
1.002	0.769	6.0	1.4	1.520	1.453	0.008	0.0	32	0.621
2.000	1.006	7.9	0.7	1.200	1.264	0.004	0.0	20	0.613

Pipeline Schedule

Link	Length (m)	Slope (1:X)	Dia (mm)	Link Type	US CL (m)	US IL (m)	US Depth (m)	DS CL (m)	DS IL (m)	DS Depth (m)
1.000	5.000	4.8	100	Circular	48.426	47.894	0.432	48.422	46.845	1.477
1.001	12.000	100.0	100	Circular	48.422	46.845	1.477	48.345	46.725	1.520
1.002	5.000	100.0	100	Circular	48.345	46.725	1.520	48.228	46.675	1.453
2.000	6.649	58.8	100	Circular	48.394	47.094	1.200	48.345	46.981	1.264

Link	US Node	Dia (mm)	Node Type	MH Type	DS Node	Dia (mm)	Node Type	MH Type
1.000	SO1	450	Manhole	Adoptable	SO1		Junction	
1.001	SO1		Junction		Flow Control	450	Manhole	Adoptable
1.002	Flow Control	450	Manhole	Adoptable	Outfall	450	Manhole	Adoptable
2.000	Drainage Channel	150	Manhole	Adoptable	Flow Control	450	Manhole	Adoptable

Manhole Schedule

Node	Easting (m)	Northing (m)	CL (m)	Depth (m)	Dia (mm)	Connections	Link	IL (m)	Dia (mm)	
Drainage Channel	3.459	-5.072	48.394	1.300	150		0	2.000	47.094	100
SO1	10.046	0.029	48.422	1.577			1	1.000	46.845	100
						0	0	1.001	46.845	100
SO1	9.936	11.855	48.426	0.532	450		0	1.000	47.894	100
Flow Control	10.102	-4.791	48.345	1.620	450		1	2.000	46.981	100
						2	2	1.001	46.725	100
						0	0	1.002	46.725	100
Outfall	10.067	-10.021	48.228	1.553	450		1	1.002	46.675	100

Simulation Settings

Rainfall Methodology	FSR	Drain Down Time (mins)	240
FSR Region	England and Wales	Additional Storage (m³/ha)	20.0
M5-60 (mm)	17.000	Check Discharge Rate(s)	✓
Ratio-R	0.400	1 year (l/s)	0.9
Summer CV	0.950	2 year (l/s)	1.1
Winter CV	0.950	30 year (l/s)	2.1
Analysis Speed	Normal	100 year (l/s)	2.6
Skip Steady State	x	Check Discharge Volume	x

Storm Durations

15	30	60	120	180	240	360	480	600	720	960	1440
----	----	----	-----	-----	-----	-----	-----	-----	-----	-----	------

Return Period (years)	Climate Change (CC %)	Additional Area (A %)	Additional Flow (Q %)
1	0	0	0
2	0	0	0
30	0	0	0
30	40	0	0
100	0	0	0
100	40	0	0

Pre-development Discharge Rate

Site Makeup	Brownfield	Time of Concentration (mins)	6.00
Brownfield Method	MRM	Betterment (%)	0
Contributing Area (ha)	0.006	Q 1 year (l/s)	
PIMP (%)	100	Q 30 year (l/s)	
CV	0.950	Q 100 year (l/s)	

Node Flow Control Online Orifice Control

Flap Valve	x	Invert Level (m)	46.725	Diameter (m)	0.017
Downstream Link	1.002	Design Depth (m)	0.600	Discharge Coefficient	0.600
Replaces Downstream Link	✓	Design Flow (l/s)	0.5		

Node S01 Depth/Area Storage Structure

Base Inf Coefficient (m/hr)	0.00000	Safety Factor	2.0	Invert Level (m)	46.845
Side Inf Coefficient (m/hr)	0.00000	Porosity	0.96	Time to half empty (mins)	26

Depth (m)	Area (m ²)	Inf Area (m ²)	Depth (m)	Area (m ²)	Inf Area (m ²)	Depth (m)	Area (m ²)	Inf Area (m ²)	Depth (m)	Area (m ²)	Inf Area (m ²)
0.000	3.0	0.0	0.400	3.0	0.0	0.800	3.0	0.0	0.801	0.0	0.0

Rainfall

Event	Peak Intensity (mm/hr)	Average Intensity (mm/hr)	Event	Peak Intensity (mm/hr)	Average Intensity (mm/hr)
1 year 15 minute summer	92.521	26.180	1 year 960 minute summer	5.653	1.489
1 year 15 minute winter	64.927	26.180	1 year 960 minute winter	3.745	1.489
1 year 30 minute summer	60.022	16.984	1 year 1440 minute summer	4.127	1.106
1 year 30 minute winter	42.121	16.984	1 year 1440 minute winter	2.773	1.106
1 year 60 minute summer	40.398	10.676	2 year 15 minute summer	119.760	33.888
1 year 60 minute winter	26.839	10.676	2 year 15 minute winter	84.042	33.888
1 year 120 minute summer	24.980	6.602	2 year 30 minute summer	77.518	21.935
1 year 120 minute winter	16.596	6.602	2 year 30 minute winter	54.399	21.935
1 year 180 minute summer	19.271	4.959	2 year 60 minute summer	51.720	13.668
1 year 180 minute winter	12.527	4.959	2 year 60 minute winter	34.361	13.668
1 year 240 minute summer	15.301	4.043	2 year 120 minute summer	31.549	8.338
1 year 240 minute winter	10.165	4.043	2 year 120 minute winter	20.961	8.338
1 year 360 minute summer	11.775	3.030	2 year 180 minute summer	24.133	6.210
1 year 360 minute winter	7.654	3.030	2 year 180 minute winter	15.687	6.210
1 year 480 minute summer	9.342	2.469	2 year 240 minute summer	19.039	5.032
1 year 480 minute winter	6.207	2.469	2 year 240 minute winter	12.649	5.032
1 year 600 minute summer	7.682	2.101	2 year 360 minute summer	14.516	3.735
1 year 600 minute winter	5.249	2.101	2 year 360 minute winter	9.436	3.735
1 year 720 minute summer	6.859	1.838	2 year 480 minute summer	11.436	3.022
1 year 720 minute winter	4.609	1.838	2 year 480 minute winter	7.598	3.022

Rainfall

Event	Peak Intensity (mm/hr)	Average Intensity (mm/hr)	Event	Peak Intensity (mm/hr)	Average Intensity (mm/hr)
2 year 600 minute summer	9.363	2.561	30 year +40% CC 960 minute summer	17.189	4.526
2 year 600 minute winter	6.398	2.561	30 year +40% CC 960 minute winter	11.387	4.526
2 year 720 minute summer	8.339	2.235	30 year +40% CC 1440 minute summer	12.303	3.297
2 year 720 minute winter	5.605	2.235	30 year +40% CC 1440 minute winter	8.269	3.297
2 year 960 minute summer	6.846	1.803	100 year 15 minute summer	291.766	82.560
2 year 960 minute winter	4.535	1.803	100 year 15 minute winter	204.748	82.560
2 year 1440 minute summer	4.967	1.331	100 year 30 minute summer	191.982	54.324
2 year 1440 minute winter	3.338	1.331	100 year 30 minute winter	134.724	54.324
30 year 15 minute summer	226.195	64.005	100 year 60 minute summer	129.253	34.158
30 year 15 minute winter	158.733	64.005	100 year 60 minute winter	85.873	34.158
30 year 30 minute summer	147.452	41.724	100 year 120 minute summer	78.836	20.834
30 year 30 minute winter	103.475	41.724	100 year 120 minute winter	52.377	20.834
30 year 60 minute summer	98.615	26.061	100 year 180 minute summer	59.966	15.431
30 year 60 minute winter	65.517	26.061	100 year 180 minute winter	38.980	15.431
30 year 120 minute summer	59.946	15.842	100 year 240 minute summer	46.975	12.414
30 year 120 minute winter	39.827	15.842	100 year 240 minute winter	31.209	12.414
30 year 180 minute summer	45.598	11.734	100 year 360 minute summer	35.264	9.075
30 year 180 minute winter	29.640	11.734	100 year 360 minute winter	22.923	9.075
30 year 240 minute summer	35.759	9.450	100 year 480 minute summer	27.350	7.228
30 year 240 minute winter	23.758	9.450	100 year 480 minute winter	18.171	7.228
30 year 360 minute summer	26.939	6.932	100 year 600 minute summer	22.137	6.055
30 year 360 minute winter	17.511	6.932	100 year 600 minute winter	15.126	6.055
30 year 480 minute summer	20.981	5.545	100 year 720 minute summer	19.562	5.243
30 year 480 minute winter	13.940	5.545	100 year 720 minute winter	13.147	5.243
30 year 600 minute summer	17.039	4.661	100 year 960 minute summer	15.851	4.174
30 year 600 minute winter	11.642	4.661	100 year 960 minute winter	10.500	4.174
30 year 720 minute summer	15.093	4.045	100 year 1440 minute summer	11.278	3.023
30 year 720 minute winter	10.143	4.045	100 year 1440 minute winter	7.579	3.023
30 year 960 minute summer	12.278	3.233	100 year +40% CC 15 minute summer	408.473	115.584
30 year 960 minute winter	8.133	3.233	100 year +40% CC 15 minute winter	286.647	115.584
30 year 1440 minute summer	8.788	2.355	100 year +40% CC 30 minute summer	268.775	76.054
30 year 1440 minute winter	5.906	2.355	100 year +40% CC 30 minute winter	188.614	76.054
30 year +40% CC 15 minute summer	316.673	89.607	100 year +40% CC 60 minute summer	180.954	47.821
30 year +40% CC 15 minute winter	222.226	89.607	100 year +40% CC 60 minute winter	120.222	47.821
30 year +40% CC 30 minute summer	206.433	58.413	100 year +40% CC 120 minute summer	110.370	29.168
30 year +40% CC 30 minute winter	144.865	58.413	100 year +40% CC 120 minute winter	73.327	29.168
30 year +40% CC 60 minute summer	138.061	36.485	100 year +40% CC 180 minute summer	83.953	21.604
30 year +40% CC 60 minute winter	91.724	36.485	100 year +40% CC 180 minute winter	54.572	21.604
30 year +40% CC 120 minute summer	83.924	22.179	100 year +40% CC 240 minute summer	65.765	17.380
30 year +40% CC 120 minute winter	55.757	22.179	100 year +40% CC 240 minute winter	43.693	17.380
30 year +40% CC 180 minute summer	63.837	16.427	100 year +40% CC 360 minute summer	49.370	12.705
30 year +40% CC 180 minute winter	41.495	16.427	100 year +40% CC 360 minute winter	32.092	12.705
30 year +40% CC 240 minute summer	50.063	13.230	100 year +40% CC 480 minute summer	38.291	10.119
30 year +40% CC 240 minute winter	33.261	13.230	100 year +40% CC 480 minute winter	25.439	10.119
30 year +40% CC 360 minute summer	37.715	9.705	100 year +40% CC 600 minute summer	30.992	8.477
30 year +40% CC 360 minute winter	24.516	9.705	100 year +40% CC 600 minute winter	21.176	8.477
30 year +40% CC 480 minute summer	29.374	7.763	100 year +40% CC 720 minute summer	27.387	7.340
30 year +40% CC 480 minute winter	19.515	7.763	100 year +40% CC 720 minute winter	18.406	7.340
30 year +40% CC 600 minute summer	23.854	6.525	100 year +40% CC 960 minute summer	22.191	5.844
30 year +40% CC 600 minute winter	16.299	6.525	100 year +40% CC 960 minute winter	14.700	5.844
30 year +40% CC 720 minute summer	21.130	5.663	100 year +40% CC 1440 minute summer	15.789	4.232
30 year +40% CC 720 minute winter	14.201	5.663	100 year +40% CC 1440 minute winter	10.611	4.232

Results for 1 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
15 minute summer	Drainage Channel	12	47.111	0.017	0.5	0.0014	0.0000	OK
60 minute summer	S01	41	46.894	0.049	0.6	0.1423	0.0000	OK
15 minute summer	SO1	10	47.903	0.009	0.5	0.0029	0.0000	OK
60 minute summer	Flow Control	42	46.895	0.170	0.7	0.0270	0.0000	SURCHARGED
15 minute summer	Outfall	1	46.675	0.000	0.2	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
15 minute summer	Drainage Channel	2.000	Flow Control	0.5	0.555	0.063	0.0060	
60 minute summer	S01	1.001	Flow Control	0.3	0.104	0.056	0.0701	
15 minute summer	SO1	1.000	S01	0.5	1.296	0.018	0.0075	
60 minute summer	Flow Control	Orifice	Outfall	0.2				0.8

Results for 2 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
15 minute summer	Drainage Channel	11	47.115	0.021	0.7	0.0016	0.0000	OK
30 minute winter	S01	27	46.924	0.079	0.8	0.2273	0.0000	OK
15 minute summer	SO1	11	47.905	0.011	0.7	0.0034	0.0000	OK
60 minute summer	Flow Control	42	46.924	0.199	0.7	0.0317	0.0000	SURCHARGED
15 minute summer	Outfall	1	46.675	0.000	0.3	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
15 minute summer	Drainage Channel	2.000	Flow Control	0.7	0.612	0.088	0.0076	
30 minute winter	S01	1.001	Flow Control	0.4	0.105	0.064	0.0867	
15 minute summer	SO1	1.000	S01	0.7	1.296	0.025	0.0130	
60 minute summer	Flow Control	Orifice	Outfall	0.3				1.1

Results for 30 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
15 minute summer	Drainage Channel	11	47.121	0.027	1.2	0.0022	0.0000	OK
60 minute winter	S01	50	47.076	0.231	0.9	0.6665	0.0000	SURCHARGED
15 minute summer	SO1	10	47.908	0.014	1.2	0.0044	0.0000	OK
60 minute winter	Flow Control	49	47.076	0.351	0.7	0.0559	0.0000	SURCHARGED
15 minute summer	Outfall	1	46.675	0.000	0.3	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
15 minute summer	Drainage Channel	2.000	Flow Control	1.2	0.711	0.152	0.0143	
60 minute winter	S01	1.001	Flow Control	0.3	0.104	0.050	0.0939	
15 minute summer	SO1	1.000	S01	1.2	1.297	0.043	0.0212	
60 minute winter	Flow Control	Orifice	Outfall	0.4				1.9

Results for 30 year +40% CC Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	Drainage Channel	50	47.203	0.109	0.9	0.0086	0.0000	SURCHARGED
60 minute winter	S01	49	47.203	0.358	1.1	1.0320	0.0000	SURCHARGED
15 minute summer	SO1	11	47.911	0.017	1.7	0.0052	0.0000	OK
60 minute winter	Flow Control	49	47.203	0.478	0.9	0.0760	0.0000	SURCHARGED
15 minute summer	Outfall	1	46.675	0.000	0.4	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	Drainage Channel	2.000	Flow Control	0.9	0.656	0.114	0.0520	
60 minute winter	S01	1.001	Flow Control	0.3	0.120	0.053	0.0939	
15 minute summer	SO1	1.000	SO1	1.7	1.379	0.061	0.0217	
60 minute winter	Flow Control	Orifice	Outfall	0.4				2.8

Results for 100 year Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	Drainage Channel	49	47.173	0.079	0.9	0.0062	0.0000	OK
60 minute winter	S01	48	47.173	0.328	1.1	0.9435	0.0000	SURCHARGED
15 minute summer	SO1	11	47.910	0.016	1.6	0.0050	0.0000	OK
60 minute winter	Flow Control	49	47.172	0.447	0.9	0.0711	0.0000	SURCHARGED
15 minute summer	Outfall	1	46.675	0.000	0.4	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	Drainage Channel	2.000	Flow Control	0.9	0.648	0.114	0.0480	
60 minute winter	S01	1.001	Flow Control	0.3	0.113	0.042	0.0939	
15 minute summer	SO1	1.000	SO1	1.6	1.512	0.057	0.0216	
60 minute winter	Flow Control	Orifice	Outfall	0.4				2.6

Results for 100 year +40% CC Critical Storm Duration. Lowest mass balance: 100.00%

Node Event	US Node	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Node Vol (m³)	Flood (m³)	Status
60 minute winter	Drainage Channel	52	47.336	0.242	1.2	0.0191	0.0000	SURCHARGED
60 minute winter	S01	52	47.336	0.491	1.5	1.4149	0.0000	SURCHARGED
15 minute summer	SO1	11	47.913	0.019	2.2	0.0059	0.0000	OK
60 minute winter	Flow Control	52	47.336	0.611	1.2	0.0971	0.0000	SURCHARGED
15 minute summer	Outfall	1	46.675	0.000	0.4	0.0000	0.0000	OK

Link Event (Upstream Depth)	US Node	Link	DS Node	Outflow (l/s)	Velocity (m/s)	Flow/Cap	Link Vol (m³)	Discharge Vol (m³)
60 minute winter	Drainage Channel	2.000	Flow Control	1.2	0.669	0.152	0.0520	
60 minute winter	S01	1.001	Flow Control	0.3	0.126	0.052	0.0939	
15 minute summer	SO1	1.000	SO1	2.2	1.379	0.079	0.0221	
60 minute winter	Flow Control	Orifice	Outfall	0.5				3.6

Appendix D

Drawing scale	Line length	Drawing scale	Line length
1:5	= 0.25 metres	1:200	= 10.0 metres
1:10	= 0.5 metres	1:250	= 12.5 metres
1:20	= 1.0 metres	1:500	= 25.0 metres
1:25	= 1.25 metres	1:1000	= 50.0 metres
1:50	= 2.5 metres	1:1250	= 62.5 metres
1:100	= 5.0 metres	1:2500	= 125 metres

Measure length of line above for checking of scale

GENERAL NOTES

- All dimensions are in millimetres and levels in m AOD unless stated otherwise.
- Do not scale. If in any doubt, consult Engineer.
- Read in conjunction with the architects and engineers schedule drawings.
- Check inverts and sizes of existing pipes prior to the commencement of any work. Report any discrepancies to the engineer and await instructions.
- The location of services is shown as indicative. This drawing should be read in conjunction with the utilities drawings. No warranty to their accuracy can be given. The contractor shall take all necessary measures to satisfy himself as to the location of the existing services and connection points. Excavation should be undertaken in compliance with HSG47.
- Concrete structures design sulphate class and ACEC concrete class unknown.
- Pipework to be 110mm Thermoplastics U-PVC (Polypipe or similar) installed at levels marked on this drawing UNO. Pipe bedding should be class Z in pipes within 1.5m of the building or shallower than 700mm below ground level. For all other areas the pipe bedding should be class S.
- Joints and fittings for gravity sewers shall comply with the relevant provisions of BS EN 1401-1, BS EN 1852 and BS EN 12666-1. Pipes shall have a limit of 6% deformation. Pipes shall be SN8 ring stiffness and stamped accordingly. Pipe sections shall not be longer than 3m.
- Plastic chambers and rings, including demarcation chambers, shall comply with BS EN 3598-1 or BS EN 13598-2 as appropriate.
- Inspection chamber covers and frames shall comply with the relevant provisions of BS EN 124 and should be double sealed.
- All inspection chamber covers shall be the non-ventilating type and shall have closed keyways.
- Testing of pipelines should be as follow:
Gravity Pipework: Air pipe testing. Pipework should withstand a pressure of 100mm water gauge and this should not fall by more than 25mm in a 5minute period. However where traps or gullies are connected they should withstand a pressure of 50mm water gauge and this should not fall by more than 12mm in a 5minute period. It is recommended that pipework installations are tested in sections rather than waiting to complete in one operation.
- Manhole covers to be set square to the building. Covers of existing manholes to be adjusted to match final ground levels.
- Granular Bedding for pipes shall be constructed by spreading and compacting granular bedding material over the full width of the pipe trench. After the pipes have been laid, additional granular material shall, if required, be placed and compacted equally on each side of the pipes and, where practicable, this shall be done in sequence with the removal of the trench supports.


Rev	Details	Date	By	Chd

Drawing Status: **PRELIMINARY**



Client:
Project:
22 Honor Street, Manchester, M13 0WY
Drawing:
Proposed Drainage Strategy

Print Size: A1 Scale: 1:50 Project No: 0412 Drawing No: 003 Revision: P1



BASEMENT DRAINAGE PLAN
1:50

GROUND FLOOR DRAINAGE PLAN
1:50

KEY

- Proposed Surface Water Sewer Pipe
- Exceedance Flows
- Linear Drainage Channel
- Silt Trap
- Existing Combined Sewer Pipe

Typical Section in areas subject to vehicle loading

Sited in domestic driveways or footways

Sited in private garden - No loading

Notes:

1. Refer to drawing 8193 for base layouts

Chamber Type 3 Base Layouts

NOTES:

1. Permeable modular storage cell with 95% minimum void ratio. Ultimate compressive strength of 400kN/m² minimum. Resistant to chemicals likely to be found in rain water and durability of a minimum of 40 years.
2. Dimensions as applicable to the manufacturers recommendations for given storage requirement UNO.
3. Air Vents should be provided as per suppliers recommendations
4. See GA drgs for pipe sizes and layout and IL, ILoS, ToS, GL levels.

ASPHALT PAVEMENT

CONCRETE PAVEMENT

BLOCK PAVEMENT (OPTION 1 & 2)

Load Class		A15	B125	C250	D400*	F900
Minimum Dimensions (mm)	X	100	150	150	250	300
	Y	Full Channel Height (Less Y2 where necessary)				
	Z	100	150	150	250	300
Maximum Dimensions (mm)	Y ₂ *	35	35	35	35	35
	Y ₁	100	60	60	60	35

8341 - Linear Drainage Channel Detail (Steel)

8250 - External Rainwater (High Level)

Pipe Bedding Detail Type Z

Pipe Bedding Detail Type S

Typical Section in areas subject to vehicle loading

Sited in domestic driveways or footways

Sited in soft landscaped areas

Plan view

NOTES

1. Refer to GA drg for pipe layout.
2. Chamber can be fabricated by Seel Environmental UK

Flow Control -Orifice Plate - Plastic - Type 3

PLAN VIEW

SECTION VIEW

NOTES:

1. The vertical angle between the connecting pipe and the horizontal should be greater than 0° and not more than 60°.
2. Where the connection is being made to a sewer with a nominal internal diameter of 300 mm or less, connections should be made using 45° angle, or 90° angle, curved square junctions.
3. Connections made with junction fittings should be made by cutting the existing pipe, inserting the junction fitting and jointing with flexible repair couplings or slip couplers.

Lateral Connection to private sewer

External Rodding Eye Detail

Cross-Sectional View of Sewer

Plan View of Sewer

NOTES:

1. The vertical angle between the connecting pipe and the horizontal should be greater than 0° and not more than 60° .
2. Where the connection is being made to a sewer with a nominal internal diameter of 300 mm or less, connections should be made using 45° angle, or 60° angle, curved square junctions.
3. Connections made with junction fittings should be made by cutting the existing pipe, inserting the junction fitting and joining with flexible repair couplings or slip couplers.
4. Where the connection is being made to a sewer with a nominal internal diameter greater than 300 mm:
 - a) Where the diameter of the connecting pipe is greater than half the diameter of the sewer, the connection of an access point should be constructed as shown in Figure 10.10.
 - b) Where the diameter of the connecting pipe is less than or equal to half the diameter of the sewer, then the connection should be made using a preformed saddle fitting.

Lateral Connection to public sewer

Drawing Scale Bar			
Drawing scale	Line length	Drawing scale	Line length
1:5	= 0.25 metres	1:200	= 10.0 metres
1:10	= 0.5 metres	1:250	= 12.5 metres
1:20	= 1.0 metres	1:500	= 25.0 metres
1:25	= 1.25 metres	1:1000	= 50.0 metres
1:50	= 2.5 metres	1:1250	= 62.5 metres
1:100	= 5.0 metres	1:2500	= 125 metres

Measure length of line above for checking of scale

GENERAL NOTES

