

Window Schedule - North				
Mark	Height (mm)	Width (mm)	Required	Description

Level 00					
00-012	1500	1280	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
00-013A	983	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Electrical Window Actuators required / Blinds	
00-013B	1670	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
00-014A	983	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Electrical Window Actuators required / Blinds	
00-014B	1670	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
00-015A	983	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Electrical Window Actuators required / Blinds	
00-015B	1670	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
00-016A	983	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Electrical Window Actuators required / Blinds	
00-016B	1670	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
00-017A	983	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Electrical Window Actuators required / Blinds	
00-017B	1670	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
00-018A	983	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Electrical Window Actuators required / Blinds	
00-018B	1670	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
00-019A	983	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Electrical Window Actuators required / Blinds	



1 Proposed Glazing Window Alterations_North Elevation
1 : 100

Window Schedule - North				
Mark	Height (mm)	Width (mm)	Required	Description

00-019B	1670	1035	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
---------	------	------	---	--------

[illegible]

Level 02				
02-012A	950	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-012B	1500	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-012C	950	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-012D	1500	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-012E	950	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-012F	1500	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-013	1810	1020	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-014	1810	1020	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-015	1810	1020	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-016	1810	1020	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-017	1810	1020	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-018	1810	823	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds
02-019	1810	823	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds

Level 03					
03-002A	950	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
03-002B	1500	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
03-002C	950	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
03-002D	1500	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
03-002E	950	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	
03-002F	1500	917	New timber casements to match existing, Glazing replaced with vacuum glazed system, frames refurbished weather seals installed and air tightness system applied as spec	Blinds	

Notes: <ul style="list-style-type: none">This drawing is copyright.Do not scale dimensions from this drawing.This drawing is to be read in conjunction with all other relevant drawings.All discrepancies on this drawing are to be reported to the architect.Do not modify any element of this drawing.Use drawing only for purpose(s) issued.This drawing may contain colour.						North Point	
Scale Bar 0 1m 3m 5m Scale: 1:100							
Key Plan							
The following external model files are included within this drawing:							
P5	2023/12/01	Listed Building Consent Submission.				AB	RM
P4	2023/10/06	Stage 4 Issue for Costing				AB	RM
P3	2023/08/04	Drawings issued for LBC Application				AB	RM
P2	2023/07/21	Preliminary issue to Heritage Consultant				AB	RM
P1	2023/06/02	Stage 3 Preliminary Issue for costing				AB	RM
Rev	Date	Revision Notes				Drawn	Review
 The University of Manchester							
Project: Rutherford Building							
Drawing Title: Window + External Door Schedule_North Elevation							
Job Number 141532	Date FEB'23	Security Classification				Drawn By MTW	
Scale@A1 1 : 100	Purpose LISTED BUILDING CONSENT					Reviewed By RM	
Drawing Number 3213-RBUM-ARC-XX-ZZ-SH-A-3213						Revision P5	