

UP STREAM MH DETAILS								
MH	CL	IL	DEPTH TO SOFFIT	MH SIZE	MH TYPE	OPENING	COVER SIZE	COVER TYPE / REFERENCE
F1	66.350	65.750	0.500	460	PPIC	460	540x540	URP760 RECESSED
F2	66.350	65.710	0.540	460	PPIC	460	540x540	URP760 RECESSED
F3	66.700	65.675	0.925	460	PPIC	460	540x540	URP760 RECESSED
F4	66.700	65.360	1.240	460	PPIC	350	540x540	URP760 RECESSED
F5	66.550	65.285	1.165	460	PPIC	350	540x540	URP760 RECESSED
F6	66.550	65.230	1.220	460	PPIC	350	540x540	URP760 RECESSED
F7	66.500	64.325	2.025	1200	Type B	600x600	600x600	SOLID - D400
F8	66.350	65.600	0.600	460	PPIC	460	540x540	URP760 RECESSED
F9	66.350	65.570	0.630	460	PPIC	460	540x540	URP760 RECESSED
F10	66.350	65.600	0.650	460	PPIC	460	540x540	URP760 RECESSED
F11	66.350	65.600	0.650	460	PPIC	460	540x540	URP760 RECESSED
F12	66.350	65.600	0.650	460	PPIC	460	540x540	URP760 RECESSED
F13	66.350	65.600	0.650	460	PPIC	460	540x540	URP760 RECESSED
F14	66.350	65.600	0.650	460	PPIC	460	540x540	URP760 RECESSED
F15	66.350	65.600	0.650	460	PPIC	460	540x540	URP760 RECESSED
F16	66.350	65.150	1.050	460	PPIC	350	540x540	URP760 RECESSED
F17	66.700	64.210	2.340	1200	Type B	600x600	600x600	SOLID - D400

S1	66.350	65.600	0.600	150	Rodding Eye			
S2	66.350	65.480	0.720	460	PPIC	460	540x540	URP760 RECESSED
S3	66.350	65.600	0.600	150	Rodding Eye			
S4	66.350	65.340	0.860	460	PPIC	460	540x540	URP760 RECESSED
S5	66.700	65.950	0.600	150	Rodding Eye			
S6	66.700	65.140	1.410	460	PPIC	350	540x540	URP760 RECESSED
S7	66.625	65.800	0.675	150	Rodding Eye			
S8	66.550	65.800	0.600	460	PPIC	460	540x540	URP760 RECESSED
S9	66.550	65.675	0.725	460	PPIC	460	540x540	URP760 RECESSED
S10	66.550	64.955	1.445	1500	Type E	1200	750x600	SOLID - D400
S11	66.250	64.965	0.910	1500	Type E	1200	750x600	SOLID - D400
S12	66.550	64.650	1.525	1500	Type B	1200	600x600	SOLID - D400
S13	66.35	65.6	0.600	460	PPIC	460	540x540	URP760 RECESSED
S14	66.35	65.405	0.795	460	PPIC	460	540x540	URP760 RECESSED
S15	66.35	64.825	1.375	460	PPIC	350	540x540	URP760 RECESSED
S16	66.750	64.415	1.960	1500	Type B	1200	600x600	SOLID - D400
S17	66.350	65.600	0.600	460	PPIC	460	540x540	URP760 RECESSED
S18	66.350	65.350	0.850	460	PPIC	460	540x540	URP760 RECESSED
S19	66.250	64.595	1.280	1500	Type E	1200	750x600	SOLID - D400
S20	66.300	64.480	1.445	1500	Type E	1200	750x600	SOLID - D400
S21	66.350	64.900	1.300	460	PPIC	350	540x540	URP760 RECESSED
S22	66.350	64.650	1.550	460	PPIC	350	540x540	URP760 RECESSED
S23	66.400	64.385	1.640	1500	Type B	1200	600x600	SOLID - D400
S24	66.750	64.280	2.095	1500	Type B	1200	600x600	SOLID - D400
S25/FC	66.750	64.260	2.115	1500	Type B	1200	600x600	SOLID - D400
S26	TBC	TBC	TBC	1500	Type B	1200	600x600	SOLID - D400

OUTLET PIPE DETAILS			DOWN STREAM MH DETAILS			NOTES / COMMENTD
PIPE SIZE	PIPE GRADIENT	PIPE LENGTH	D / S MH	D / S CL	D / S IL	
100	80	2.25	F2	66.350	65.710	Polypipe Inspection Chamber
100	80	28.15	F4	66.700	65.360	Polypipe Inspection Chamber
100	10	3.10	F4	66.700	65.360	Polypipe Inspection Chamber
100	80	6.10	F5	66.550	65.285	Polypipe Inspection Chamber with 350mm Reduced Opening
100	80	4.50	F6	66.550	65.230	Polypipe Inspection Chamber with 350mm Reduced Opening
100	17	14.65	F7	66.500	64.375	Polypipe Inspection Chamber with 350mm Reduced Opening
150	145	16.55	F17	66.700	64.210	PCC Manhole
150	80	2.55	F2	66.350	65.570	Polypipe Inspection Chamber
150	80	33.44	F16	66.350	65.150	Polypipe Inspection Chamber
100	-	1.00	Junction onto Main Drainage			Polypipe Inspection Chamber
100	-	1.00	Junction onto Main Drainage			Polypipe Inspection Chamber
100	-	1.00	Junction onto Main Drainage			Polypipe Inspection Chamber
100	-	1.00	Junction onto Main Drainage			Polypipe Inspection Chamber
100	-	1.00	Junction onto Main Drainage			Polypipe Inspection Chamber
100	-	1.00	Junction onto Main Drainage			Polypipe Inspection Chamber
150	9	8.25	F17	66.700	64.210	Polypipe Inspection Chamber with 350mm Reduced Opening
150	145	18.70	EX FWMH 1	65.780 (tbc)	64.080 (tbc)	PCC Manhole

150	80	9.40	S2	66.350	65.480	Rodding Eye
150	80	11.00	S4	66.350	65.340	Polypipe Inspection Chamber
150	36	9.40	S4	66.350	65.340	Rodding Eye
150	80	16.20	S6	66.700	65.140	Polypipe Inspection Chamber
150	12	9.50	S6	66.700	65.140	Rodding Eye
150	80	14.80	S10	66.550	64.955	Polypipe Inspection Chamber with 350mm Reduced Opening
150	11	9.50	S10	66.550	64.955	Rodding Eye
150	80	9.50	S9	66.550	65.675	Polypipe Inspection Chamber
150	80	14.75	S10	66.550	64.955	Polypipe Inspection Chamber
150	80	6.25	S12	66.550	64.875	PCC Manhole
375	100	31.55	S12	66.550	64.650	PCC Manhole
375	150	35.15	S13	66.750	64.415	PCC Manhole
150	80	15.70	S14	66.350	65.405	Polypipe Inspection Chamber
150	30	17.90	S15	66.350	64.825	Polypipe Inspection Chamber
150	6	13.00	Junction onto Main Drainage			Polypipe Inspection Chamber with 350mm Reduced Opening
375	34	4.55	S24	66.750	64.280	PCC Manhole
150	80	19.80	S18	66.350	65.350	Polypipe Inspection Chamber
150	28	14.70	S19	66.250	64.820	Polypipe Inspection Chamber
375	150	17.50	S20	66.300	64.480	PCC Manhole
375	150	14.35	S23	66.400	64.385	PCC Manhole
150	80	19.90	S22	66.350	64.650	Polypipe Inspection Chamber with 350mm Reduced Opening
150	80	3.40	S23	66.400	64.610	Polypipe Inspection Chamber with 350mm Reduced Opening
375	150	16.05	S24	66.750	64.280	PCC Manhole
375	150.0	3.00	S24/FC	66.750	64.260	PCC Manhole
375	100.0	5.00	S26	65.750	64.210	PCC Manhole
EX 600	-	-	-	-	-	PCC Manhole

P1	Preliminary Issue	MDS	05.05.23
----	-------------------	-----	----------

rev	amendments	by	date
-----	------------	----	------



Client:
Watson Construction Ltd

Project:
Levenshulme Road, Gorton

Title:
Below Ground Drainage
Manhole and Pipe Schedule

Drawing Status: Preliminary	Date Created: May '23	Drawing Scale: N.T.S
--------------------------------	--------------------------	-------------------------

23-2405/ A1 / 203 P1

Project Leader: LS	Drawn By: MS	Initial Review: LS
-----------------------	-----------------	-----------------------

Preliminary Issue - For Discussion Purposes Only