

The Alan Johnston Partnership		Page 1
1 Dale Street Liverpool L2 2ET	223-008 Benmore Road, Manchester Proposed S.W Network	
Date 01/06/2023 File 223-008 Proposed S.W Ne...	Designed by JCM Checked by JLS	
XP Solutions Network 2020.1		
<p style="text-align: center;"><u>Synthetic Rainfall Details</u></p> <p style="text-align: center;">Cv (Summer) 0.750 Storm Duration (mins) 30 Cv (Winter) 0.840</p>		
©1982-2020 Innovyze		

The Alan Johnston Partnership		Page 2
1 Dale Street Liverpool L2 2ET	223-008 Benmore Road, Manchester Proposed S.W Network	
Date 01/06/2023 File 223-008 Proposed S.W Ne...	Designed by JCM Checked by JLS	
XP Solutions	Network 2020.1	

Online Controls for 223-008 S.W NETWORK.SWS


Hydro-Brake® Optimum Manhole: 4, DS/PN: 1.004, Volume (m³): 21.9

Unit Reference	MD-SHE-0100-5000-1350-5000
Design Head (m)	1.350
Design Flow (l/s)	5.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	100
Invert Level (m)	98.431
Minimum Outlet Pipe Diameter (mm)	150
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	1.350	5.0
Flush-Flo™	0.400	5.0
Kick-Flo®	0.829	4.0
Mean Flow over Head Range	-	4.4

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	3.3	1.200	4.7	3.000	7.3	7.000	10.9
0.200	4.6	1.400	5.1	3.500	7.8	7.500	11.2
0.300	4.9	1.600	5.4	4.000	8.3	8.000	11.6
0.400	5.0	1.800	5.7	4.500	8.8	8.500	11.9
0.500	5.0	2.000	6.0	5.000	9.2	9.000	12.2
0.600	4.8	2.200	6.3	5.500	9.7	9.500	12.6
0.800	4.2	2.400	6.5	6.000	10.1		
1.000	4.4	2.600	6.8	6.500	10.5		

The Alan Johnston Partnership		Page 3
1 Dale Street Liverpool L2 2ET	223-008 Benmore Road, Manchester Proposed S.W Network	
Date 01/06/2023	Designed by JCM	
File 223-008 Proposed S.W Ne...	Checked by JLS	
XP Solutions	Network 2020.1	

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for 223-008 S.W NETWORK.SWS

Simulation Criteria

Number of Input Hydrographs	0	Number of Storage Structures	0
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

```
Margin for Flood Risk Warning (mm) 300.0      DVD Status ON
      Analysis Timestep  Fine Inertia Status ON
      DTS Status      ON
```

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 45

PN	US/MH		Storm	Return Period	Climate Change	First (X) SurchARGE	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water
	Name									Level (m)
1.000	8	15	Winter	2	+0%	100/15	Summer			99.693
1.001	7	60	Winter	2	+0%	100/120	Winter			98.767
1.002	6	60	Winter	2	+0%	100/120	Winter			98.767
1.003	5	60	Winter	2	+0%	100/120	Winter			98.767
1.004	4	60	Winter	2	+0%	2/15	Summer			98.767
1.005	3	60	Winter	2	+0%					98.312
1.006	2	60	Winter	2	+0%					97.967

PN	US/MH	Surcharged	Flooded	Flow / Cap.	Overflow	Half Drain	Pipe	Status	Level
	Name	Depth (m)	Volume (m³)		(l/s)	Time (mins)	Flow (l/s)		Exceeded
1.000	8	-0.132	0.000	0.35			12.2		OK
1.001	7	-0.974	0.000	0.01			9.4		OK
1.002	6	-0.958	0.000	0.01			9.3		OK
1.003	5	-0.888	0.000	0.01			4.8		OK
1.004	4	0.112	0.000	0.11			5.0	SURCHARGED	
1.005	3	-0.177	0.000	0.10			5.0		OK
1.006	2	-0.191	0.000	0.06			5.0		OK

The Alan Johnston Partnership		Page 5
1 Dale Street Liverpool L2 2ET	223-008 Benmore Road, Manchester Proposed S.W Network	
Date 01/06/2023	Designed by JCM	
File 223-008 Proposed S.W Ne...	Checked by JLS	
XP Solutions	Network 2020.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for 223-008 S.W NETWORK.SWS

Simulation Criteria

Number of Input Hydrographs	0	Number of Storage Structures	0
Number of Online Controls	1	Number of Time/Area Diagrams	0
Number of Offline Controls	0	Number of Real Time Controls	0

Synthetic Rainfall Details

```
Margin for Flood Risk Warning (mm) 300.0      DVD Status ON
      Analysis Timestep    Fine Inertia Status ON
      DTS Status          ON
```

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 240, 360, 480, 960, 1440
Return Period(s) (years)	2, 30, 100
Climate Change (%)	0, 0, 45

										Water	
PN	US/MH		Storm	Return Period	Climate Change	First (X)		First (Y)	First (Z)	Overflow	Level (m)
	Name					Surcharge	Flood	Overflow	Act.		
1.000	8	15	Winter	100	+45%	100/15	Summer				99.866
1.001	7	120	Winter	100	+45%	100/120	Winter				99.801
1.002	6	120	Winter	100	+45%	100/120	Winter				99.801
1.003	5	120	Winter	100	+45%	100/120	Winter				99.801
1.004	4	120	Winter	100	+45%	2/15	Summer				99.801
1.005	3	120	Winter	100	+45%						98.312
1.006	2	120	Winter	100	+45%						97.967

PN	US/MH Name	Surcharged		Flooded	Flow / Cap.	Overflow (l/s)	Half Drain	Pipe	Status	Level Exceeded
		Depth (m)	Volume (m³)	Time (mins)			Flow (l/s)			
1.000	8	0.041	0.000	1.24				43.0	SURCHARGED	
1.001	7	0.060	0.000	0.03				22.2	SURCHARGED	
1.002	6	0.076	0.000	0.01				20.6	SURCHARGED	
1.003	5	0.146	0.000	0.01				4.6	SURCHARGED	
1.004	4	1.146	0.000	0.11				5.0	SURCHARGED	
1.005	3	-0.177	0.000	0.10				5.0	OK	
1.006	2	-0.190	0.000	0.06				5.0	OK	