

	PLANTING SCHEDULE					
Abr.	**Species**	**Size**	**Height**	**Pot Size**	**Density**	**Specification**
	SEMI MATURE TREES					
Pc 'C'	Pyrus calleryana 'Chanticleer'	25-30cm girth	5.0 - 6.0m	WRB	.	4x; Semi-mature; clear stem minimum 200cm
	SEMI MATURE TREES					
Al	Amelanchier lamarckii	.	2.5 - 3.0m	WRB	.	4x; Umbrella shape; Multi-stem; 100-150cm wide; clear stems 150-200cm; clipped
Buj	Betula utilis var. Jacquemontii	.	3.0 - 3.5m	WRB	.	3x; Multi-stem; bushy; 2 stems
	CLIMBER PLANTING					
.	Jasminum officinale	.	100 - 150cm	10L	3/lin m	Caned; several shoots; 5 breaks
	HEDGE PLANTING					
.	Prunus lusitanica	.	1.2m	1m trough	.	1m instant hedging

	ORNAMENTAL GRASSES & SHRUBS							Mix %
.	Deschampsia cespitosa 'Tautrager'	.	40 - 60 cm height	5L PG	4/m2	Full Pot	4/m2	10%
.	Pennisetum alopecuroides 'Hameln'	.	40 - 60 cm height	5L PG	4/m2	Full Pot	4/m2	10%
.	Stipa tenuissima	.	40 - 60 cm height	5L PG	4/m2	Full Pot	4/m2	7%
.	Agapanthus africanus 'Albus'	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Astilbe arendsii 'Fiery Red'	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Echinacea purpurea	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Perovskia 'Blue Spire'	.	40 - 60 cm height	3L PG	5/m2	Full Pot	5/m2	5%
.	Sanguisorba 'Tanna'	.	40 - 60 cm height	2L PG	8/m2	Full Pot	8/m2	8%
.	Salvia leucantha	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Salvia 'Mystic Spires Blue'	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Nepeta 'Blue'	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Luzula sylvatica	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Liriope muscari 'Royal Purple'	.	40 - 60 cm height	5L PG	5/m2	Full Pot	5/m2	5%
.	Bergania cordifolia ' Purpurea'	.	20 - 30cm height	2L PG	5/m2	Full Pot	5/m2	5%
.	Dryopteris erythrosora	.	40 - 60 cm height	3L PG	4/m2	Full Pot	4/m2	10%
.	Polypodium vulgare	.	40 - 60 cm height	3L PG	4/m2	Full Pot	4/m2	5%
	BULBS							
.	Allium aflatunense	.	18/20 grade		10/m2	.	10/m2	

NOTES:

1. DO NOT SCALE FROM THIS DRAWING. ALWAYS WORK TO NOTED DIMENSIONS.
2. ALL SETTING OUT, LEVELS AND DIMENSIONS TO BE CHECKED ON SITE PRIOR TO THE INSTALLATION OF MATERIALS AND ANY DISCREPANCIES ARE TO BE BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
3. THIS DRAWING MUST BE READ WITH THE RELEVANT SPECIFICATION DOCUMENTS AND DETAIL DRAWINGS. ANY DISCREPANCIES MUST BROUGHT TO THE ATTENTION OF THE CONTRACT ADMINISTRATOR IMMEDIATELY.
4. THIS DRAWING IS COPYRIGHT PROTECTED AND MAY NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN AUTHORITY.
5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE STATED.

THIS DRAWING WAS PLOTTED ON:
15/11/2023

REVISION HISTORY

DATE	REV	ZONE	DESCRIPTION	CHK
04/09/20	1		Planning Issue	ST
17/08/21	2		Draft issue for co-ordination	ST
15/11/2023	3		Entrance and 1st floor terrace updates	AD

KEY

GENERAL INFORMATION

Application Site Boundary

SOFTWORKS

Clear-stem Tree Planting
Refer to planting schedule

Multi-stem Tree Planting
Refer to planting schedule

Ornamental Shrub & Grasses
Refer to planting schedule

Instant Hedging
Height: 1500mm
Refer to planting schedule

Climber Planting
Refer to planting schedule

ORIGINATOR
Layer. studio
W layer.studio
T 01625 523 157
E manchester or newcastle@layer.studio
MANCHESTER
The Barn
One Hollin Lane
Styal
Cheshire
SK9 4JH
NEWCASTLE
The Studio
Low Shilford House
Stocksfield
Northumberland
NE43 7HW

CLIENT
Cert Property / Heatley Developments

PROJECT
Osborne Yard
Manchester

DRAWING TITLE
SOFTWORKS

DRAWING NUMBER **220-LYR-XX-00-DWG-L-3001** | REV **2** | STATUS **Draft**

SCALE **1:150 @ A1** | CREATED BY **HC** | CHECKED BY **ST**