



1. Allow for ceiling access hatches - nominally 2 no.
2. Pod construction pending S.E. input
3. Fire rated ceiling over new stud wall.
4. Fire rated loadbearing walls to support cap - notionally timber stud
5. Fire rated shaft wall. Floor fixed with resin anchors to a depth. of approx. 100mm. 2 no. per post.
6. Fire detection to be updated to suit revised layout.
7. Fire rated stud wall. Floor fixed with resin anchors to a depth. of approx. 100mm. 2 no. per post.
8. Additional posts to reinforce existing non historic stud wall. Fixed into to non original vaulted concrete soffit.

C 12/07/2023	Updated following S.E. feedback.	HW	H W
B 24/05/2023	Pin ref. updated. Sections omitted following Fire Engineer feedback.	HW	H W
A 02/05/2023	Works at Pin 0125:38 omitted following Fire Engineer feedback.	HW	
Rev	Note	DRN	CHK

SK sketch **E** existing **P** proposed **T** tender **C** construction **FI** final issue

www.ateliermb.co.uk
t 0161 236 0051
e architect@ateliermb.co.uk