

Project No: 313225

Manchester Communications Academy - Glint & Glare Assessment

Prepared for:

Energy Intelligence Ltd
19-33 South Promenade
Lytham St Annes, UK
FY8 1LS

Contents Amendment Record

This report has been issued and amended as follows:

Revision	Description	Date	Signed
1.0	First Issue	06 June 2023	A Clacy



SAFETY
SCHEMES IN
PROCUREMENT




Mabbett & Associates Ltd, Corporate and Registered Office: 13 Henderson Road, Inverness, UK, IV1 1SN
Registered in Scotland No: SC 163378 info@mabbett.eu www.mabbett.eu

Acknowledgement

This report has been prepared for the sole and exclusive use of Energy Intelligence Ltd (Energy Intelligence) in accordance with the scope of work presented in Mabbett & Associates Ltd (Mabbett) Letter Agreement (313225/LA/JJ), dated 25 April 2023. This report is based on information and data collected by Mabbett. Should any of the information be incorrect, incomplete or subject to change, Mabbett may wish to revise the report accordingly.

This report has been prepared by the following Mabbett personnel:


MABBETT & ASSOCIATES LTD

A handwritten signature in black ink, appearing to read 'Alexandra Clacy', written over a light blue grid background.

Alexandra Clacy, MSc
Environmental Engineer

This report has been reviewed and approved by the following Mabbett personnel:

MABBETT & ASSOCIATES LTD

A handwritten signature in blue ink, appearing to read 'S. Carson', written over a light blue grid background.

Stephen Carson, BSc, MIAQM
Senior Environmental Consultant

Table of Contents

Section 1.0: Introduction	1
1.1 Introduction	1
1.2 Glint & Glare	1
1.3 Scope of Work	1
Section 2.0: Development Characteristics	2
2.1 Site Description	2
2.2 Proposed Development	2
Section 3.0: Legislation & Guidance	5
3.1 Planning Guidance	5
3.1.1 Planning Guidance: National Planning Policy Framework	5
3.1.2 Revised Draft National Policy Statement for Renewable Energy Infrastructure	5
3.2 UK Highway Code	7
3.3 Network Rail Guidance	7
3.4 Aviation Guidance	7
3.4.1 Interim Civil Aviation Authority Guidance – Solar PV Systems	7
3.4.2 US Federal Aviation Agency Guidance	7
Section 4.0: Methodology	10
4.1 Solar Reflection Model	10
4.2 Receptor Identification	10
4.3 Magnitude of Impact	12
4.3.1 Ocular Impact	12
4.3.2 Glint & Glare Impact Significance	12
4.4 Time Zone / Datum	14
4.5 Assumptions, Limitations & Fixed Model Variables	14
Section 5.0: Receptor Screening & Modelling Considerations	15
5.1 Nearby Dwellings	15
5.2 Aviation Infrastructure	16
5.2.1 Manchester Royal Infirmary Helipad	16
5.3 Road Infrastructure	16
5.4 Rail Infrastructure	18
Section 6.0: Modelling Results & Interpretation	19
6.1 Nearby Dwellings	19
6.2 Aviation – Manchester Royal Infirmary Helipad	19
Section 7.0: Conclusions	20
7.1 Assessment Findings Summary	20

Section 1.0: Introduction

1.1 Introduction

Energy Intelligence Ltd is proposing to install solar panels at the Manchester Communication Academy on 2A Silchester Drive, Manchester (planning application number: 136761/P14J/2023).

It is understood that the solar farm will be comprised of roof-mounted solar arrays (hereafter referred to as the 'Proposed Development').

The report presents the findings of the glint and glare assessment undertaken for the Proposed Development.

1.2 Glint & Glare

Reflectivity refers to light that is reflected off surfaces (e.g. glazed surfaces or areas of metal cladding). The potential effects of reflectivity are glint and glare. The Federal Aviation Administration's (FAA) '*Technical Guidance for Evaluating Selected Solar Technologies on Airports*' provides the following glint and glare definitions:

- Glint – *"a momentary flash of bright light"*
- Glare – *"a continuous source of bright light"*

These present an ocular hazard to light sensitive receptors such as road users, train drivers, occupants of nearby dwellings, pilots, and air-traffic control personnel, as they can cause a brief, temporary or permanent eye damage (ocular impact categories and significance further discussed in Section 4.3).

In general, solar PV systems are constructed of dark, light-absorbing material designed to maximise light adsorption and minimise reflection. However, the glass surfaces of solar PV systems also reflect sunlight to varying degrees throughout the day and year, based on the incidence angle of the sun relative to ground-based receptors. Lower incidence angles amount to increased reflection.

As such, the amount of light reflected off a solar PV panel surface or an array of solar panels depends on a variety of factors to include:

- The amount of sunlight hitting the surface;
- Its surface reflectivity;
- Its geographic location;
- Time of the year;
- Cloud coverage; and
- Panel orientation.

1.3 Scope of Work

Based on definitions and factors described in Section 1.2 and in combination with available guidance and good practice recommendations, a desk-based evaluation was undertaken to evaluate the potential to experience the effects of glint and glare towards Manchester Royal Infirmary Helipad, residential dwellings, and road users. A solar glare analysis tool was utilised to model the solar PV arrays and examine the times of the year and days such effects may occur, as well as the magnitude of their impact. The results of this study were subsequently interpreted, and appropriate recommendations made.

Section 4.0 provides further details on methodology followed to complete this study.

Section 2.0: Development Characteristics

2.1 Site Description

The site (centred at National Grid Reference, NGR 385686, 400709) is located on Silchester Drive, Manchester, M40 8NT. It is bounded to the north by residential dwellings, to the east by a small area of woodland, to the south by the A6010 and dwellings, and to the west by Rochdale Road, dwellings and Queens Park.

The site location is shown in Figure 2.1 below in red.

Figure 2.1 Site Location



Imagery © 2023 Google

2.2 Proposed Development

The Proposed Development comprises of the installation of two roof-mounted arrays on the existing Manchester Communications Academy building. Array 1 is due to face south-southwest, and Array 2 is due to face east-southeast (see Figure 2.2).

The modelled PV module orientation and inclination, as well as PV panel height above ground, is summarised in the below table¹.

PV Array	Orientation (Azimuth) ²	Panel Tilt	Height above ground ³
Array 1	19°	5°	12.2m
Array 2	115°	30°	12.2m

¹ Based on information provided by Energy Intelligence Ltd.


² North referenced at 0°.

³ Building height derived from 1m Lidar Data from Defra Survey Data Download

The two array systems will be coated in an anti-reflective coating. For the purpose of this assessment the PV panels will be modelled as 'smooth glass with Anti-Reflective Coating (ARC)'.

The proposed solar plan is shown in Figure 2.2 with the arrays marked up. For modelling purposes, the PV layout has been simplified as shown in Figure 2.3.

Figure 2.2 Proposed Solar Plan



Imagery Infoterra Ltd & Bluesky, Maxar Technologies, The GeoInformation Group

Figure 2.3 Modelled PV Arrays



Section 3.0: Legislation & Guidance

3.1 Planning Guidance

3.1.1 Planning Guidance: National Planning Policy Framework

The National Planning Policy Framework Guidance for 'Renewable and Low Carbon Energy'⁴ dictates the following with respect to solar PV developments and glint and glare:

“The deployment of large-scale solar farms can have a negative impact on the rural environment, particularly in undulating landscapes. However, the visual impact of a well-planned and well-screened solar farm can be properly addressed within the landscape if planned sensitively.

Particular factors a local planning authority will need to consider include:

- *... the proposal's visual impact, the effect on landscape of glint and glare (see guidance on landscape assessment) and on neighbouring uses and aircraft safety;*
- *the extent to which there may be additional impacts if solar arrays follow the daily movement of the sun;*
- *... great care should be taken to ensure heritage assets are conserved in a manner appropriate to their significance, including the impact of proposals on views important to their setting. As the significance of a heritage asset derives not only from its physical presence, but also from its setting, careful consideration should be given to the impact of large-scale solar farms on such assets. Depending on their scale, design and prominence, a large-scale solar farm within the setting of a heritage asset may cause substantial harm to the significance of the asset;*
- *the potential to mitigate landscape and visual impacts through, for example, screening with native hedges;*

The approach to assessing cumulative landscape and visual impact of large scale solar farms is likely to be the same as assessing the impact of wind turbines. However, in the case of ground mounted solar panels it should be noted that with effective screening and appropriate land topography the area of a zone of visual influence could be zero.”

3.1.2 Revised Draft National Policy Statement for Renewable Energy Infrastructure

The Revised Draft National Policy Statement for Renewable Energy Infrastructure (EN-3)⁵ sets out the primary policy for decisions by the Secretary of State for nationally significant renewable energy infrastructure.

Sections 3.10.12 and 3.10.93-3.10.97 outlines the potential impact of glint and glare that the applicants may consider:

“3.10.12 Utility-scale solar farms are large sites that may have a significant zone of visual influence. The two main impact issues that determine distances to sensitive receptors are therefore likely to be visual amenity and glint and glare. These are considered in Landscape, Visual and Residential Amenity (paragraphs 3.10.84- 3.10.92) and Glint and Glare (paragraphs 3.10.93 – 3.10.97) impact sections below.”

...

3.10.93 Solar panels are specifically designed to absorb, not reflect, irradiation⁶. However, solar panels may reflect the sun's rays at certain angles, causing glint and glare. Glint is defined as a momentary flash of light that may be produced as a direct reflection of the sun in the solar panel.

⁴ <https://www.gov.uk/guidance/renewable-and-low-carbon-energy>

⁵ https://assets.publishing.service.gov.uk/government/uploads/system/uploads/attachment_data/file/1147382/NPS_EN-3.pdf

⁶ Most commercially available solar panels are designed with anti-reflective glass or are produced with anti-reflective coating and have a reflective capacity that is generally equal to or less hazardous than other objects typically found in the outdoor environment, such as bodies of water or glass buildings.

Glare is a continuous source of excessive brightness experienced by a stationary observer located in the path of reflected sunlight from the face of the panel. The effect occurs when the solar panel is stationed between or at an angle of the sun and the receptor.

3.10.94 Applicants should map receptors to qualitatively identify potential glint and glare issues and determine if a glint and glare assessment is necessary as part of the application.

3.10.95 When a quantitative glint and glare assessment is necessary, applicants are expected to consider the geometric possibility of glint and glare affecting nearby receptors and provide an assessment of potential impact and impairment based on the angle and duration of incidence and the intensity of the reflection.

3.10.96 The extent of reflectivity analysis required to assess potential impacts will depend on the specific project site and design. This may need to account for 'tracking' panels if they are proposed as these may cause differential diurnal and/or seasonal impacts.

3.10.97 When a glint and glare assessment is undertaken, the potential for solar PV panels, frames and supports to have a combined reflective quality may need to be assessed, although the glint and glare of the frames and supports is likely to be significantly less than the panels."

Sections 3.10.125-3.10.127 outlines the potential mitigations for glint and glare impacts that the applicants may consider:

"3.10.125 Applicants should consider using, and in some cases the Secretary of State may require, solar panels to comprise of (or be covered with) anti-glare/anti-reflective coating with a specified angle of maximum reflection attenuation for the lifetime of the permission.

3.10.126 Applicants may consider using screening between potentially affected receptors and the reflecting panels to mitigate the effects.

3.10.127 Applicants may consider adjusting the azimuth alignment of or changing the elevation tilt angle of a solar panel, within the economically viable range, to alter the angle of incidence. In practice this is unlikely to remove the potential impact altogether but in marginal cases may contribute to a mitigation strategy."

Sections 3.10.149-3.10.150 outlines further detail on the potential glint and glare impacts that the Secretary of State may consider as part of their decision making:

"3.10.149 Solar PV panels are designed to absorb, not reflect, irradiation. However, the Secretary of State should assess the potential impact of glint and glare on nearby homes, motorists, public rights of way, and aviation infrastructure (including aircraft departure and arrival flight paths).

3.10.150 Whilst there is some evidence that glint and glare from solar farms can be experienced by pilots and air traffic controllers in certain conditions, there is no evidence that glint and glare from solar farms results in significant impairment on aircraft safety. Therefore, unless a significant impairment can be demonstrated, the Secretary of State is unlikely to give any more than limited weight to claims of aviation interference because of glint and glare from solar farms."

Finally, the above draft policy is only applicable to:

- Significant renewable energy infrastructure (i.e. solar photovoltaic >50 MW in England and >350MW in Wales, where MW is measured as alternating current)
- In Scotland, the Secretary of State will not examine applications for nationally significant generating stations or electricity network infrastructure. However, energy policy is generally a matter reserved to UK Ministers and this draft policy may therefore be a relevant consideration in planning decisions in Scotland.
- In Northern Ireland, planning consents for all nationally significant infrastructure projects are devolved to the Northern Ireland Executive so this draft policy does not apply there.

3.2 UK Highway Code

The UK Highway Code states that a road user should be aware of particular hazards such as glare from the sun and should adjust their driving style appropriately. Solar PV panels reflect sunlight producing solar glare under specific conditions, which may likely pose hazard towards road users.

3.3 Network Rail Guidance

Rail Industry Standard (RIS) RIS-0737-CCS on 'Signal Sighting Assessment Requirements' highlights that:

"a planned change external to the railway could affect signal sighting, for example changes that affect the built environment (for example, a new structure causing obscuration, a solar farm causing reflection)."

In addition to the above, additional guidelines are provided which detail reflections and glare, visibility of signals, and train drivers' field of vision. As no nearby rail receptors have been identified in relation to the Proposed Development, the relevant guidance is excluded from the report for simplicity.

It should be noted that Network Rail guidance does not provide a specific glare assessment methodology for rail receptors, beyond the above information.

3.4 Aviation Guidance

3.4.1 Interim Civil Aviation Authority Guidance – Solar PV Systems

The UK Civil Aviation Authority (CAA) issued interim guidance relating to solar PV systems on 17 December 2010 but this was withdrawn on 7 September 2012. The guidance is provided in Appendix A. At the time of writing it remains the most recent and comprehensive publicly available CAA guidance produced to date.

In general, the interim guidance recommends that solar PV developments in the vicinity of or within an aerodrome's boundaries should provide safety assurance documentation (e.g. glint and glare assessment) regarding the full potential impact of the proposed installation on aviation interests, as part of the relevant planning application. It is further suggested that this information should be consulted with the CAA, particularly if the Proposed Development is within aerodrome boundaries, and during the installation process the developer should liaise with the affected aerodrome. Beyond these recommendations, no specific methodology or frame of reference are defined for assessing the impact of glint and glare on aviation infrastructure.

3.4.2 US Federal Aviation Agency Guidance

In general, aviation stakeholders in the UK, as well as internationally, make use of the US Federal Aviation Agency (FAA) relevant guidance on solar energy systems as it provides the most detailed methodology for assessing glint and glare internationally.

The most comprehensive guidelines available for the assessment of solar PV developments near aerodromes were initially produced in November 2010 (entitled '*Technical Guidance for Evaluating Selected Solar Technologies on Airports*') by the FAA and updated in 2013 (entitled '*Interim Policy, FAA Review of Solar Energy System Projects on Federally Obligated Airports*'). The 2013 edition was updated in 2018 as version 1.1 and is entitled '*Technical Guidance for Evaluating Selected Solar Technologies on Airports*'. The key changes are as follows:

Version 1.1 (April 2018):

- *Updated Section 3.1.2, Reflectivity, to incorporate the latest information about evaluating solar glint and glare.*
- *Updated corresponding references to glare throughout the document.*
- *Clarified the relationship between solar energy and the FAA's Voluntary Airport Low Emissions (VALE) program in Section 5.3.2.*
- *Added information about the FAA's Airport Energy Efficiency Program to Section 5.3.3.*
- *Updated FAA Contact information on Appendix B (where appropriate).*

Key points from the latest FAA guidance produced in 2018 are presented in Appendix B. The full document can be accessed [here](#).

Overall, the 2018 update offers three assessment options:

- Assessing Baseline Reflectivity Conditions
- Tests in the Field
- Geometric Analysis

A final policy entitled 'Federal Aviation Administration Policy: Review of Solar Energy System Projects on Federally-Obligated Airports' was released in 2021, which superseded the all previous guidance. The 2021 final policy has taken a step back and allowed aerodromes to safeguard as they see fit, with no longer a recommendation for any given glare model. However, where a proposed solar development is located where a risk to aviation safety is possible, geometric analysis, as per the 2013 guidance, will likely be the only option available to alleviate concerns. Aerodromes in the UK and internationally safeguard against glint and glare based on the 2018 FAA guidance.

Key points from the 2013 guidance are replicated below:

"...the FAA has determined that glint and glare from solar energy systems could result in an ocular impact to pilots and/or air traffic control (ATC) facilities and compromise the safety of the air transportation system. While the FAA supports solar energy systems on airports, the FAA seeks to ensure safety by eliminating the potential for ocular impact to pilots and/or air traffic control facilities due to glare from such projects."

- **Standard for Measuring Ocular Impact**

"FAA adopts the Solar Glare Hazard Analysis Plot⁷ as the standard for measuring the ocular impact of any proposed solar energy system on a federally-obligated airport. To obtain FAA approval to revise an airport layout plan to depict a solar installation and/or a "no objection" to a Notice of Proposed Construction Form 7460-1, the airport sponsor will be required to demonstrate that the proposed solar energy system meets the following standards:

- 1. No potential for glint or glare in the existing or planned Airport Traffic Control Tower (ATCT) cab, and*
- 2. No potential for glare or "low potential for after-image" (shown in green in hazard plot) along the final approach path for any existing landing threshold or future landing thresholds (including any planned interim phases of the landing thresholds) as shown on the current FAA-approved Airport Layout Plan (ALP). The final approach path is defined as two (2) miles from fifty (50) feet above the landing threshold using a standard three (3) degree glidepath.*

Ocular impact must be analysed over the entire calendar year in one (1) minute intervals from when the sun rises above the horizon until the sun sets below the horizon."

- **Tool to Assess Ocular Impact**

"In cooperation with the Department of Energy (DOE), the FAA is making available free-of-charge the Solar Glare Hazard Analysis Tool (SGHAT). The SGHAT was designed to determine whether a proposed solar energy project would result in the potential for ocular impact as depicted on the Solar Glare Hazard Analysis Plot shown above."

- **Required Use of SGHAT**

"As of the date of publication of this interim policy, the FAA requires the use of the SGHAT to demonstrate compliance with the standards for measuring ocular impact stated above for any proposed solar energy system located on a federally-obligated airport. The SGHAT is a validated tool specifically designed to measure glare according to the Solar Glare Hazard Analysis Plot. All sponsors of federally obligated airports who propose to install or to permit others to install solar energy systems on the airport must attach the SGHAT report, outlining solar panel glare and ocular impact, for each point of measurement to the Notice of Proposed Construction Form 7460-1. The FAA will consider the use of alternative tools or methods on a

⁷ Plot provided in Section 4.3.1.

case-by-case basis. However, the FAA must approve the use of an alternative tool or method prior to an airport sponsor seeking approval for any proposed on-airport solar energy system. The alternative tool or method must evaluate ocular impact in accordance with the Solar Glare Hazard Analysis Plot.”

It should be noted that due to cybersecurity restrictions, SGHAT public use is restricted. This has been succeeded by ForgeSolar which also meets FAA glare analysis requirements.

Section 4.0: Methodology

A desk-based assessment is undertaken to assess glint and glare that may be experienced by light-sensitive receptors within the vicinity of the proposed solar PV development.

4.1 Solar Reflection Model

A computational modelling tool was used, where appropriate/required, to model and assess solar reflectivity of the Proposed Development in relation to specified receptors, in line with FAA guidance.

The tool employs an interactive Google map where the site location, proposed solar energy system and receptor paths/locations can be specified. Latitude, longitude, and elevation are automatically recorded through the Google interface, providing necessary information for sun position and vector calculations.

PV systems are represented by contiguous planar polygon footprints and a set of customisable parameters. Each footprint comprises three or more vertices, defined by a latitude, longitude, elevation, and height. Each distinct PV installation or array is modelled with its own PV array footprint. The PV panel tilt, orientation, and height are considered to be the same across the entire array. This is considered acceptable due to the distance of the sun from the Proposed Development and the relatively small differences in location of the sun over the Proposed Development.

The solar reflectance of the PV modules is specified based on the module surface material. The modelling tool has five general module material reflectance profiles which were developed by analysing different PV module samples. The following options are available:

- Smooth glass without ARC
- Smooth glass with ARC
- Light textured glass without ARC
- Light textured glass with ARC
- Deeply textured glass

During analysis, sunlight is reflected over each PV array on a minute-by-minute basis according to the specified module tilt and orientation or axis tracking parameters, if the system is not fixed-mount. The system then checks whether the resulting solar reflections intersect (impact) the specified receptors, thus predicting glint and glare occurrence.

4.2 Receptor Identification

In general, light-sensitive receptors with view of a solar PV development have potential to experience solar reflection. While no technical distance limits/thresholds are reported within which solar reflections are possible for such receptors, the potential or significance of a reflection decreases with distance due to an observer's decreasing field of vision capability with increasing distance, as well as possible obstructions such as shielding caused by terrain and vegetation. For the purpose of this assessment, the following good practice considerations will be applied, incorporating relevant guidance as laid out in Section 3.0

Aviation	Aerodromes In accordance with industry guidance, aerodromes located: ▪ Within less than 5 km of proposed development, will be assessed for glint and glare. ▪ Within 5-30 km away from the proposed development will be identified but not assessed unless requested by relevant aerodrome safeguarding authority during planning consultation. ▪ Beyond 30 km radius from the proposed development are not considered. In accordance with US FAA guidance, the recommended modelling assessment methodology is: ▪ Additional height above ground level will be considered to represent the viewing height of an air controller within the ATCT (ATCT height).
-----------------	--

	2-mile approach path thresholds towards runway(s) will be assessed, with starting points taken at 15.2 m above runway threshold at a 3-degree descent path (unless otherwise stated). - Reference aircraft location receptor points will be taken at no more than ¼ miles intervals, with a minimum of 9 points, over the 2-mile approach paths identified. - A pilot azimuthal field-of-view (FOV) of 100° will be applied (50° view angle to left and right). According to the FAA, glare that appears beyond this FOV range is mitigated. - A pilot vertical FOV of 30° will be applied. Anything appearing beyond this FOV is not visible to the pilot and is acceptable to FAA. Heliports & Helipads Industry guidance suggests that heliports and helipads may be assessed where glare poses a potential hazard to safety. The approach paths are considered to be the most critical stage of helicopter flight and the associated modelling assessment methodology is: 8 approach paths will be assessed which start 2 m above the heliport centre (approximate eye level of a helicopter pilot) and spread out to 8 cardinal directions⁸ at a length of 3.4 km and 152 m above the elevation of the heliport (e.g. ~2.6-degree decent path)⁹. - Where possible, the above approach paths will be identified in line with CAA's CAP1264 – Standards for helicopter landing areas at hospitals, where: <i>"the cross bar of the "H" lying perpendicular to the preferred direction of approach (normally based on the prevailing wind direction)".</i> Similar pilot vertical and azimuthal FOVs as aerodromes will be applied.
Dwellings	- Residential dwellings to around 1 km from the solar PV development boundary with a visual line of sight to the panels will be considered. - An additional height of 1.8 m above ground level will be considered to account for observer's eye level on ground floor which is typically occupied during daylight hours, unless otherwise stated. Where blocks of residential apartments are assessed, each storey height will be taken as 3 m plus 1.8 m to represent observer's eye level.
Railways	- Railways in the immediate surrounding area to around 100 m from the solar PV development boundary with a visual line of sight to the panels will be considered. - Length of railway line will be assessed via individual static receptor locations no more than 200 m apart up to 500 m from the Proposed Development boundaries. - An additional height of 2.75 m above ground level will be considered to represent typical train driver viewing height. - Where signals are located immediately adjacent to or above a railway line, their lens is in line of sight of the Proposed Development, and are used to direct trains on the lines, these will also be assessed as individual static receptors.
Road Users	- An additional height of 1.5 m above ground level will be considered to represent the typical road user viewing height, unless otherwise stated. - A driver field-of-view (FOV) of 100° will be applied (50° view angle to left and right). According to the FAA, glare that appears beyond this FOV is mitigated.

⁸ North (N), north-east (NE), east (E), south-east (SE), south (S), south-west (SW), west (W) and north-west (NW).

⁹ Final approach path dimensions as defined under CAA's CAP1264 – Standards for helicopter landing areas at hospitals (<http://publicapps.caa.co.uk/docs/33/CAP1264HelicopterlandingathospitalsAugust2019.pdf>).

4.3 Magnitude of Impact


4.3.1 Ocular Impact

Ocular impact significance depends on the line of sight between the reflector (solar PV panels) and the receptor, the location of the receptor relative to the reflector and thus the solar reflection, the time of the day, they path between the sun and the reflective surface, and the reflection exposure period (e.g. momentary exposure is less significant than prolonged exposure).

As such, ocular impact can be classified into three levels based on the retinal irradiance and subtended source angle: low potential for after-image (**green**), potential for after-image (**yellow**), and potential for permanent eye damage (**red**). These categories are illustrated in the Ocular Hazard plot¹⁰ shown in Figure 4.1 (NOTE: this is a universal Ocular Hazard plot and does not represent potential glare conditions that may be experienced at the Proposed Development.).

The subtended source angle represents the size of glare observed by receptor, while the retinal irradiance is the quantity of energy impacting the retina of the observer. As it can be seen from Figure 4.1, wide subtended source angles can cause retinal irritation/damage even at low retinal irradiance.

Figure 4.1: Ocular Hazard Plot



4.3.2 Glint & Glare Impact Significance

4.3.2.1 Dwellings

While there is no specific guidance on glint and glare significance evaluation, the following classifications may be used:

No Impact	Solar reflection is not geometrically possible or will not be visible from the assessed receptor.
Low	Glare of any intensity (green or yellow) occurs for less than 60 minutes per day and for less than three months per year. Mitigation is not required.
Moderate	Glare of any intensity (green or yellow) occurs for longer than 60 minutes or for more than 3 months per year. Mitigation may be required at planner's discretion.
High	Glare of any intensity (green or yellow) occurs for longer than 60 minutes per day and for more than 3 months of the year. Mitigation will be required if the Proposed Development is to proceed.

¹⁰ Sliney, D.H. and B.C. Freasier, 1973, Evaluation of Optical Radiation Hazards, Applied Optics, 12(1), p. 1-24.

4.3.2.2 Road and Aviation

Air Traffic Control Towers (ATCT)	Based on FAA guidance:	
	Acceptable	'No potential for glint and glare' towards ATCT should be produced by a proposed solar PV development.
	Unacceptable	Any glare of any duration/frequency predicted towards ATCT from proposed solar PV development.
It is recommended that any predicted solar reflection is assessed pragmatically. Therefore, the following will also be considered when determining whether a solar reflection is significant: 1. The predicted intensity of the solar reflection; 2. Location of origin of the solar reflection relative to the ATCT; 3. Solar reflection duration per day; 4. Number of days a solar reflection is geometrically possible per year; and 5. The time of day when a solar reflection is geometrically possible.		
Approaching Aircrafts	Based on FAA guidance:	
	Acceptable	'No potential for glare' or 'low potential for after-image' along the final approach path for any existing or future landing thresholds.
	Unacceptable	Yellow glare with potential for temporary after-image predicted towards the final approach path.
Road Users	While there is no specific guidance on glint and glare impact significance evaluation or limits, the following approach will be adapted in line with best available practice guidance/recommendations:	
	No or Insignificant Impact	Solar reflection is not geometrically possible or will not be visible from the assessed receptor.
	Low	Glare of any intensity (yellow or green) predicted towards a local road. Mitigation is not considered necessary.
	Moderate	Glare of any intensity (e.g. yellow or green) predicted towards a major national, national or regional road, and does not originate in front of driver (e.g. not in centre of FOV). Mitigation may be required at regulator's discretion.
	High	Glare of any intensity (e.g. yellow or green) predicted towards a major national, national or regional road, and originates in front of driver (e.g. in centre of FOV). Mitigation recommended if the Proposed Development is to proceed.
Railways	While there is no specific guidance on glint and glare impact significance evaluation or limits, the following approach will be adapted in line with best available practice guidance/recommendations:	
	Railway	
	No or Insignificant Impact	Solar reflection is not geometrically possible or will not be visible from the assessed receptor.
	Low	Glare which does <u>not</u> originate in front of the train driver predicted. Mitigation is not considered necessary.

	Moderate	Glare originates in front of the train driver and towards a section of track where <u>no</u> signal or crossing is sited. Mitigation may be required at regulator's discretion.
	High	Glare originates in front of the train driver <u>and</u> towards a section of track where a signal or crossing is sited. Mitigation recommended if the Proposed Development is to proceed.
	Signals If the assessed reflectors (e.g. solar development) are not in line of sight to the signal lens, then no phantom aspect illusion is possible.	

4.4 Time Zone / Datum

The UK uses British Summer Time (BST, UTC +01:00) in the summer and Greenwich Mean Time (GMT, UTC +0) in the winter. For the purpose of this report all time references are in GMT.

All locations are given in Eastings and Northings using the UK National Grid Reference system, unless otherwise specified.

4.5 Assumptions, Limitations & Fixed Model Variables

Provided in Appendix C is a list of assumptions, limitations and fixed variables of the model and assessment methodology.

Section 5.0: Receptor Screening & Modelling Considerations

5.1 Nearby Dwellings

A number of residential dwellings exist within 1 km of the Proposed Development boundaries. Only the receptor points closest to the Proposed Development with a potential line of sight towards the PV panels were assessed via modelling, as other dwellings are expected to be screened by these receptors, as well as vegetation and/or other buildings found in between them. As per industry guidance, glare modelling focuses on ground floor residential receptors because it is typically the most occupied part of the dwelling during daylight hours.

A detailed receptor review indicates that residential dwellings lie to the north, west, south and southeast of the Proposed Development while the PC arrays are orientated south-southwest and east-southeast. As such, glare from the Proposed Development directed to the dwellings north and west of the Site is not geometrically possible as they are orientated in the opposite direction. Therefore, these dwellings were screened from further assessment.

Dwellings located south and southwest of the Proposed Development have been modelled in the assessment. It was noted that OP1-OP3 are residential flats and have such been modelled at three heights to represent each floor. As per Section 4.2, a height of 1.8 m above ground level is considered representative of eye level for ground floor receptors. For the additional floors, an additional height of 3 m has been added to the modelled height above ground level to represent observer's eye level.

The modelled receptors (Observation Points (OPs)) are shown in Figure 5.1 below.

Figure 5.1 Modelled Residential Dwellings




5.2 Aviation Infrastructure

5.2.1 Manchester Royal Infirmary Helipad

Manchester Royal Infirmary is located approximately 4.5km southeast from the Proposed Development, as shown in Figure 5.2.

In accordance with the methodology detailed in Section 4.2, the assessed approach paths are illustrated in Figure 5.2 below, where the central point represents to the helipad location. These will be assessed as routes starting at 2 m above the helipad centre out to a length of 3.4 km, 152 m above the elevation of the helipad.

Figure 5.2 Helipad Approach Paths




5.3 Road Infrastructure

A number of local roads exist within 1 km of the Proposed Development boundaries. However, glare assessment typically only focuses on high speed, high traffic roads such as motorways and trunk A roads, in proximity to the Proposed Development boundaries.

The A6010 is located west, south and southeast of the Proposed Development, as can be seen below in Figure 5.3.

Figure 5.3 Major Road A6010




As detailed in Section 2.2, the PV arrays are orientated in a south-southwest and east-southeast direction. As such, glare from the Proposed Development to the western section of the A6010 (shown in pink) is not geometrically possible. As such, this section of the A6010 has been screened from further assessment.

For the section of the A6010 located southeast of the Proposed Development (shown in orange), it is considered that the intervening residential dwellings will act as an obstruction of line of sight between the road and the Proposed Development, and as such have been screened from further assessment.


The building of the Proposed Development acts as an obstruction of line of sight between the section of the A6010 south of the building and the solar arrays (shown in yellow), as can be seen in Figure 5.4 and Figure 5.5. Therefore, this section has been screened from further development.

Figure 5.4 Obstruction of line of sight between A6010 and Proposed Development



Imagery © 2023 Google Street View

Figure 5.5 Obstruction of line of sight between A6010 and Proposed Development



Imagery © 2023 Google Street View

Therefore, as there is no line of sight between the road user and the Proposed Development, the A6010 has been screened from further assessment.

All other nearby roads are classed as minor roads. Therefore, in the unlikely situation that glare does affect them, the impact would be of low risk (in line with Section 4.3.2).

5.4 Rail Infrastructure

In accordance with industry guidance, rail operators may raise an objection to solar developments that are within 100 m of their infrastructure due to safety implications caused by glare on train drivers, level crossings and railway light signals.

A detailed receptor review does not indicate any such receptors within this distance and therefore, no rail receptors are within the modelling assessment.

Section 6.0: Modelling Results & Interpretation

6.1 Nearby Dwellings

PV Array	Observation Receptors Affected	Observation Receptor Location	Impact
Array 1	<i>No glare predicted towards nearby dwellings.</i>	-	No Impact
Array 2	<i>No glare predicted towards nearby dwellings.</i>	-	No Impact

No glare is predicted at any of the modelled residential dwellings. With reference to the impact significance (Section 4.3.2.1), the Proposed Development will have 'no impact' on amenity of the nearby dwellings.

6.2 Aviation – Manchester Royal Infirmary Helipad

Receptor	Results	Impact
North Approach Path	<i>No glare predicted towards approach path</i>	Acceptable
Northeast Approach Path	<i>No glare predicted towards approach path</i>	Acceptable
East Approach Path	<i>No glare predicted towards approach path</i>	Acceptable
Southeast Approach Path	<i>No glare predicted towards approach path</i>	Acceptable
South Approach Path	<i>No glare predicted towards approach path</i>	Acceptable
Southwest Approach Path	<i>No glare predicted towards approach path</i>	Acceptable
West Approach Path	<i>No glare predicted towards approach path</i>	Acceptable
Northwest Approach Path	<i>No glare predicted towards approach path</i>	Acceptable

No glare is predicted to any of the modelled approach paths. With reference to Section 4.3.2.2, the impact of the Proposed Development on Manchester Royal Infirmary Helipad is 'acceptable'.

Section 7.0: Conclusions

7.1 Assessment Findings Summary

The glare modelling assessment findings are summarised in table below:

Receptor	Impact	Significance
Aviation Infrastructure (Manchester Royal Infirmary Helipad)	<i>No glare predicted to approach paths</i>	Acceptable
Nearby Dwellings	<i>No glare predicted to nearby dwellings</i>	No Impact

As it can be seen from the summary table above, the Proposed Development poses an acceptable impact on aviation infrastructure at Manchester Royal Infirmary Helipad, and no impact on amenity of nearby dwellings.

In addition, it was identified in the receptor screening review that the impact on any local minor roads with line of sight to panels would be “low” in accordance with industry guidance on risk significance. Furthermore, glare from the solar panels toward the A6010 was found to be not geometrically possible based on the orientation of the panels or the screening provided by intervening obstructions. The screening review also concluded that there is no rail infrastructure within 100m of the development.

On this basis, no mitigation is recommended, and the Proposed Development does not conflict with adopted national planning policy.

Appendix A: Interim CAA Guidance on Solar Photovoltaic Systems



Interim CAA Guidance - Solar Photovoltaic Systems

BACKGROUND

- 1 Airport interest in solar energy is growing rapidly as a way to reduce operating costs and to demonstrate a commitment to renewable energy and sustainable development. In response, the CAA is seeking to develop its policy on the installation of Solar Photovoltaic (SPV) Systems and their impact on aviation. In doing so, it is reviewing the results of research having been carried out in the United States by the Federal Aviation Administration (FAA) culminating in the publication of [Technical Guidance for Evaluating Solar Technologies on Airports](#) and also reviewing guidance issued by other National Aviation Safety Administrations and Authorities on this subject.
- 2 On completion of the review, the CAA, together with the assistance of other aviation stakeholders, will develop a policy and provide formal guidance material on the installation of SPV, principally on or in the vicinity¹ of licensed aerodromes but will also include guidance on installations away from aerodromes (or 'en-route'²). This document therefore constitutes interim CAA guidance until a formal policy has been developed.

DISCUSSION

- 3 At present the key safety issue is perceived to be the potential for reflection from SPV to cause glare, dazzling pilots or leading them to confuse reflections with aeronautical lights. Whilst permission is not required from the CAA for any individual or group to shine or reflect a light or lights into the sky, SPV developers should be aware of the requirements to comply with the [Air Navigation Order \(ANO\) 2009](#). In particular, developers and Local Planning Authorities (LPA) should be cognisant of the following articles of the ANO with respect to any SPV development regardless of location:
 - Article 137 – Endangering safety of an aircraft.
 - Article 221 – Lights liable to endanger.
 - Article 222 – Lights which dazzle or distract.
- 4 The potential for SPV installations to cause electromagnetic or other interference with aeronautical Communications Navigational and Surveillance equipment (CNS) must be considered by the SPV developer, in coordination with the CAA, the aerodrome Air Traffic Service provider (ATS), the Air Navigation Service Provider (ANSP) and/or NATS and the MoD, as required.

¹ In this context, the term 'in the vicinity' refers to officially safeguarded aerodromes noted in the Planning Circulars ([see Paragraph 10](#)) and a distance of up to 15km from the 'Aerodrome Reference Point' or the centre of the longest runway.

² SPV installations proposed further than 15km from an aerodrome are considered 'en-route' developments, and may still require consultation with the CAA for an assessment on the impact, if any, to CNS equipment.

- 5 Where SPV systems are installed on structures that, for example, extend above the roofline of tall buildings (either on, or 'off-aerodrome'), or where they are installed in the vertical plane (on plinths or towers), then there may be the potential for creating an obstacle hazard to aircraft and - in addition to the potential for creating turbulence hazard to aircraft - any infringement of the aerodrome Obstacle Limitation Surfaces (OLS) shall also need to be considered by the Aerodrome Licence Holder (ALH).
- 6 For all planned SPV installations it is best practice for the developer to consult with the operators of nearby aerodromes before any construction is initiated.
- 7 An ALH, in agreement with their LPA, may wish to initiate procedures so that it is only consulted on SPV planning applications at shorter distances from the aerodrome (for example within a 5 km radius), or at distances that would limit SPV development from within the aircraft operating visual circuit; however, this is at the discretion of the ALH and no CAA approval or endorsement of this decision is necessary.

RECOMMENDATIONS

- 8 It is recommended that, as part of a planning application, the SPV developer provide safety assurance documentation (including risk assessment) regarding the full potential impact of the SPV installation on aviation interests.
- 9 Guidance on safeguarding procedures at CAA licensed aerodromes is published within [CAP 738 Safeguarding of Aerodromes](#) and advice for unlicensed aerodromes is contained within [CAP 793 Safe Operating Practices at Unlicensed Aerodromes](#).
- 10 Where proposed developments in the vicinity of aerodromes require an application for planning permission³ the relevant LPA normally consults aerodrome operators or NATS when aeronautical interests might be affected. This consultation procedure is a statutory obligation in the case of certain major airports, and may include military establishments and certain air traffic surveillance technical sites. These arrangements are explained in [Department for Transport Circular 1/2003](#) and for Scotland, [Scottish Government Circular 2/2003](#).
- 11 In the event of SPV developments proposed under the Electricity Act, the relevant government department should routinely consult with the CAA. There is therefore no requirement for the CAA to be separately consulted for such proposed SPV installations or developments.
- 12 If an installation of SPV systems is planned **on**-aerodrome (i.e. within its licensed boundary) then it is recommended that data on the reflectivity of the solar panel material should be included in any assessment before installation approval can be granted. Although approval for installation is the responsibility of the ALH, as part of a condition of a CAA Aerodrome Licence, the ALH is required to obtain prior consent from CAA Aerodrome Standards Department before any work is begun or approval to the developer or LPA is granted, in accordance with the procedures set out in [CAP 791 Procedures for Changes to Aerodrome Infrastructure](#).
- 13 During the installation and associated construction of SPV systems there may also be a need to liaise with nearby aerodromes if cranes are to be used; CAA notification and permission is not required.

³ The CAA is aware of changes to planning legislation that may provide for 'Permitted Development Rights' for certain micro-generation equipment on both domestic and non-domestic property, under the General Permitted Development Order (1995).

- 14 The CAA aims to replace this informal guidance with formal policy in due course and reserves the right to cancel, amend or alter the guidance provided in this document at its discretion upon receipt of new information.
- 15 Further guidance may be obtained from CAA's Aerodrome Standards Department via aerodromes@caa.co.uk.

17 December 2010

Appendix B: Technical Guidance for Evaluating Selected Solar Technologies on Airports (2018)

16. Abstract

“Airport interest in solar energy is growing rapidly as a way to reduce airport operating costs and to demonstrate a commitment to sustainable development. In response, the Federal Aviation Administration (FAA) has prepared Technical Guidance for Evaluating Selected Solar Technologies on Airports to meet the regulatory and informational needs of the FAA Airports organization and airport sponsors.

For airports with favourable solar access and economics, this report provides a checklist of FAA procedures to ensure that proposed photovoltaic or solar thermal hot water systems are safe and pose no risk to pilots, air traffic controllers, or airport operations. Case studies of operating airport solar facilities are provided, including Denver International, Fresno Yosemite International, and Albuquerque International Sunport.”

Preface

“Over 15 airports around the country are operating solar facilities and airport interest in solar energy is growing rapidly. In response, the Federal Aviation Administration (FAA) has prepared this report, Technical Guidance for Evaluating Selected Solar Technologies on Airports, to meet the regulatory and information needs of FAA personnel and airport sponsors in evaluating airport solar projects.

The guidance is intended to provide a readily usable reference for FAA technical staff who review proposed airport solar projects and for airport sponsors that may be considering a solar installation. It addresses a wide range of topics including solar technology, electric grid infrastructure, FAA safety regulations, financing alternatives, and incentives.

Airport sponsors are interested in solar energy for many reasons. Solar technology has matured and is now a reliable way to reduce airport operating costs. Environmentally, solar energy shows a commitment to environmental stewardship, especially when the panels are visible to the traveling public. Among the environmental benefits are cleaner air and fewer greenhouse gases that contribute to climate change. Solar use also facilitates small business development and U.S. energy independence.

While offering benefits, solar energy introduces some new and unforeseen issues, like possible reflectivity and communication systems interference. The guidance discusses these issues and offers new information that can facilitate FAA project reviews, including a flow chart of FAA procedures to ensure that proposed systems are safe and pose no risks to pilots, air traffic controllers, or airport operations.”

AIRPORTS AND SOLAR ENERGY: CHARTING A COURSE


“Though solar energy has been evolving since the early 1990’s as a mainstream form of renewable energy generation, the expansion in the industry over the past 10 years and corresponding decrease in prices has only recently made it a practical consideration for airports. Solar energy presents itself as an opportunity for FAA and airports to produce on-site electricity and to reduce long-term electricity use and energy costs. While solar energy has many benefits, it does introduce some new and unforeseen issues, like possible glare (also referred to as reflectivity) and communication systems interference, which have complicated FAA review and approval of this technology. This guide discusses such issues and how FAA reviews for solar projects can be streamlined and standardized to a greater extent.”

3.1.2 Reflectivity

“Reflectivity refers to light that is reflected off surfaces. The potential effects of reflectivity are glint (a momentary flash of bright light) and glare (a continuous source of bright light). These two effects are referred to hereinafter as “glare,” which can cause a brief loss of vision, also known as flash blindness.

FAA Order 7400.2, Procedures for Handling Airspace Matters, defines flash blindness as “generally, a temporary visual interference effect that persists after the source of illumination has ceased.”

The amount of light reflected off a solar panel surface depends on the amount of sunlight hitting the surface, its surface reflectivity, geographic location, time of year, cloud cover, and solar panel orientation. As illustrated on Figure 16, flat, smooth surfaces reflect a more concentrated amount of sunlight back to the receiver, which is referred to as specular reflection. The more a surface is polished, the more it shines. Rough or uneven surfaces reflect light in a diffused or scattered manner and, therefore, the light will not be received as bright.



CSP systems use mirrors to maximize reflection and focus the reflected sunlight and associated heat on a design point to produce steam, which generates electricity. About 90 percent of sunlight is reflected. However, because the reflected sunlight is controlled and focused on the heat collecting element (HCE) of the system, it generally does not reflect back to other sensitive receptors. Another source of reflection in a CSP system is the light that contacts the back of the HCE and never reaches the mirror. Parts of the metal frame can also reflect sunlight. In central receiver (or power tower) applications, the receiver can receive concentrated sunlight that is up to a thousand times the sun's normal irradiance. Reflections from a central receiver, although approximately 90% absorptive, can still reflect a great deal of sunlight.

Solar PV and SHW panels are constructed of dark, light-absorbing materials and covered with an anti-reflective coating designed to maximize absorption and minimize reflection. However, the glass surfaces of solar PV and SHW systems also reflect sunlight to varying degrees throughout the day and year. The amount of reflected sunlight is based on the incidence angle of the sun relative to the light-sensitive receptor (e.g., a pilot or air traffic tower controller). The amount of reflection increases with lower incidence angles. In some situations, 100% of the sun's energy can be reflected from solar PV and SHW panels.

Because solar energy systems introduce new visual surfaces to an airport setting where reflectivity could result in glare that can cause flash blindness to those that require clear, unobstructed vision, project proponents should evaluate reflectivity during project siting and design.”

Completing an Individual Glare Analysis

“Evaluating glare for a specific project should be an iterative process that looks at one or more of the methodologies described below. Airport sponsors should coordinate closely with the FAA’s Office of Airports to evaluate the potential for glint and glare for solar projects on airport property. These data should include a review of existing airport conditions and a comparison with existing sources of glare, as well as related information obtained from other airports with experience operating solar projects.

Because the FAA has no specific standards for airport solar facilities and potential glare, the type of glare analysis may vary. Depending on site specifics (e.g., existing land uses, location and size of the project) an acceptable evaluation could involve one or more of the following levels of assessment:

- (1) A qualitative analysis of potential impact in consultation with the Air Traffic Control Tower, pilots, and airport officials
- (2) A demonstration field test with solar panels at the proposed site in coordination with Air Traffic Control Tower personnel

(3) A geometric analysis to determine days and times when there may be an ocular impact.

The FAA should be consulted after completing each of the following steps to determine if potential reflectivity issues have been adequately considered and addressed.

The extent of reflectivity analysis required to assess potential impacts will depend on the specific project site and system design.”

1. Assessing Baseline Reflectivity Conditions

“Reflection in the form of glare is present in current aviation operations. The existing sources of glare come from glass windows, auto surface parking, rooftops, and water bodies. At airports, existing reflecting surfaces may include hangar roofs, surface parking, and glassy office buildings. To minimize unexpected glare, windows of air traffic control towers and airplane cockpits are coated with anti-reflective glazing. Operators also wear polarized eye wear. Potential glare from solar panels should be viewed in this context. Any airport considering a solar PV project should first review existing sources of glare at the airport and the effectiveness of measures used to mitigate that glare.”

2. Tests in the Field

“Potential glare from solar panels can easily be viewed at the airport through a field test. A few airports have coordinated these tests with FAA Air Traffic Controllers to assess the significance of glare impacts. To conduct such a test, a sponsor can take a solar panel out to proposed location of the solar project, and tilt the panel in different directions to evaluate the potential for glare onto the air traffic control tower. For the two known cases where a field test was conducted, tower personnel determined the glare was not significant. If there is a significant glare impact, the project can be modified by ensuring panels are not directed in that direction.”

3. Geometric Analysis

“Geometric studies are the most technical approach for reflectivity issues. They are conducted when glare is difficult to assess through other methods. Studies of glare can employ geometry and the known path of the sun to predict when sunlight will reflect off of a fixed surface (like a solar panel) and contact a fixed receptor (e.g., control tower). At any given site, the sun moves across the sky every day and its path in the sky changes throughout year. This in turn alters the destination of the resultant reflections since the angle of reflection for the solar panels will be the same as the angle at which the sun hits the panels. The larger the reflective surface, the greater the likelihood of glare impacts. Figure 17 provides an example of such a geometric analysis (not shown).

Facilities placed in remote locations, like the desert, will be far from receptors and therefore potential impacts are limited to passing aircraft. Because the intensity of the light reflected from the solar panel decreases with increasing distance, an appropriate question is how far you need to be from a solar reflected surface to avoid flash blindness. It is known that this distance is directly proportional to the size of the array in question²³ but still requires further research to definitively answer.

The FAA Airport Facilities Terminal Integration Laboratory (AFTIL), located at the William J. Hughes Technical Centre at Atlantic City International Airport, provides system capabilities to evaluate control tower interior design and layout, site selection and orientation, height determination studies, and the transition of equipment into the airport traffic control tower environment. AFTIL regularly conducts computer assessments of potential penetrations of airspace for proposed airport design projects and has modelled the potential characteristics of glare sources, though not for solar projects. AFTIL may be a resource for regional FAA officials and sponsors who seek to evaluate the potential effects of glare from proposed solar projects.”

Experiences of Existing Airport Solar Projects

“Solar installations are presently operating at a number of airports, including megawatt-sized solar facilities covering multiple acres. Air traffic control towers have expressed concern about glint and glare from a small number of solar installations. These were often instances, where solar installations were sited between the tower and airfield, or for installations with inadequate or no reflectivity analysis. Adequate reflectivity analysis and alternative siting addressed initial issues at those installations.”

Appendix C: Assumptions, Limitations & Fixed Model Variables

1. The sun position and glare analysis will be determined throughout the year on a 1-minute basis.
2. The maximum amount of solar power striking surface normal to the sun per unit area (Peak direct normal irradiance, DNI) is set at 1,000 W/m². This will be scaled for each time step to account for changing sun position.
3. The average subtended angle of the sun as viewed from earth is 9.3 mrad.
4. The ocular transmission coefficient for the radiation that is absorbed in the eye before reaching the retina, is set to 0.5.^{11,12}
5. Observer pupil diameter is set at the typical value of 0.002 m for daylight.^{11,12}
6. Eye focal length for the distance between the nodal point (where rays intersect in the eye) and the retina is set at the typical value of 0.017 m.^{11,12}
7. The algorithm does not rigorously represent the detailed geometry of a system; detailed features such as gaps between modules, variable height of the PV array, and support structures may impact actual glare results. However, models have been validated against several systems, including a PV array causing glare to the air-traffic control tower at Manchester-Boston Regional Airport and several sites in Albuquerque, and the tool accurately predicted the occurrence and intensity of glare at different times and days of the year.¹³
8. The algorithm assumes that the PV array is aligned with a plane defined by the total heights (ground elevation plus PV array height) of the coordinates outlined in the Google map.
9. The actual DNI on any given day can be affected by cloud cover, atmospheric attenuation, and other environmental factors. As such, calculated DNI may vary from actual DNI experienced by observer.
10. The system output calculation is a DNI-based approximation that assumes clear, sunny skies all year-round.
11. Hazard zone boundaries shown in the Glare Hazard plot are an approximation and visual aid. Actual ocular impact outcomes encompass a continuous, not discrete, spectrum.
12. Glare locations displayed on receptor plots are approximate. Actual glare-spot locations may differ.
13. Glare vector plots are simplified representations of analysis data. Actual glare emanations and results may differ.
14. PV array tracking assumes the modules move instantly when tracking the sun, and when reverting to the rest position.

¹¹ Ho, C. K., Ghanbari, C. M., and Diver, R. B., 2011, Methodology to Assess Potential Glint and Glare Hazards From Concentrating Solar Power Plants: Analytical Models and Experimental Validation, ASME J. Sol. Energy Eng., 133.

¹² Sliney, D.H. and B.C. Freasier, 1973, Evaluation of Optical Radiation Hazards, Applied Optics, 12(1), p. 1-24.

¹³ <https://www.forgesolar.com/help/#assumptions>

Mabbett®

Safety

CDOIF Environmental Risk Tolerability Assessment
Chemical Management
COMAH Regulations Compliance Support
Consequence Modelling
Control of Electromagnetic Fields (EMF)
DSEAR & Hazardous Area Classification
Functional Safety
Health & Safety Compliance & Consultancy

Hazard Analysis Critical Control Point (HACCP)
Hazard & Operability Studies (HAZOP)
Local Exhaust Ventilation (LEV) Examination & Testing
Occupational Hygiene
Occupied Building Risk Assessment (OBRA)
Reliability Engineering
Risk Analysis Studies
Risk Assessment & Management

Mabbett®

Environment

Air Quality Assessment
Best Available Technique (BAT) Services
Circular Economy, Waste Reduction & Compliance
Contaminated Land Services
Construction Environment Services
Ecological & Ornithological Surveys
Environmental Impact Assessment (EIA)
Environmental Monitoring

Legal Compliance
Management Systems (ISO 9001, 14001, 45001, 50001)
Noise Impact Support
Permitting Support
Planning Services & Community Consultation
Policy Development
Secondment Services
Flood Risk Assessment

Mabbett®

Engineering

Air Pollution Control
Anaerobic Digestion
Electrical & Mechanical Isolations
Energy, Water & Waste
Industrial Effluent Treatment

Local Exhaust Ventilation (LEV) Design
Management, Operation & Maintenance
Mechanical & Electrical Engineering Design
Process Engineering
Renewable Energy Systems

Mabbett®

Training

Bespoke Environmental, Health & Safety Training
IEMA Approved Environmental Training
IOSH Approved Health & Safety Training

Contact Us:

0141 227 2300
info@mabbett.eu
www.mabbett.eu

Please connect with us at Mabbett Ltd:

LinkedIn: <https://www.linkedin.com/company/mabbett>
Twitter: <https://twitter.com/MabbettEU>



SAFETY
SCHEMES IN
PROCUREMENT



Mabbett & Associates Ltd, Corporate and Registered Office: 13 Henderson Road, Inverness, UK, IV1 1SN
Registered in Scotland No: SC 163378 info@mabbett.eu www.mabbett.eu

[Anglesey](#) | [Belfast](#) | [Caerphilly](#) | [Carlisle](#) | [Dublin](#) | [Dundee](#) | [Edinburgh](#) | [Forres](#) | [Glasgow](#) | [Inverness](#) | [Leicester](#) | [Liverpool](#) | [Winchester](#)

© 2023, Mabbett & Associates Ltd. All Rights Reserved. The name Mabbett and the Mabbett logo are Trade Marks licensed to Mabbett & Associates Ltd.