Amendment		Date
-	Planning Issue	16.07.2020
A	Listed Building GF updates to suit Phase 1 works	31.08.2023
B	Listed Building GF tags to suit Phase 1 works	18.09.2023

Elevation Key:

01	Pigmented (red) pre-cast concrete (acid etched unless stated)	08	Notional lettering formed in pre-cast	15	Bronzed PPC aluminium frame with glazing	22	Coloured PPC aluminium frame with glazing
02	Pigmented (red) pre-cast concrete - polished face	09	Notional signage zone	16	Bronzed PPC aluminium frame with back-painted glazing	23	Coloured PPC aluminium doorset
03	Pigmented (red) pre-cast concrete - form-lined pattern	10	Stone-faced concrete upstand	17	Bronzed PPC aluminium balustrade	24	Coloured PPC aluminium doorset with glazing
04	Pigmented (red/brown) pre-cast concrete (acid etched unless stated)	11	Brick-faced pre-cast concrete	18	Bronzed PPC aluminium doorset	25	Coloured PPC aluminium louvres
05	Pigmented (red/brown) pre-cast concrete - polished face	12	Hit and miss brickwork screen	19	Bronzed PPC aluminium doorset with glazing	26	Coloured PPC aluminium cill / coping
06	PPC mastic joint with aggregate finish to match pre-cast facade	13	Articulated parapet brick-faced pre-cast concrete	20	Bronzed PPC aluminium service panel	27	Coloured PPC aluminium frame with steel doors
07	PPC mastic joint with mortar finish to match pre-cast facade	14	Existing refurbished facade (refer to LBC drawings)	21	Bronzed PPC aluminium curtain walling (set-back to terrace)		

0m 5m

Scale:100

FeildenCleggBradleyStudios LLP

Bath Brewery
Toll Bridge Road
Bath BA1 7DE

t 01225 852545
f 01225 852528
e bath@fcbstudios.com

Project Name	Project No.	Amendment
PICCADILLY HOTEL, MANCHESTER	1936-FCBS-ZZ-ZZ-PL-A-0805	B

PROPOSED ELEVATION
NORTH EAST - BACK PICCADILLY

Scale 1:100 @ A1 (1:200 @ A3)
Date JULY 2020
Drawn FCBS-MCR

Do not scale

All dimensions to be checked on site

Original printed at A1

All information subject to site surveys