



PROPOSED RESIDENTIAL DEVELOPMENT, KINGSWAY, BURNAGE

TRANSPORT ASSESSMENT

OCTOBER 2023

PROPOSED RESIDENTIAL DEVELOPMENT, KINGSWAY, BURNAGE

TRANSPORT ASSESSMENT

TRIPLE JERSEY

Final Issue

Project no: 21894-001

Date: October 2023

Andrew Moseley Associates
15 St Paul's Street
Leeds
LS1 2JG

www.amatp.co.uk

Q U A L I T Y M A N A G E M E N T

ISSUE/REVISION	FIRST ISSUE	REVISION 1	REVISION 2	REVISION 3
Remarks	First Issue	Final Issue		
Date	06.10.23	26.10.23		
Prepared by	JF	JF		
Checked by	ATM	ATM		
Authorised by	ATM	ATM		

P R O D U C T I O N T E A M

AMA

Managing Director	Andrew Moseley
Principal Transport Planner	Jacky Fitzpatrick

TABLE OF CONTENTS

1	INTRODUCTION.....	8
1.1	OVERVIEW	8
1.2	PRE-APPLICATION SCOPING	8
1.3	REPORT STRUCTURE	9
2	POLICY BACKGROUND	10
2.1	NATIONAL POLICY	10
2.2	REGIONAL POLICY	11
2.3	LOCAL POLICY	11
3	EXISTING CONDITIONS.....	13
3.1	SITE LOCATION.....	13
3.2	LOCAL HIGHWAY NETWORK.....	13
3.3	COLLISION DATA	14
4	EXISTING SUSTAINABLE TRANSPORT PROVISION	15
4.1	INTRODUCTION	15
4.2	WALKING ACCESSIBILITY.....	15
4.3	CYCLING ACCESSIBILITY	16
4.4	PUBLIC TRANSPORT	16
4.5	ACCESSIBLE AMENITIES	17
4.6	SUMMARY	17
5	PROPOSED DEVELOPMENT	18
5.1	DEVELOPMENT PROPOSALS.....	18
5.2	ACCESS AND SERVICING ARRANGEMENTS	18
5.3	PARKING	18
6	ASSESSMENT PARAMETERS	20

6.1	INTRODUCTION	20
6.2	BASE TRAFFIC SURVEYS	20
6.3	TRAFFIC GROWTH	20
6.4	EXISTING TRAFFIC GENERATION AND ASSIGNMENT	20
6.5	DEVELOPMENT TRAFFIC GENERATION	21
6.6	DEVELOPMENT TRAFFIC DISTRIBUTION AND ASSIGNMENT	21
6.7	RESIDUAL TRIP GENERATION	21
6.8	SUMMARY	22
7	FUTURE DEVELOPMENT IMPACTS	23
7.1	INTRODUCTION	23
7.2	A34 KINGSWAY / TALBOT ROAD / GRANGETHORPE DRIVE	23
7.3	SUMMARY	24
8	SUMMARY	25
	APPENDICES	27

T A B L E S

Table 3-1 Summary of Personal Injury Collision Data.....	14
Table 4-1 National Cycle Routes in Vicinity of Site	16
Table 4-2 Local Bus Services	16
Table 4-3 Accessible Amenities	17
Table 6-1 Traffic Growth Factors.....	20
Table 6-2 Existing Trips	20
Table 6-3 Trip Rates and Trips	21
Table 6-4 Residual Trip Generation	21
Table 7-1 A34 Kingsway / Talbot Road / Grangethorpe Drive Capacity Modelling Results.....	24

FIGURES

Figure 1 – Site Location Plan

Figure 2 – 2km Walking Isochrone

Figure 3 – 5km Cycling Isochrone

Figure 4 – Local Cycle Infrastructure

Figure 5 – Local Bus Stops

Figure 6 – Existing Development Trips

Figure 7 – Proposed Development Distribution

Figure 8 – Proposed Development Trips

Figure 9 – Residual Trip Generation

Figure 10 – 2023 Base Scenario

Figure 11 – 2028 Do Nothing Scenario

Figure 12 – 2028 Do Minimum Scenario

APPENDICES

Appendix A – Personal Injury Collision Data Plot

Appendix B – Proposed Site Layout

Appendix C – Site Access and Visibility Splays

Appendix D – Swept Path Analysis

Appendix E – Proposed Signal Junction Improvements

Appendix F – TRICS Trip Rates

Appendix G – LinSig Outputs

1 INTRODUCTION

1.1 OVERVIEW

- 1.1.1 Andrew Moseley Associates (AMA) have been commissioned by Triple Jersey to produce this Transport Assessment (TA) in connection with the submission of a planning application for the redevelopment of an existing retail unit at Kingsway, Burnage to provide residential development.
- 1.1.2 The site is located approximately 5km southeast of Manchester city centre, within the suburb of Withington. The site is currently occupied by a B&M retail store and associated parking facilities. The site is bound to the north by Talbot Road, to the east by Kingsway, to the south by existing commercial units and to the west by the Styal railway line. The site location is shown in **Figure 1**.
- 1.1.3 The Local Planning Authority (LPA) and Local Highway Authority (LHA) is Manchester City Council (MCC).
- 1.1.4 The purpose of this report is to review the local highway network and the accessibility of the proposed development site and to assess the impacts of the development in a local transport context.
- 1.1.5 This TS demonstrates the site is in an accessible location with good access to sustainable transport modes, in accordance with the National Planning Policy Framework (NPPF). It will also demonstrate that the vehicle trips generated as a result of the development proposals would not be material.

1.2 PRE-APPLICATION SCOPING

- 1.2.1 Pre-application scoping discussions have been undertaken with MCC to agree the scope of this TA and to seek advice on the access strategy and internal site layout. Some of the key elements that were agreed during these discussions:
- ▶ The principle of reconfiguring the access onto Talbot Road to provide two-way vehicle movements;
 - ▶ Provision of push button pedestrian crossing facilities on the Talbot Road arm of the Kingsway / Talbot Road / Grangethorpe Drive signalised junction; and
 - ▶ Provision of parking below the local standards given the highly sustainable location of the site.

1.3 REPORT STRUCTURE

1.3.1 The structure of the report is set out as follows:

- ▶ Section 2 – sets out the local and national transport planning policy against which the proposals have been assessed;
- ▶ Section 3 - describes the site location and the local highway network;
- ▶ Section 4 – reviews the existing sustainable transport infrastructure in and around the proposed development site;
- ▶ Section 5 – sets out the development proposals including the proposed access arrangements and car parking provision;
- ▶ Section 6 – details the assessment parameters used to assess the impact of the proposals;
- ▶ Section 7 – assesses the impact of the proposals on the local highway network; and
- ▶ Section 8 – provides a summary and conclusions.

2 POLICY BACKGROUND

2.1 NATIONAL POLICY

2.1.1 The National Planning Policy Framework (NPPF) came into effect in 2012. The document was designed to supersede and simplify previous national planning documents and their policies. The latest revision of the NPPF was adopted in 2023.

2.1.2 The preparation of this TA is consistent with the guidance set out in the NPPF, which advocates the submission of such documents to support applications for new developments which generate traffic movements.

2.1.3 The NPPF states under the subheading 'Considering development proposals' that:

The NPPF states under the subheading 'Considering development proposals' that:

'In assessing sites that may be allocated for development in plans, or specific applications for development, it should be ensured that:

a) appropriate opportunities to promote sustainable transport modes can be – or have been – taken up, given the type of development and its location;

b) safe and suitable access to the site can be achieved for all users;

c) the design of streets, parking areas, other transport elements and the content of associated standards reflects current national guidance, including the National Design Guide and the National Model Design Code 46; and

c) any significant impacts from the development on the transport network (in terms of capacity and congestion), or on highway safety, can be cost effectively mitigated to an acceptable degree (Paragraph 110).

Development should only be prevented or refused on highways grounds if there would be an unacceptable impact on highway safety, or the residual cumulative impacts on the road network would be severe (Paragraph 111).

Within this context, applications for development should:

a) give priority first to pedestrian and cycle movements, both within the scheme and with neighbouring areas; and second – so far as possible – to facilitating access to high quality public transport, with layouts that maximise the catchment area for bus or other public transport services, and appropriate facilities that encourage public transport use;

b) address the needs of people with disabilities and reduced mobility in relation to all modes of transport;

c) create places that are safe, secure and attractive – which minimise the scope for conflicts between pedestrians, cyclists and vehicles, avoid unnecessary street clutter, and respond to local character and design standards;

d) allow for the efficient delivery of goods, and access by service and emergency vehicles; and

e) be designed to enable charging of plug-in and other ultra-low emission vehicles in safe, accessible and convenient locations (Paragraph 112).

All developments that will generate significant amounts of movement should be required to provide a travel plan, and the application should be supported by a transport statement or transport assessment so that the likely impacts of the proposal can be assessed Paragraph 113).'

- 2.1.4 **Section 3** of this report highlights the existing sustainable travel modes within the vicinity of the site and demonstrates that the development will be well suited to this location.
- 2.1.5 **Section 7** of this report assesses the traffic associated with the development on the surrounding road network and will identify mitigation measures where necessary to ensure that the impact of the development is not severe.
- 2.1.6 The Government's objectives set out in the revised NPPF are to ensure that new developments are provided in sustainable locations, where the need to travel is minimised and the use of sustainable modes can be maximised.

2.2 REGIONAL POLICY

- 2.2.1 Transport for the North (TfN) became England's first sub-national transport body in April 2018. As a partnership TfN encompasses 20 local transport authorities in northern England, together with Network Rail and National Highways, to plan and prioritise long-term infrastructure investment in the North.
- 2.2.2 TfNs role is to add strategic value by ensuring value by ensuring that funding and strategy decisions about transport in the North are informed by local knowledge and requirements. TfN published its Strategic Transport Plan (STP) in 2019 setting out proposals for the northern transport network to 2050. The STP is being updated and a draft for consultation was published in May 2023.
- 2.2.3 TFNs core vision is to have 'a thriving North of England, where world class transport supports sustainable economic growth, excellent quality of life and improved opportunities for all'. Supporting this vision are the four pan-Northern transport objectives, which are:
 - ▶ Transforming economic performance;
 - ▶ Increasing efficiency, reliability, integration, and resilience in the transport system;
 - ▶ Improving inclusivity, health, and access to opportunities for all; and
 - ▶ Promoting and enhancing the built, historic and natural environment.

2.3 LOCAL POLICY

Greater Manchester Transport Strategy

- 2.3.1 The Greater Manchester Transport Strategy (GMTS) sets out the long-term proposals to 2040 to create a cleaner, greener, more prosperous city region through better transport connections and simpler travel. This includes the aspiration for 50% of all journeys in Greater Manchester to be made by walking, cycling and public transport by 2040.
- 2.3.2 Integration is at the heart of the strategy with an ambition to create a high-quality network for Greater Manchester that enables people to move efficiently and effortlessly between different modes of

transport. Integrated land use and transport planning are recognised as key tools in realising this ambition.

- 2.3.3 Policy 4 states that new developments should be accessible by sustainable modes to reduce transport emissions and impacts on the highway network.

Manchester City Council Core Strategy

- 2.3.4 Manchester's Core Strategy was adopted in July 2012 and outlines the Council's vision for development of the city up to 2027.

- 2.3.5 Policy T1 considers sustainable transport and sets out that the Council will support proposals that, amongst other things:

- ▶ Improve choice by developing alternatives to the car;
- ▶ Improve access to transport services and facilities in order to enable disabled people and people with mobility impairments to participate fully in public life;
- ▶ Improve pedestrian routes and the pedestrian environment;
- ▶ Improve and develop further Manchester's cycle network;
- ▶ Contribute to improvements to the extent and reliability of the public transport network through safe and attractive waiting and interchange facilities, better priority, improved services and information provision;
- ▶ Facilitate modes of transport that reduce carbon emissions e.g. by incorporating charging points for electric vehicles, subject to their appropriate design and location; and
- ▶ Would reduce the negative impacts of road traffic, for example, congestion, air pollution and road accident casualties.

- 2.3.6 Policy T2 details that the Council will actively manage the pattern of development, ensuring that new development is well located for walking, cycling and public transport access.

Manchester Residential Quality Guidance

- 2.3.7 The Residential Quality Guidance document was published in 2017 and outlines the considerations, qualities and opportunities to help deliver high quality residential development as part of successful and sustainable neighbourhoods. In terms of transport, the Council will require developers to demonstrate how proposals:

- ▶ Facilitate and encourage walking and cycling;
- ▶ Create clear, safe and obvious connections to the public transport network;
- ▶ Define a clear street hierarchy; and
- ▶ Support opportunities to improve wayfinding and orientation.

3 EXISTING CONDITIONS

3.1 SITE LOCATION

- 3.1.1 The site is located approximately 5km southeast of Manchester city centre, within the suburb of Withington. The site is currently occupied by a B&M retail store and associated parking facilities. The site is bound to the north by Talbot Road, to the east by Kingsway, to the south by existing commercial units and to the west by the Styal railway line. The site location is shown in **Figure 1**.

3.2 LOCAL HIGHWAY NETWORK

- 3.2.1 Access is achieved from both the north and the south of the site. The northern access is in-only (one way southbound between access and Talbot Road) and is taken from Talbot Road. The southern access connects with Mauldeth Road at a simple priority junction and allows two-way vehicle movements.
- 3.2.2 The access road serving the site is unadopted, and also provides access to Mauldeth Road Railway Station and an industrial use to the south. To the north of the car park access, the access road is one way, permitting southbound movements only. As such, all vehicles must exist the site via Mauldeth Road.
- 3.2.3 Talbot Road is a two-way, single carriageway road subject to a 20mph speed limit. Lit footways are provided on both sides of the carriageway. Talbot Road routes in a general northeast / southwest alignment. Immediately east of the site it connects with the A34 Kingsway and Grangethorpe Drive at a signalised crossroads. To the southwest, Talbot Road connects with Parsonage Road and Mauldeth Road at a priority crossroads with right turn facilities.
- 3.2.4 Mauldeth Road is a two-way, single carriageway road subject to a 20mph speed limit. Lit footways are provided on both sides of the carriageway. Mauldeth Road routes in a general east / west alignment, connecting with the A34 Kingsway immediately east of the site at a signalised crossroads.
- 3.2.5 To the east, Mauldeth Road continues from Kingsway to connect with Burnage Lane and Avon Road at a signalised staggered crossroads. West of the site, Mauldeth Road connects with Wilmslow Road and Mauldeth Road West at a signalised crossroads. Maldeth Road West continues west to connect with the A5103 Princess Road before continuing west into Chorlton where it connects with the A5145 Barlow Moor Road at a signalised crossroads.
- 3.2.6 The A34 Kingsway is a dual carriageway two-way road which routes in a north / south alignment immediately east of the site. The road is subject to a 40mph speed limit and is provided with lit footways on both sides of the carriageway.
- 3.2.7 The A34 is a strategic corridor which connects with the A57(M) Manchester Ring Road to the north before continuing into the heart of the city centre and connecting with Trinity Way. South of the site, the A34 connects with the M60 Manchester Outer Ring Road at junction 3 and the M56 at junction 1. The A34 continues south through the Greater Manchester suburbs to Stoke-on-Trent, Stafford, Walsall and Birmingham, ultimately connecting with the M42 at junction 4.
- 3.2.8 The site is considered to be well located for access to both local and regional highway networks.

3.3 COLLISION DATA

- 3.3.1 Personal Injury Collision (PIC) data for the local highway network has been obtained from Transport for Greater Manchester (TfGM) for the latest five-year period. The area for assessment includes Talbot Road, Mauldeth Road between its junctions with Talbot Road and Kingsway, and Kingsway between its junctions with Talbot Road and Mauldeth Road. The collision plot is included at **Appendix A** and the data is summarised in **Table 3-1**.

Table 3-1 Summary of Personal Injury Collision Data

Severity	2018*	2019	2020	2021	2022	2023*	Total
Talbot Road / Kingsway / Grangethorpe Drive							
Slight	0	0	1	2	1	0	4
Serious	0	1	0	0	0	0	1
Fatal	0	1	0	0	0	0	1
Mauldeth Road / Kingsway							
Slight	1	5	1	1	0	0	8
Serious	0	0	0	1	0	0	1
Fatal	0	0	0	0	0	0	0
Talbot Road / Mauldeth Road / Parsonage Road							
Slight	0	1	1	1	1	0	4
Serious	0	0	0	0	0	0	0
Fatal	0	0	0	0	0	0	0
Total	1	8	3	5	2	0	19

*2018 data is April – December and 2023 data is January – March.

- 3.3.2 It is noted that there are small clusters of incidents at the two signal junctions on Kingsway, however, this is to be expected given the high number of vehicles using these junctions. The majority of incidents were classified as 'slight' in severity, and where contributory factors were provided, these generally indicated that the collisions were as a result of driver / road user error rather than related to road layout.
- 3.3.3 The majority of incidents were collisions involving cars. Two incidents involved cyclists and two involved motorcycles. One incident involved a motorcycle and a pedestrian and resulted in a fatality. This incident was attributed to the motorcyclist exceeding the speed limit, travelling too fast for conditions and aggressive driving.
- 3.3.4 No incidents were recorded at the site access onto Talbot Road, or the existing access on Mauldeth Road, which demonstrates that these junctions operate safely at the current time.
- 3.3.5 It is not considered that there is a pattern to the existing collision record that would be impacted by the development proposals.

4 EXISTING SUSTAINABLE TRANSPORT PROVISION

4.1 INTRODUCTION

- 4.1.1 The Government's objectives set out in the NPPF are to ensure that new developments are provided in sustainable locations, where the need to travel is minimised and the use of sustainable modes can be maximised.
- 4.1.2 The site has an excellent level of accessibility to sustainable modes of transport, which will encourage the use of alternative modes of travel to the private car.
- 4.1.3 This section outlines the existing walking, cycling and public transport facilities within the vicinity of the site and describes the accessibility of the site in terms of its proximity to key services and destinations.

4.2 WALKING ACCESSIBILITY

- 4.2.1 Whilst superseded by the NPPF, the transport policies set out in the former PPG13 set out specific guidance related to walking:
"Walking is the most important mode of travel at the local level and offers the greatest potential to replace short car trips, particularly under 2 kilometres" (Para 74)
- 4.2.2 Consideration has been given to the existing pedestrian facilities in the vicinity of the proposed development. A plan showing a 2km walking catchment from the centre of the site is attached at **Figure 2**.
- 4.2.3 This demonstrates that much of the surrounding residential area can be accessed within a reasonable walking distance of the site. A summary of those facilities that can be accessed within a 2km walk is provided in **Table 4-3**.
- 4.2.4 The surrounding highway network has an established network of interconnected footways and crossing points. Lit footways are provided along the length of the access road serving the site. To the south, adjacent to Mauldeth Road Railway Station, the footway is provided on the opposite side of the carriageway, and a marked zebra crossing is provided which offers pedestrian priority in this location.
- 4.2.5 Outside the site, dropped kerbs are provided over most local junctions. To the east of the site, controlled crossing facilities are provided at both the Talbot Road / Kingsway / Grangethorpe Drive and the Mauldeth Road / Kingsway signalised junctions. An informal pedestrian crossing point is provided over Kingsway between these two junctions, adjacent to Burnside Drive.
- 4.2.6 The site is therefore considered to be accessible on foot and is within an acceptable walking distance of key destinations in the local area.

4.3 CYCLING ACCESSIBILITY

4.3.1 Whilst superseded by the NPPF, the transport policies set out in the former PPG13 set out specific guidance related to cycling:

“Cycling also has potential to substitute for short car trips, particularly those under 5 kilometres, and to form part of a longer journey by public transport” (Para 77).

4.3.2 The plan attached at **Figure 3** shows a 5km cycling catchment from the site. The 5km cycling catchment includes the southern extents of Manchester, Chorlton, Heaton and Stockport.

4.3.3 The site is well connected to the local and strategic cycle network, as shown at **Figure 4**. Many of the roads neighbouring the site are subject to a 20mph speed limit and are therefore considered suitable for on-carriageway cycling.

4.3.4 A number of National Cycle Routes (NCR) operate within the vicinity of the site. Routes 6, 60 and 55 route in a general east / west direction to the north of the site. Routes 62 and 558 operate in a general east / west alignment to the south of the site. These routes are summarised in **Table 4-1**.

Table 4-1 National Cycle Routes in Vicinity of Site

Route No.	Route	Local Connections
6	London – Lake District	Manchester, Bury, Sheffield
55	Ironbridge – Preston	Heaton, Trafford, Bolton, Marple, Macclesfield
60	North Manchester – East Manchester	Withington, Harpurhey
62	Fleetwood – Selby	Stockport, Hadfield, Stretford, Warrington
558	Stockport – Herald Green	Cheadle

4.3.5 It is therefore considered that there is good opportunity for future residents to cycle to and from the site.

4.4 PUBLIC TRANSPORT

4.4.1 A number of bus stops are provided close to the site on Kingsway and Mauldeth Road. Those stops within a 400m walk distance of the site are shown at **Figure 5**. The stops closest to the site on Kingsway are provided with off-carriageway bus laybys and shelter facilities. The stops closest to the site on Mauldeth Road are provided with shelters.

4.4.2 A summary of the routes serving these stops and their frequency is provided in **Table 4-2**.

Table 4-2 Local Bus Services

Service	Route	Mon-Fri	Saturday	Sunday
25	Stockport – intu Trafford Centre	30 mins	30 mins	30 mins
50	Media City – East Didsbury	12 mins	12 mins	15 mins
51	Media City – East Didsbury	7 per day (AM)	-	-
728	Moss Side – Barlow High School	School Service	-	-
749	Moss Side – Barlow High School	School Service	-	-
750	Manchester – Barlow High School	School Service	-	-
750S	Levenshulme – Loreto Grammar	School Service	-	-
751	Manchester – Barlow High School	School Service	-	-

- 4.4.3 The local bus stops are served by approximately six services per hour, seven-days per week, providing access to key local destinations.
- 4.4.4 Mauldeth Road Railway Station sits adjacent to the site and can be accessed within less than one minute on foot. The station is operated by Northern Railway and provides four services per hour to destinations including Crewe, Liverpool, Manchester and Manchester Airport.
- 4.4.5 The Metrolink can be accessed from East Didsbury, via a 35-minute walk, 14-minute cycle or a 12-minute journey by public transport (either by rail or the number 50 bus).

4.5 ACCESSIBLE AMENITIES

- 4.5.1 There are a significant number of amenities located within close proximity to the site. Some of these are listed in **Table 4-3**.

Table 4-3 Accessible Amenities

Amenity	Distance	Walk Time	Cycle Time
Mauldeth Road Railway Station	140m	2 mins	1 mins
Mauldeth Road Primary School	400m	4 mins	2 mins
Rainbows Nursery	350m	4 mins	2 mins
Place of Worship	250m	3 mins	1 min
Takeaway	350m	5 mins	3 mins
Londis Convenience Store	400m	6 mins	3 mins
Burnage Community Sports and Social Club	450m	6 mins	3 mins
Hairdressers	400m	5 mins	3 mins
Co-op Food	600m	7 mins	2 mins
Mauldeth Pharmacy	500m	6 mins	2 mins
Mauldeth Medical Centre	650m	8 mins	2 mins
Ladybarn Lane Post Office	900m	11 mins	2 mins
Kingswood Park Playground	900m	11 mins	2 mins
Sainsburys Supermarket	1.6km	19 mins	5 mins
Burnage Academy for Boys	1km	13 mins	5 mins
Levenshulme High School	1.2km	15 mins	6 mins

- 4.5.2 It is therefore demonstrated that the site is located with ready access to a wide range of local amenities.

4.6 SUMMARY

- 4.6.1 The existing pedestrian, cycle, and public transport facilities within the vicinity of the site are of a high quality and the site is within a highly sustainable location with ready access to a range of local amenities.
- 4.6.2 It is therefore considered that the everyday journeys undertaken by future residents can be undertaken without reliance on the private car. The site is therefore considered to be in sustainable location for travel by non-car modes, in line with local and national planning policy.

5 PROPOSED DEVELOPMENT

5.1 DEVELOPMENT PROPOSALS

- 5.1.1 The proposals comprise the redevelopment of the existing retail store to provide 112 residential dwellings. The proposed site layout is included at **Appendix B**.

5.2 ACCESS AND SERVICING ARRANGEMENTS

- 5.2.1 Access to the site will be achieved from the existing access points on Talbot Road and Mauldeth Road. The northern access onto Talbot Road will be reconfigured to enable two-way vehicle movements.
- 5.2.2 This access will measure 5.5m in width with a 4m western radius and an 8m eastern radius. Visibility splays of 2.4m by 25m can be achieved, in accordance with the posted 20mph speed limit and the guidance set out within Manual for Streets. The proposed access design is included at **Appendix C**.
- 5.2.3 The internal road will be narrowed to 5.5m in width, which is typical of a residential access road. A 3m shared footway / cycleway will be provided on the eastern side of the carriageway, providing access to the residential development as well as Mauldeth Road Railway Station.
- 5.2.4 No changes are proposed to the existing service road to the south of the site. Residents will be able to make use of this access road as required, however, this is outside of the site ownership boundary.
- 5.2.5 Bin stores will be provided throughout the site, within a reasonable carry distance for residents and within a compliant drag distance for refuse collection. Refuse will be collected from the main access road serving the site.
- 5.2.6 Vehicle swept path analysis of the site has been undertaken to demonstrate that the necessary vehicles can access and egress the site in a forward gear and use the proposed turning heads. These drawings are included at **Appendix D**.
- 5.2.7 The proposals also incorporate the provision of pedestrian crossing push-button facilities on the Talbot Road arm of the adjacent signalised junction with the A34 Kingsway, to better facilitate pedestrian movements north from the site. The drawings indicating this are included at **Appendix E**.

5.3 PARKING

- 5.3.1 The parking standards for new development in Manchester are set out in the Council's Core Strategy at Appendix B. However, no specific standards are set for residential development. Within Manchester's Residential Quality Guide, the 'comply or justify' approach is outlined, and recommended standards for residential development outside the city centre are set as 100% provision as a starting point. However, reduced on site provision may be justified on the basis of:
- ▶ Secure cycle parking in excess of 50% provision relative to apartment numbers (4 cycle spaces per car park space);
 - ▶ Identification of sufficient off-site capacity within 5 minutes' walk of the proposed development;
 - ▶ Provision of designated on-street parking;

- ▶ Demonstrating that provision of full parking provision will unacceptably comprise the development's active frontages and relationship with the street, and evidence that alternative parking solutions cannot be viably accommodated; and
- ▶ Provision of robust research and market evidence to demonstrate that lower levels of car parking demand will be appropriate.

- 5.3.2 In total, 86 parking spaces are proposed, which equates to a ratio of 0.77 spaces per unit. Each of the three and four-bed dwellings will each be provided with an allocated parking space. The remainder of the parking spaces will be unallocated and therefore the use of these spaces will be flexible.
- 5.3.3 Consideration has been given to the Department for Communities and Local Government (DCLG) Residential Car Parking Research Report (May 2007). This report identifies that, among other things, car ownership is influenced by dwelling type, tenure and location. Households occupying rented accommodation can have up to 0.5 fewer cars than owner-occupied households in dwellings of similar size and type.
- 5.3.4 The provision of much of the parking within the site as unallocated also means that no additional visitor parking is necessary: *"whilst there are times such as evenings and weekends, when residents are likely to receive significant numbers of visitors in cars, this demand can to some degree be offset by other residents being away at the same time"*.
- 5.3.5 It is therefore considered that the proposed level of parking is sufficient to meet the needs of the site without resulting in overspill parking on the highway network.
- 5.3.6 Cycle storage will be provided across the site, providing at least one space per unit. The houses with gardens will be provided with sheds in which they can store cycles. For houses without gardens, dedicated cycle stores are proposed adjacent to the bin stores. The apartments will be provided with dedicated shared cycle storage within each block.

6 ASSESSMENT PARAMETERS

6.1 INTRODUCTION

- 6.1.1 This section sets out the methodology and parameters used in assessing the proposed development and its potential impact on the highway network.

6.2 BASE TRAFFIC SURVEYS

- 6.2.1 Base traffic data for the A34 Kingsway / Talbot Road / Grangethorpe Drive signalised junction has been obtained from TfGM. The surveys were undertaken in 2021 and are considered appropriate to use to understand the development impacts of the proposed development.

6.3 TRAFFIC GROWTH

- 6.3.1 In order to assess the operation of the highway network in the current and future year, traffic growth rates have been derived using the Department for Transport software TEMPro. The TEMPro outputs have been factored by the National Transport Model using Middle Super Output Area (MSOA) Manchester 036, which is considered the most representative MSOA of the proposed development site.
- 6.3.2 The future assessment year of 2028 has been assessed, providing a five-year horizon in which the development is likely to be built out. The output growth factors are shown in **Table 6-1**.
- 6.3.3 The factors for an 'urban principal' road have been applied to the A34 Kingsway, and the factors for an 'urban minor' road to the Talbot Road and Grangethorpe Drive arms of the junction.

Table 6-1 Traffic Growth Factors

Period	Urban Principal		Urban Minor	
	AM Peak	PM Peak	AM Peak	PM Peak
2021-2023	1.031	1.0312	1.0325	1.0327
2021-2028	1.0988	1.0998	1.103	1.104

- 6.3.4 Given that the above TEMPro growth rates have been applied, no specific committed development sites have been considered within this assessment.

6.4 EXISTING TRAFFIC GENERATION AND ASSIGNMENT

- 6.4.1 As noted, the site is currently operational as a B&M store. Traffic surveys were undertaken on Tuesday 6th June 2023. These surveys included observations of vehicle movements into and out of the car park. This data is summarised in **Table 6-2** below for the peak hours of 08:00-09:00 and 17:00-18:00.

Table 6-2 Existing Trips

	AM Peak		PM Peak	
	Arrivals	Departures	Arrivals	Departures
Trips	39	23	106	92

- 6.4.2 The existing site generates 62 two-way trips in the morning peak hour and 198 two-way trips in the evening peak hour.

6.4.3 At the current time, vehicles can arrive from the north and the south, but can only exit to the south of the site. In the AM peak, 64% of trips arrived from the north and 36% arrived from the south. In the PM peak 51% arrived from the north and 49% arrived from the south.

6.4.4 Outside of the site, the existing trips have been assigned to the local highway network based on Census Journey to Work data, which is discussed further below. The existing trips on the local network are shown graphically at **Figure 6**.

6.5 DEVELOPMENT TRAFFIC GENERATION

6.5.1 The trip generation of the proposed development has been assessed using the national TRICS trip rate database. Sites in the category '03 Residential; K Mixed Private Houses (Flats and Houses)' in England, Scotland and Wales (excluding Greater London) have been considered.

6.5.2 Only those sites in Suburban Area and Edge of Town locations have been considered, and any surveys undertaken during the Covid 19 pandemic have been excluded.

6.5.3 The full TRICS outputs are included at **Appendix F**. The peak hour trip rates and associated trips are summarised in **Table 6-3**.

Table 6-3 Trip Rates and Trips

	AM Peak		PM Peak	
	Arrivals	Departures	Arrivals	Departures
Trip Rates	0.102	0.316	0.291	0.147
Trips (1,396sqm)	11	35	33	16

6.5.4 The table above indicates that the proposed development could generate a total of 47 two-way trips in the morning peak hour and 49 two-way trips in the evening peak hour.

6.6 DEVELOPMENT TRAFFIC DISTRIBUTION AND ASSIGNMENT

6.6.1 The development traffic has been distributed onto the local highway network using 2011 Census Journey to Work data for MSOA Manchester 036. The resulting distribution is shown graphically in **Figure 7**, and has been applied to the proposed development trips, as shown in **Figure 8**.

6.7 RESIDUAL TRIP GENERATION

6.7.1 The residual trip generation of the site can be calculated by subtracting the existing trip generation of the site from the proposed trip generation. The results of this exercise are demonstrated graphically at **Figure 9** and are summarised in **Table 6-4**.

Table 6-4 Residual Trip Generation

	AM Peak		PM Peak	
	Arrivals	Departures	Arrivals	Departures
Residual Trips	-28	12	-73	-76

6.7.2 The above table indicates that the residual trip generation of the site would be -15 two-way trips in the AM peak hour and -149 two-way trips in the PM peak hour. Albeit it is acknowledged that the assignment of these trips on the local highway network will be different.

6.8 SUMMARY

- 6.8.1 Traffic growth on the local highway network has been accounted for using TEMPro.
- 6.8.2 The trip generation of the proposals has been quantified using the TRICS trip rate database. These trips have been assigned to the local highway network based on 2011 Census Journey to Work data.
- 6.8.3 The assessment has not taken account of the implementation of a Travel Plan at the site, which has the potential to reduce private car trips to and from the proposed development.
- 6.8.4 In summary, the trip generation and distribution methodology adopted in this TA is considered appropriate and robust.

7 FUTURE DEVELOPMENT IMPACTS

7.1 INTRODUCTION

7.1.1 This section of the TA provides an assessment of the transport impacts that may arise as a result of the proposed development.

7.1.2 Capacity modelling has been completed assuming the following scenarios for both the AM and PM peak hours:

- ▶ 2023 Base (**Figure 10**);
- ▶ 2028 Do Nothing (future year base traffic) (**Figure 11**); and
- ▶ 2028 Do Minimum (as above plus development traffic and inclusive of controlled crossing over Talbot Road) (**Figure 11**).

7.1.3 The A34 Kingsway / Talbot Road / Grangethorpe Drive junction has been modelled using LinSig. As requested during pre-application discussions, in the 2028 Do Minimum development scenario, a controlled pedestrian crossing on the Talbot Road arm of the junction has been incorporated.

7.1.4 The outputs of LinSig include the Degree of Saturation (DoS), the Mean Maximum Queue (MMQ) and the Practical Reserve Capacity (PRC). The DoS is a ratio of demand to capacity for each traffic phase, with a value of 90% indicating that an arm is at practical capacity. The PRC is calculated from the maximum percent DoS and is a measure of how much additional traffic could pass through the junction as a whole. The MMQ provides an indication of how the overall junction performance may affect adjacent junctions on the highway network and is set out in passenger car units (PCUs).

7.2 A34 KINGSWAY / TALBOT ROAD / GRANGETHORPE DRIVE

7.2.1 The results of the modelling exercise are summarised in **Table 7-1** and the full model outputs are included at **Appendix G**.

Table 7-1 A34 Kingsway / Talbot Road / Grangethorpe Drive Capacity Modelling Results

Scenario	Link	AM Peak		PM Peak	
		DoS	MMQ	DoS	MMQ
2023 Base	A34 Kingsway N	81.4%	23	71.9%	17
	Grangethorpe Drive	78.5%	9	58.9%	6
	A34 Kingsway S	58.2%	12	40.6%	6
	Talbot Road	74.8%	9	69.8%	8
	PRC	10.6%		25.1%	
	Total Delay (pcu/hr)	24.9		20.1	
2028 Do Nothing	A34 Kingsway N	86.7%	27	76.3%	19
	Grangethorpe Drive	83.6%	10	72.9%	8
	A34 Kingsway S	63.8%	14	43.3%	7
	Talbot Road	79.8%	10	74.8%	9
	PRC	3.8%		18.0%	
	Total Delay (pcu/hr)	29.6		23.6	
2028 Do Minimum	A34 Kingsway N	67.9%	14	76.1%	19
	Grangethorpe Drive	65.7%	8	61.9%	6
	A34 Kingsway S	67.5%	15	41.3%	7
	Talbot Road	66.9%	9	76.9%	10
	PRC	32.6%		17.1%	
	Total Delay (pcu/hr)	24.8		22.7	

7.2.2 The junction is shown to operate within capacity at the current time, with modest queueing experienced on the A34 Kingsway arms. The junction is expected to continue to operate well in the future, albeit with less spare capacity, particularly in the AM peak.

7.2.3 Once the development flows are considered, and the signalised crossing of Talbot Road is included, the junction is expected to operate better than the 2028 Do Nothing scenario in the AM peak. Queues on the A34 Kingsway northern arm and Grangethorpe Drive arm are expected to reduce. In the PM peak, the addition of the proposed development has a minimal impact on the operation of the junction, with a slight reduction in total delay experienced.

7.2.4 The proposals are therefore expected to have a beneficial impact on the operation of this junction, given that they will result in a net reduction in vehicle trips accessing the site when compared with the existing use.

7.3 SUMMARY

7.3.1 Overall, it is not considered that the proposed development will result in any severe impacts on the local highway network, and in fact is expected to improve the operation of the A34 Kingsway / Talbot Road / Grangethorpe Drive junction in the AM peak.

8 SUMMARY

- 8.1.1 Andrew Moseley Associates (AMA) have been commissioned by Triple Jersey to produce this Transport Assessment (TA) in connection with the submission of a planning application for the redevelopment of an existing retail unit at Kingsway, Burnage to provide residential development.
- 8.1.2 The site is located sustainably, with an excellent standard of pedestrian and cycle infrastructure providing access to nearby amenities. Regular bus services can be accessed within a short walk of the site, and Mauldeth Road Railway Station is located immediately adjacent to the site, providing regular rail services to destinations including Manchester, Manchester Airport, Crewe and Liverpool. It is therefore considered that future residents will not be reliant on the private car.
- 8.1.3 The proposals comprise the redevelopment of the existing retail store to provide 112 residential dwellings. Access to the site will be achieved from the existing access points on Talbot Road and Mauldeth Road, with the Talbot Road access reconfigured to provide two-way vehicle movements. Within the site a 3m wide shared footway / cycleway will be provided on the eastern side of the carriageway. In addition, a push-button facility will be installed on the Talbot Road arm of the adjacent junction with the A34 Kingsway, to enable controlled pedestrian crossing facilities in this location.
- 8.1.4 The level of parking at the site is reflective of the highly sustainable location and the type of dwellings proposed. This has been agreed with MCC during pre-application discussions. Cycle parking is proposed across the site, with at least one space per unit proposed.
- 8.1.5 The proposed redevelopment is expected to result in a net reduction in vehicle trips on the local highway network.
- 8.1.6 The impact of the development on the nearby Talbot Road / Kingsway / Grangethorpe Drive junction has been assessed using LinSig software. This demonstrates that the proposals are expected to improve the operation of this junction when compared with the 2028 base year scenario.
- 8.1.7 As such, it can be concluded that the impact of the development on the local road network will not be material, and will not lead to any severe cumulative impacts, nor adversely impact upon the existing highway safety record.
- 8.1.8 Given that set out above, it is not considered that there should be any highway-related objections to the proposed development.

FIGURES


- Figure 1 – Site Location Plan
- Figure 2 – 2km Walking Isochrone
- Figure 3 – 5km Cycling Isochrone
- Figure 4 – Local Cycle Infrastructure
- Figure 5 – Local Bus Stops
- Figure 6 – Existing Development Trips
- Figure 7 – Proposed Development Distribution
- Figure 8 – Proposed Development Trips
- Figure 9 – Residual Trip Generation
- Figure 10 – 2023 Base Scenario
- Figure 11 – 2028 Do Nothing Scenario
- Figure 12 – 2028 Do Minimum Scenario

Key:
Site Location





Title:
Indicative Site location Plan
B&M Kingsway, Burnage

Figure No.: Figure 1	Drawn By: IJT
-------------------------	------------------



Title:
2km Walking Catchment Plan
B&M Kingsway, Burnage



















APPENDICES

[Appendix A – Personal Injury Collision Data Plot](#)

[Appendix B – Proposed Site Layout](#)

[Appendix C – Site Access and Visibility Splays](#)

[Appendix D – Swept Path Analysis](#)

[Appendix E – Proposed Signal Junction Improvements](#)

[Appendix F – TRICS Trip Rates](#)

[Appendix G – LinSig Outputs](#)

Appendix A

PERSONAL INJURY COLLISION DATA PLOT



Appendix B

PROPOSED SITE LAYOUT

KINGSWAY, BURNAGE


Notes:



PLANNING LAYOUT LAYERS

Boundary treatments

- 1.8m High Brick wall
- 1.8m High Close boarded timber fence
- 1.2m High Metal railings
- Tree/vegetation to be retained.
- Root protection Zone.
- Tree/vegetation to be removed.
- Gate
- Plot Bin Store
- Bike Store



Accommodation Schedule							
Name	Floor Area Sq Ft	Beds	Persons	Storeys	Accom	No.	Total
Type 1	792	2	4	2	2B	6	4752
Type 2	906	2	4	3	2B	48	43488
Type 3	1128	3	4	2	3B	16	18048
Type 4	1305	4	6	3	4B	8	10440
Type 5 - Apt	537	1	2	3	1B	2	1074
	676	2	3	3	2B	21	14196
	666	2	3	4	2B	3	1998
	667	2	3	4	2B	8	5336
Sub Total						112	99332

Scaled @ 1:500
0 10m 20m 50m

STEN

ARCHITECTURE

STEN Architecture Ltd
The Station
The Square
Warrington
CH9 1PE
Tel: 01924 959595

Web: www.sten-architecture.co.uk
Twitter: [@sten_arch](https://twitter.com/sten_arch)
Facebook: [stenarchitecture](https://www.facebook.com/stenarchitecture)
LinkedIn: [Sten Architecture](https://www.linkedin.com/company/sten-architecture)

CLIENT:

TRIPLE JERSEY LIMITED

SITE:

KINGSWAY
BURNAGE

TITLE:

PLANNING LAYOUT

SCALE AT A3:

1:500

DATE:

AUG 23

DRAWN:

SSH

CHECKED:

-

PROJECT NO.:

2305

DRAWING NO.:

2305.01:PL

REVISION:

B

PLANNING LAYOUT

Appendix C

SITE ACCESS AND VISIBILITY SPLAYS



TO TIE INTO EXISTING FOOTWAY

2.4m BY 25m VISIBILITY SPLAY

2.4m BY 25m VISIBILITY SPLAY

R. 4m

R. 8m

5.5m

3m

5.5m

3m

DROPPED KERB

5.5m

3m

5.5m

3m

DROPPED KERB

TO TIE INTO EXISTING

12 NO
CYCLE
SPACES

Notes

P01	First Issue	DD/MM/YY	-
Rev	Description	Date	By



Project. B&M Kingsway, Burnage

Client. Triple Jersey Limited

Drawing. Proposed Access Option



Drawn By: MSF	Date: 05/10/2023
---------------	------------------

Checked By: JF	Scale: 1:500	Paper size: A3
----------------	--------------	----------------


Drawing No. AMA/21894/SK007	Rev. P01
-----------------------------	----------

Appendix D

SWEPT PATH ANALYSIS



Notes




Phoenix 2-25W (with Volvo FM12 chassis)	11.125m
Overall Length	2.530m
Overall Width	3.205m
Overall Body Height	0.410m
Min Body Ground Clearance	2.500m
Track Width	4.00s
Lock to lock time	9.250m
Kerb to Kerb Turning Radius	

P01	First Issue	DD/MM/YY	-
Rev	Description	Date	By
			
Project.	B&M Kingsway, Burnage		
Client.	Triple Jersey Limited		
Drawing.	Large Refuse Vehicle Swept Path Analysis Access & Egress		
Drawn By:	MSF	Date:	09/10/2023
Checked By:	JF	Scale:	1:250
Drawing No.	AMA/21894/ATR003	Paper size:	A3
		Rev.	P01

Appendix E

PROPOSED SIGNAL JUNCTION IMPROVEMENTS



Notes

P01	First Issue	DD/MM/YY	-
Rev	Description	Date	By



Project. B&M Kingsway, Burnage

Client. Triple Jersey Limited

Drawing. Signalised Junction

Drawn By: RID	Date: 22/09/2023
Checked By: JF	Scale: 1:500
Drawing No. AMA/21894/SK006	Paper size: A3
	Rev. P01

Appendix F

TRICS TRIP RATES

AMA - Leeds

Licence No: 710001

Calculation Reference: AUDIT-710001-230919-0932

TRIP RATE CALCULATION SELECTION PARAMETERS:

Land Use : 03 - RESIDENTIAL
 Category : K - MIXED PRIV HOUS (FLATS AND HOUSES)
 TOTAL VEHICLES

Selected regions and areas:

02	SOUTH EAST	
	ES EAST SUSSEX	1 days
	HC HAMPSHIRE	2 days
	WS WEST SUSSEX	2 days
03	SOUTH WEST	
	CW CORNWALL	1 days
04	EAST ANGLIA	
	CA CAMBRIDGESHIRE	2 days
05	EAST MIDLANDS	
	DY DERBY	1 days
	NG NOTTINGHAM	1 days
09	NORTH	
	FU WESTMORLAND & FURNESS	1 days
10	WALES	
	CO CONWY	1 days

This section displays the number of survey days per TRICS® sub-region in the selected set

Primary Filtering selection:

This data displays the chosen trip rate parameter and its selected range. Only sites that fall within the parameter range are included in the trip rate calculation.

Parameter: No of Dwellings
 Actual Range: 15 to 618 (units:)
 Range Selected by User: 15 to 788 (units:)

Parking Spaces Range: All Surveys Included

Parking Spaces per Dwelling Range: All Surveys Included

Bedrooms per Dwelling Range: All Surveys Included

Percentage of dwellings privately owned: All Surveys Included

Public Transport Provision:

Selection by: Include all surveys

Date Range: 01/01/15 to 02/11/22

This data displays the range of survey dates selected. Only surveys that were conducted within this date range are included in the trip rate calculation.

Selected survey days:

Monday	3 days
Tuesday	3 days
Wednesday	1 days
Thursday	5 days

This data displays the number of selected surveys by day of the week.

Selected survey types:

Manual count	12 days
Directional ATC Count	0 days

This data displays the number of manual classified surveys and the number of unclassified ATC surveys, the total adding up to the overall number of surveys in the selected set. Manual surveys are undertaken using staff, whilst ATC surveys are undertaken using machines.

Selected Locations:

Suburban Area (PPS6 Out of Centre)	3
Edge of Town	9

This data displays the number of surveys per main location category within the selected set. The main location categories consist of Free Standing, Edge of Town, Suburban Area, Neighbourhood Centre, Edge of Town Centre, Town Centre and Not Known.

Selected Location Sub Categories:

This data displays the number of surveys per location sub-category within the selected set. The location sub-categories consist of Commercial Zone, Industrial Zone, Development Zone, Residential Zone, Retail Zone, Built-Up Zone, Village, Out of Town, High Street and No Sub Category.

Inclusion of Servicing Vehicles Counts:

Servicing vehicles Included	4 days - Selected
Servicing vehicles Excluded	11 days - Selected

Secondary Filtering selection:

Use Class:

C3	12 days
----	---------

This data displays the number of surveys per Use Class classification within the selected set. The Use Classes Order (England) 2020 has been used for this purpose, which can be found within the Library module of TRICS®.

Population within 500m Range:

All Surveys Included

Population within 1 mile:

1,001 to 5,000	1 days
5,001 to 10,000	4 days
10,001 to 15,000	4 days
15,001 to 20,000	1 days
20,001 to 25,000	2 days

This data displays the number of selected surveys within stated 1-mile radii of population.

Population within 5 miles:

25,001 to 50,000	4 days
50,001 to 75,000	3 days
75,001 to 100,000	1 days
125,001 to 250,000	2 days
250,001 to 500,000	2 days

This data displays the number of selected surveys within stated 5-mile radii of population.

Car ownership within 5 miles:

0.6 to 1.0	3 days
1.1 to 1.5	7 days
1.6 to 2.0	2 days

This data displays the number of selected surveys within stated ranges of average cars owned per residential dwelling, within a radius of 5-miles of selected survey sites.

Travel Plan:

Yes	5 days
No	7 days

This data displays the number of surveys within the selected set that were undertaken at sites with Travel Plans in place, and the number of surveys that were undertaken at sites without Travel Plans.

PTAL Rating:

No PTAL Present	12 days
-----------------	---------

This data displays the number of selected surveys with PTAL Ratings.

AMA - Leeds

Licence No: 710001

LIST OF SITES relevant to selection parameters

1	CA-03-K-01	MIXED HOUSES & FLATS	CAMBRIDGESHIRE
	WEASANHAM LANE		
	WISBECH		
	FENLAND		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	100	
	Survey date: MONDAY	07/09/15	Survey Type: MANUAL
2	CA-03-K-04	MIXED HOUSES & FLATS	CAMBRIDGESHIRE
	FORDHAM ROAD		
	SOHAM		
	Suburban Area (PPS6 Out of Centre)		
	Residential Zone		
	Total No of Dwellings:	65	
	Survey date: WEDNESDAY	11/07/18	Survey Type: MANUAL
3	CO-03-K-01	MIXED HOUSES & FLATS	CONWY
	LIDDELL DRIVE		
	LLANDUDNO		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	15	
	Survey date: TUESDAY	27/03/18	Survey Type: MANUAL
4	CW-03-K-01	MIXED HOUSES & FLATS	CORNWALL
	TRELOWEN DRIVE		
	PENRYN		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	89	
	Survey date: THURSDAY	28/03/19	Survey Type: MANUAL
5	DY-03-K-01	MIXED HOUSES & FLATS	DERBY
	PRIDE PARKWAY		
	DERBY		
	WILMORTON		
	Edge of Town		
	Industrial Zone		
	Total No of Dwellings:	618	
	Survey date: MONDAY	23/07/18	Survey Type: MANUAL
6	ES-03-K-01	MIXED HOUSES & FLATS	EAST SUSSEX
	LEWES ROAD		
	UCKFIELD		
	RIDGEWOOD		
	Edge of Town		
	Residential Zone		
	Total No of Dwellings:	64	
	Survey date: THURSDAY	14/07/16	Survey Type: MANUAL
7	FU-03-K-01	SEMI-DETACHED & FLATS	WESTMORLAND & FURNESS
	NATLAND ROAD		
	KENDAL		
	Suburban Area (PPS6 Out of Centre)		
	Residential Zone		
	Total No of Dwellings:	15	
	Survey date: TUESDAY	21/06/16	Survey Type: MANUAL

AMA - Leeds

Licence No: 710001

LIST OF SITES relevant to selection parameters (Cont.)

8	HC-03-K-02 DAIRY ROAD ANDOVER	MIXED HOUSES & FLATS	HAMPSHIRE
	Edge of Town Residential Zone Total No of Dwellings: 270 Survey date: TUESDAY 11/10/22		Survey Type: MANUAL
9	HC-03-K-07 MINLEY ROAD FARNBOROUGH BLACKWATER	MIXED HOUSES & FLATS	HAMPSHIRE
	Edge of Town Residential Zone Total No of Dwellings: 313 Survey date: THURSDAY 12/05/22		Survey Type: MANUAL
10	NG-03-K-02 CASTLE BRIDGE ROAD NOTTINGHAM	MIXED HOUSES	NOTTINGHAM
	Suburban Area (PPS6 Out of Centre) No Sub Category Total No of Dwellings: 132 Survey date: MONDAY 07/11/16		Survey Type: MANUAL
11	WS-03-K-03 LITTLEHAMPTON ROAD WORTHING WEST DURRINGTON	MIXED HOUSES & FLATS	WEST SUSSEX
	Edge of Town Residential Zone Total No of Dwellings: 111 Survey date: THURSDAY 12/05/16		Survey Type: MANUAL
12	WS-03-K-04 HILLS FARM LANE HORSHAM BROADBRIDGE HEATH	MIXED HOUSES & FLATS	WEST SUSSEX
	Edge of Town Residential Zone Total No of Dwellings: 371 Survey date: THURSDAY 28/06/18		Survey Type: MANUAL

This section provides a list of all survey sites and days in the selected set. For each individual survey site, it displays a unique site reference code and site address, the selected trip rate calculation parameter and its value, the day of the week and date of each survey, and whether the survey was a manual classified count or an ATC count.

MANUALLY DESELECTED SURVEYS

Site Ref	Survey Date	Reason for Deselection
BL-03-K-01	17/05/21	Undertaken during Covid 19
BO-03-K-01	15/10/20	Undertaken during Covid 19
GM-03-K-03	06/05/21	Undertaken during Covid 19

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

TOTAL VEHICLES

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.064	12	180	0.263	12	180	0.327
08:00 - 09:00	12	180	0.102	12	180	0.316	12	180	0.418
09:00 - 10:00	12	180	0.110	12	180	0.147	12	180	0.257
10:00 - 11:00	12	180	0.118	12	180	0.131	12	180	0.249
11:00 - 12:00	12	180	0.102	12	180	0.115	12	180	0.217
12:00 - 13:00	12	180	0.135	12	180	0.117	12	180	0.252
13:00 - 14:00	12	180	0.131	12	180	0.134	12	180	0.265
14:00 - 15:00	12	180	0.131	12	180	0.160	12	180	0.291
15:00 - 16:00	12	180	0.215	12	180	0.142	12	180	0.357
16:00 - 17:00	12	180	0.219	12	180	0.136	12	180	0.355
17:00 - 18:00	12	180	0.291	12	180	0.147	12	180	0.438
18:00 - 19:00	12	180	0.271	12	180	0.152	12	180	0.423
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			1.889			1.960			3.849

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

The survey data, graphs and all associated supporting information, contained within the TRICS Database are published by TRICS Consortium Limited ("the Company") and the Company claims copyright and database rights in this published work. The Company authorises those who possess a current TRICS licence to access the TRICS Database and copy the data contained within the TRICS Database for the licence holders' use only. Any resulting copy must retain all copyrights and other proprietary notices, and any disclaimer contained thereon.

The Company accepts no responsibility for loss which may arise from reliance on data contained in the TRICS Database. [No warranty of any kind, express or implied, is made as to the data contained in the TRICS Database.]

Parameter summary

Trip rate parameter range selected: 15 - 618 (units:)
 Survey date range: 01/01/15 - 02/11/22
 Number of weekdays (Monday-Friday): 15
 Number of Saturdays: 0
 Number of Sundays: 0
 Surveys automatically removed from selection: 3
 Surveys manually removed from selection: 0

This section displays a quick summary of some of the data filtering selections made by the TRICS® user. The trip rate calculation parameter range of all selected surveys is displayed first, followed by the range of minimum and maximum survey dates selected by the user. Then, the total number of selected weekdays and weekend days in the selected set of surveys are shown. Finally, the number of survey days that have been manually removed from the selected set outside of the standard filtering procedure are displayed.

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

TAXIS

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.002	12	180	0.002	12	180	0.004
08:00 - 09:00	12	180	0.003	12	180	0.004	12	180	0.007
09:00 - 10:00	12	180	0.004	12	180	0.004	12	180	0.008
10:00 - 11:00	12	180	0.004	12	180	0.003	12	180	0.007
11:00 - 12:00	12	180	0.003	12	180	0.004	12	180	0.007
12:00 - 13:00	12	180	0.004	12	180	0.004	12	180	0.008
13:00 - 14:00	12	180	0.002	12	180	0.003	12	180	0.005
14:00 - 15:00	12	180	0.006	12	180	0.004	12	180	0.010
15:00 - 16:00	12	180	0.003	12	180	0.004	12	180	0.007
16:00 - 17:00	12	180	0.002	12	180	0.002	12	180	0.004
17:00 - 18:00	12	180	0.003	12	180	0.002	12	180	0.005
18:00 - 19:00	12	180	0.005	12	180	0.005	12	180	0.010
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			0.041			0.041			0.082

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

OGVS

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.001	12	180	0.001	12	180	0.002
08:00 - 09:00	12	180	0.000	12	180	0.000	12	180	0.000
09:00 - 10:00	12	180	0.001	12	180	0.002	12	180	0.003
10:00 - 11:00	12	180	0.004	12	180	0.003	12	180	0.007
11:00 - 12:00	12	180	0.001	12	180	0.002	12	180	0.003
12:00 - 13:00	12	180	0.002	12	180	0.001	12	180	0.003
13:00 - 14:00	12	180	0.002	12	180	0.002	12	180	0.004
14:00 - 15:00	12	180	0.002	12	180	0.003	12	180	0.005
15:00 - 16:00	12	180	0.000	12	180	0.000	12	180	0.000
16:00 - 17:00	12	180	0.001	12	180	0.001	12	180	0.002
17:00 - 18:00	12	180	0.000	12	180	0.000	12	180	0.000
18:00 - 19:00	12	180	0.000	12	180	0.000	12	180	0.000
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			0.014			0.015			0.029

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

PSVS

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.000	12	180	0.000	12	180	0.000
08:00 - 09:00	12	180	0.000	12	180	0.000	12	180	0.000
09:00 - 10:00	12	180	0.000	12	180	0.000	12	180	0.000
10:00 - 11:00	12	180	0.000	12	180	0.000	12	180	0.000
11:00 - 12:00	12	180	0.000	12	180	0.000	12	180	0.000
12:00 - 13:00	12	180	0.000	12	180	0.000	12	180	0.000
13:00 - 14:00	12	180	0.000	12	180	0.000	12	180	0.000
14:00 - 15:00	12	180	0.000	12	180	0.000	12	180	0.000
15:00 - 16:00	12	180	0.000	12	180	0.000	12	180	0.000
16:00 - 17:00	12	180	0.000	12	180	0.000	12	180	0.000
17:00 - 18:00	12	180	0.000	12	180	0.000	12	180	0.000
18:00 - 19:00	12	180	0.000	12	180	0.000	12	180	0.000
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			0.000			0.000			0.000

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

CYCLISTS

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.005	12	180	0.014	12	180	0.019
08:00 - 09:00	12	180	0.008	12	180	0.028	12	180	0.036
09:00 - 10:00	12	180	0.004	12	180	0.007	12	180	0.011
10:00 - 11:00	12	180	0.005	12	180	0.006	12	180	0.011
11:00 - 12:00	12	180	0.003	12	180	0.004	12	180	0.007
12:00 - 13:00	12	180	0.006	12	180	0.004	12	180	0.010
13:00 - 14:00	12	180	0.003	12	180	0.003	12	180	0.006
14:00 - 15:00	12	180	0.006	12	180	0.006	12	180	0.012
15:00 - 16:00	12	180	0.017	12	180	0.012	12	180	0.029
16:00 - 17:00	12	180	0.012	12	180	0.005	12	180	0.017
17:00 - 18:00	12	180	0.016	12	180	0.006	12	180	0.022
18:00 - 19:00	12	180	0.009	12	180	0.004	12	180	0.013
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			0.094			0.099			0.193

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

CARS

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.049	12	180	0.234	12	180	0.283
08:00 - 09:00	12	180	0.087	12	180	0.294	12	180	0.381
09:00 - 10:00	12	180	0.087	12	180	0.128	12	180	0.215
10:00 - 11:00	12	180	0.092	12	180	0.100	12	180	0.192
11:00 - 12:00	12	180	0.084	12	180	0.088	12	180	0.172
12:00 - 13:00	12	180	0.106	12	180	0.095	12	180	0.201
13:00 - 14:00	12	180	0.103	12	180	0.108	12	180	0.211
14:00 - 15:00	12	180	0.110	12	180	0.135	12	180	0.245
15:00 - 16:00	12	180	0.186	12	180	0.116	12	180	0.302
16:00 - 17:00	12	180	0.190	12	180	0.113	12	180	0.303
17:00 - 18:00	12	180	0.264	12	180	0.130	12	180	0.394
18:00 - 19:00	12	180	0.252	12	180	0.139	12	180	0.391
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			1.610			1.680			3.290

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

LGVS

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.012	12	180	0.023	12	180	0.035
08:00 - 09:00	12	180	0.011	12	180	0.016	12	180	0.027
09:00 - 10:00	12	180	0.018	12	180	0.014	12	180	0.032
10:00 - 11:00	12	180	0.018	12	180	0.023	12	180	0.041
11:00 - 12:00	12	180	0.014	12	180	0.020	12	180	0.034
12:00 - 13:00	12	180	0.021	12	180	0.015	12	180	0.036
13:00 - 14:00	12	180	0.022	12	180	0.018	12	180	0.040
14:00 - 15:00	12	180	0.014	12	180	0.017	12	180	0.031
15:00 - 16:00	12	180	0.024	12	180	0.020	12	180	0.044
16:00 - 17:00	12	180	0.024	12	180	0.020	12	180	0.044
17:00 - 18:00	12	180	0.019	12	180	0.014	12	180	0.033
18:00 - 19:00	12	180	0.013	12	180	0.008	12	180	0.021
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			0.210			0.208			0.418

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

AMA - Leeds

Licence No: 710001

TRIP RATE for Land Use 03 - RESIDENTIAL/K - MIXED PRIV HOUS (FLATS AND HOUSES)

MOTOR CYCLES

Calculation factor: 1 DWELLS

BOLD print indicates peak (busiest) period

Time Range	ARRIVALS			DEPARTURES			TOTALS		
	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate	No. Days	Ave. DWELLS	Trip Rate
00:00 - 01:00									
01:00 - 02:00									
02:00 - 03:00									
03:00 - 04:00									
04:00 - 05:00									
05:00 - 06:00									
06:00 - 07:00									
07:00 - 08:00	12	180	0.000	12	180	0.002	12	180	0.002
08:00 - 09:00	12	180	0.000	12	180	0.002	12	180	0.002
09:00 - 10:00	12	180	0.000	12	180	0.000	12	180	0.000
10:00 - 11:00	12	180	0.000	12	180	0.002	12	180	0.002
11:00 - 12:00	12	180	0.000	12	180	0.001	12	180	0.001
12:00 - 13:00	12	180	0.001	12	180	0.002	12	180	0.003
13:00 - 14:00	12	180	0.002	12	180	0.002	12	180	0.004
14:00 - 15:00	12	180	0.000	12	180	0.000	12	180	0.000
15:00 - 16:00	12	180	0.001	12	180	0.001	12	180	0.002
16:00 - 17:00	12	180	0.002	12	180	0.000	12	180	0.002
17:00 - 18:00	12	180	0.005	12	180	0.000	12	180	0.005
18:00 - 19:00	12	180	0.001	12	180	0.000	12	180	0.001
19:00 - 20:00									
20:00 - 21:00									
21:00 - 22:00									
22:00 - 23:00									
23:00 - 24:00									
Total Rates:			0.012			0.012			0.024

This section displays the trip rate results based on the selected set of surveys and the selected count type (shown just above the table). It is split by three main columns, representing arrivals trips, departures trips, and total trips (arrivals plus departures). Within each of these main columns are three sub-columns. These display the number of survey days where count data is included (per time period), the average value of the selected trip rate calculation parameter (per time period), and the trip rate result (per time period). Total trip rates (the sum of the column) are also displayed at the foot of the table.

To obtain a trip rate, the average (mean) trip rate parameter value (TRP) is first calculated for all selected survey days that have count data available for the stated time period. The average (mean) number of arrivals, departures or totals (whichever applies) is also calculated (COUNT) for all selected survey days that have count data available for the stated time period. Then, the average count is divided by the average trip rate parameter value, and multiplied by the stated calculation factor (shown just above the table and abbreviated here as FACT). So, the method is: $COUNT/TRP*FACT$. Trip rates are then rounded to 3 decimal places.

Appendix G

LINSIG OUTPUTS


Full Input Data And Results

Full Input Data And Results


User and Project Details

Project:	21894 Kingsway, Burnage
Title:	Talbot Road / Kingsway / Grangethorpe Drive
Location:	Burnage, Manchester
Additional detail:	
File name:	Kingsway, Burnage.lsg3x
Author:	BD/JF
Company:	AMA
Address:	15 St Paul's Street, Leeds

Network Layout Diagram



Phase Diagram



Full Input Data And Results

Phase Input Data

Phase Name	Phase Type	Assoc. Phase	Street Min	Cont Min
A	Traffic		7	7
B	Traffic		7	7
C	Traffic		7	7
D	Traffic		7	7
E	Pedestrian		7	7
F	Pedestrian		7	7
G	Pedestrian		7	7
H	Pedestrian		7	7
I	Pedestrian		7	7
J	Pedestrian		7	7

Phase Intergreens Matrix


Terminating Phase	Starting Phase										
		A	B	C	D	E	F	G	H	I	J
	A		9	-	7	-	-	-	7	-	7
	B	7		9	-	7	-	-	6	9	-
	C	-	6		6	-	7	7	-	-	-
	D	7	-	6		7	-	-	-	6	-
	E	-	7	-	7		-	-	-	-	-
	F	-	-	7	-	-		-	-	-	-
	G	-	-	7	-	-	-		-	-	-
	H	7	9	-	-	-	-	-		-	-
	I	-	6	-	7	-	-	-	-		-
	J	7	-	-	-	-	-	-	-	-	

Phases in Stage

Stage No.	Phases in Stage
1	A F G I
2	B F G J
3	C E H J
4	D F G J
5	A C E
6	C E H I J
7	C H J
8	A C
9	A F G I
10	B D F G J
11	C E H J
12	A C
13	A F G I
14	B D F G J

Full Input Data And Results

Stage Diagram



Phase Delays

Term. Stage	Start Stage	Phase	Type	Value	Cont value
1	4	A	Losing	2	2
1	4	I	Losing	2	2

Prohibited Stage Change

	To Stage													
	1	2	3	4	5	6	7	8	9	10	11	12	13	14
From Stage	1		9	7	9	7	7	X	X	X	X	X	X	X
	2	9		9	2	9	9	X	X	X	X	X	X	X
	3	7	9		7	7	0	X	X	X	X	X	X	X
	4	7	2	7		7	7	X	X	X	X	X	X	X
	5	7	9	7	7		7	7	0	7	9	7	0	7
	6	7	9	0	7	7		0	7	7	9	0	7	7
	7	7	9	0	7	7	0		7	7	9	0	7	7
	8	X	X	X	X	0	7	7		7	9	7	0	7
	9	X	X	X	X	7	7	7	7		9	7	7	0
	10	X	X	X	X	9	9	9	9	9		9	9	0
	11	X	X	X	X	7	0	0	7	7	9		7	7
	12	X	X	X	X	0	7	7	0	7	9	7		7
	13	X	X	X	X	7	7	7	7	0	9	7	7	
	14	X	X	X	X	9	9	9	9	9	0	9	9	9

Full Input Data And Results

Give-Way Lane Input Data

Junction: Kingsway x Talbot Road											
Lane	Movement	Max Flow when Giving Way (PCU/Hr)	Min Flow when Giving Way (PCU/Hr)	Opposing Lane	Opp. Lane Coeff.	Opp. Mvmnts.	Right Turn Storage (PCU)	Non-Blocking Storage (PCU)	RTF	Right Turn Move up (s)	Max Turns in Intergreen (PCU)
2/3 (A34 (Kingsway, N))	7/1 (Right)	1439	0	6/2	1.09	All	3.00	-	0.50	3	2.00
				6/3	1.09	All					
				6/4	1.09	All					
				8/1	1.09	To 1/2 (Left) To 3/1 (Ahead) To 5/1 (Right) To 5/2 (Right)					
6/4 (A34 (Kingsway, S))	3/1 (Right)	1439	0	4/2	1.09	All	2.00	-	0.50	2	2.00
				2/1	1.09	All					
				2/2	1.09	All					
				4/2	1.09	All					
				8/1	1.09	To 1/2 (Left) To 3/1 (Ahead) To 5/1 (Right) To 5/2 (Right)					

Lane Input Data

[illegible]

[illegible]

Flow Group	Start Time	End Time	Duration	Formula
1: 'Flow Group 1'	15:30	16:30	01:00	
2: '2023 Base AM'	08:00	09:00	01:00	
3: '2023 Base PM'	17:00	18:00	01:00	
4: '2028 Base AM'	08:00	09:00	01:00	
5: '2028 Base PM'	17:00	18:00	01:00	
6: '2028 Base + Dev AM'	08:00	09:00	01:00	
7: '2028 Base + Dev PM'	17:00	18:00	01:00	

Traffic Flows, Desired

Origin	Destination					
		A	B	C	D	Tot.
	A	0	60	853	129	1042
	B	90	0	45	145	280
	C	1253	76	0	21	1350
	D	84	148	38	0	270
	Tot.	1427	284	936	295	2942

Traffic Lane Flows

Lane	Scenario 1: 2023AM
Junction: Kingsway x Talbot Road	
1/1	717
1/2	710
2/1	913
2/2 (with short)	129(In) 0(Out)
2/3 (short)	129
3/1	284
4/1 (short)	45
4/2 (with short)	280(In) 235(Out)
5/1	895
5/2	41
6/1 (short)	21
6/2 (with short)	651(In) 630(Out)
6/3 (with short)	699(In) 623(Out)
6/4 (short)	76
7/1	295
8/1	270

Full Input Data And Results

Lane Saturation Flows

Junction: Kingsway x Talbot Road								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (A34 (Kingsway, N) Lane 1)	Infinite Saturation Flow						Inf	Inf
1/2 (A34 (Kingsway, N) Lane 2)	Infinite Saturation Flow						Inf	Inf
2/1 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 3 Left	Inf	6.6 %	1945	1945
				Arm 5 Ahead	Inf	93.4 %		
2/2 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 5 Ahead	Inf	0.0 %	1945	1945
2/3 (A34 (Kingsway, N))	3.20	0.00	Y	Arm 7 Right	Inf	100.0 %	1935	1935
3/1 (Grangethorpe Drive Lane 1)	Infinite Saturation Flow						Inf	Inf
4/1 (Grangethorpe Drive)	4.00	0.00	Y	Arm 5 Left	Inf	100.0 %	2015	2015
4/2 (Grangethorpe Drive)	3.30	0.00	Y	Arm 1 Right	Inf	38.3 %	1945	1945
				Arm 7 Ahead	Inf	61.7 %		
5/1 (A34 (Kingsway, S) Lane 1)	Infinite Saturation Flow						Inf	Inf
5/2 (A34 (Kingsway, S) Lane 2)	Infinite Saturation Flow						Inf	Inf
6/1 (A34 (Kingsway, S))	5.00	0.00	Y	Arm 7 Left	Inf	100.0 %	2115	2115
6/2 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/3 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/4 (A34 (Kingsway, S))	3.20	0.00	Y	Arm 3 Right	Inf	100.0 %	1935	1935
7/1 (Talbot Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Talbot Road)	3.60	0.00	Y	Arm 1 Left	Inf	31.1 %	1975	1975
				Arm 3 Ahead	Inf	54.8 %		
				Arm 5 Right	Inf	14.1 %		

Scenario 2: '2023PM' (FG3: '2023 Base PM', Plan 5: 'Existing')

Traffic Flows, Desired

Desired Flow :

Origin	Destination					
		A	B	C	D	Tot.
	A	0	94	1309	175	1578
	B	59	0	40	125	224
	C	797	90	0	32	919
	D	78	160	27	0	265
	Tot.	934	344	1376	332	2986

Traffic Lane Flows

Lane	Scenario 2: 2023PM
Junction: Kingsway x Talbot Road	
1/1	461
1/2	473
2/1	753
2/2 (with short)	825(In) 650(Out)
2/3 (short)	175
3/1	344
4/1 (short)	40
4/2 (with short)	224(In) 184(Out)
5/1	693
5/2	683
6/1 (short)	32
6/2 (with short)	424(In) 392(Out)
6/3 (with short)	495(In) 405(Out)
6/4 (short)	90
7/1	332
8/1	265

Full Input Data And Results

Lane Saturation Flows

Junction: Kingsway x Talbot Road								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (A34 (Kingsway, N) Lane 1)	Infinite Saturation Flow						Inf	Inf
1/2 (A34 (Kingsway, N) Lane 2)	Infinite Saturation Flow						Inf	Inf
2/1 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 3 Left Arm 5 Ahead	Inf Inf	12.5 % 87.5 %	1945	1945
2/2 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 5 Ahead	Inf	100.0 %	1945	1945
2/3 (A34 (Kingsway, N))	3.20	0.00	Y	Arm 7 Right	Inf	100.0 %	1935	1935
3/1 (Grangethorpe Drive Lane 1)	Infinite Saturation Flow						Inf	Inf
4/1 (Grangethorpe Drive)	4.00	0.00	Y	Arm 5 Left	Inf	100.0 %	2015	2015
4/2 (Grangethorpe Drive)	3.30	0.00	Y	Arm 1 Right Arm 7 Ahead	Inf Inf	32.1 % 67.9 %	1945	1945
5/1 (A34 (Kingsway, S) Lane 1)	Infinite Saturation Flow						Inf	Inf
5/2 (A34 (Kingsway, S) Lane 2)	Infinite Saturation Flow						Inf	Inf
6/1 (A34 (Kingsway, S))	5.00	0.00	Y	Arm 7 Left	Inf	100.0 %	2115	2115
6/2 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/3 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/4 (A34 (Kingsway, S))	3.20	0.00	Y	Arm 3 Right	Inf	100.0 %	1935	1935
7/1 (Talbot Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Talbot Road)	3.60	0.00	Y	Arm 1 Left Arm 3 Ahead Arm 5 Right	Inf Inf Inf	29.4 % 60.4 % 10.2 %	1975	1975

Scenario 3: '2028 Base AM' (FG4: '2028 Base AM', Plan 5: 'Existing')

Traffic Flows, Desired

Desired Flow :

Origin	Destination					
	A	B	C	D	Tot.	
	A	0	64	909	137	1110
	B	96	0	49	154	299
	C	1335	81	0	22	1438
	D	89	158	41	0	288
	Tot.	1520	303	999	313	3135

Full Input Data And Results

Traffic Lane Flows

Lane	Scenario 3: 2028 Base AM
Junction: Kingsway x Talbot Road	
1/1	766
1/2	754
2/1	973
2/2 (with short)	137(In) 0(Out)
2/3 (short)	137
3/1	303
4/1 (short)	49
4/2 (with short)	299(In) 250(Out)
5/1	955
5/2	44
6/1 (short)	22
6/2 (with short)	695(In) 673(Out)
6/3 (with short)	743(In) 662(Out)
6/4 (short)	81
7/1	313
8/1	288

Full Input Data And Results

Lane Saturation Flows

Junction: Kingsway x Talbot Road								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (A34 (Kingsway, N) Lane 1)	Infinite Saturation Flow						Inf	Inf
1/2 (A34 (Kingsway, N) Lane 2)	Infinite Saturation Flow						Inf	Inf
2/1 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 3 Left Arm 5 Ahead	Inf Inf	6.6 % 93.4 %	1945	1945
2/2 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 5 Ahead	Inf	0.0 %	1945	1945
2/3 (A34 (Kingsway, N))	3.20	0.00	Y	Arm 7 Right	Inf	100.0 %	1935	1935
3/1 (Grangethorpe Drive Lane 1)	Infinite Saturation Flow						Inf	Inf
4/1 (Grangethorpe Drive)	4.00	0.00	Y	Arm 5 Left	Inf	100.0 %	2015	2015
4/2 (Grangethorpe Drive)	3.30	0.00	Y	Arm 1 Right Arm 7 Ahead	Inf Inf	38.4 % 61.6 %	1945	1945
5/1 (A34 (Kingsway, S) Lane 1)	Infinite Saturation Flow						Inf	Inf
5/2 (A34 (Kingsway, S) Lane 2)	Infinite Saturation Flow						Inf	Inf
6/1 (A34 (Kingsway, S))	5.00	0.00	Y	Arm 7 Left	Inf	100.0 %	2115	2115
6/2 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/3 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/4 (A34 (Kingsway, S))	3.20	0.00	Y	Arm 3 Right	Inf	100.0 %	1935	1935
7/1 (Talbot Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Talbot Road)	3.60	0.00	Y	Arm 1 Left Arm 3 Ahead Arm 5 Right	Inf Inf Inf	30.9 % 54.9 % 14.2 %	1975	1975

Scenario 4: '2028 Base PM' (FG5: '2028 Base PM', Plan 5: 'Existing')

Traffic Flows, Desired

Desired Flow :

Origin	Destination					
	A	B	C	D	Tot.	
	A	0	100	1396	187	1683
	B	96	0	43	134	273
	C	850	96	0	34	980
	D	84	171	29	0	284
	Tot.	1030	367	1468	355	3220

Traffic Lane Flows

Lane	Scenario 4: 2028 Base PM
Junction: Kingsway x Talbot Road	
1/1	509
1/2	521
2/1	808
2/2 (with short)	875(In) 688(Out)
2/3 (short)	187
3/1	367
4/1 (short)	43
4/2 (with short)	273(In) 230(Out)
5/1	745
5/2	723
6/1 (short)	34
6/2 (with short)	453(In) 419(Out)
6/3 (with short)	527(In) 431(Out)
6/4 (short)	96
7/1	355
8/1	284

Full Input Data And Results

Lane Saturation Flows

Junction: Kingsway x Talbot Road								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (A34 (Kingsway, N) Lane 1)	Infinite Saturation Flow						Inf	Inf
1/2 (A34 (Kingsway, N) Lane 2)	Infinite Saturation Flow						Inf	Inf
2/1 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 3 Left	Inf	12.4 %	1945	1945
				Arm 5 Ahead	Inf	87.6 %		
2/2 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 5 Ahead	Inf	100.0 %	1945	1945
2/3 (A34 (Kingsway, N))	3.20	0.00	Y	Arm 7 Right	Inf	100.0 %	1935	1935
3/1 (Grangethorpe Drive Lane 1)	Infinite Saturation Flow						Inf	Inf
4/1 (Grangethorpe Drive)	4.00	0.00	Y	Arm 5 Left	Inf	100.0 %	2015	2015
4/2 (Grangethorpe Drive)	3.30	0.00	Y	Arm 1 Right	Inf	41.7 %	1945	1945
				Arm 7 Ahead	Inf	58.3 %		
5/1 (A34 (Kingsway, S) Lane 1)	Infinite Saturation Flow						Inf	Inf
5/2 (A34 (Kingsway, S) Lane 2)	Infinite Saturation Flow						Inf	Inf
6/1 (A34 (Kingsway, S))	5.00	0.00	Y	Arm 7 Left	Inf	100.0 %	2115	2115
6/2 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/3 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/4 (A34 (Kingsway, S))	3.20	0.00	Y	Arm 3 Right	Inf	100.0 %	1935	1935
7/1 (Talbot Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Talbot Road)	3.60	0.00	Y	Arm 1 Left	Inf	29.6 %	1975	1975
				Arm 3 Ahead	Inf	60.2 %		
				Arm 5 Right	Inf	10.2 %		

Scenario 5: '2028 Base + AM' (FG6: '2028 Base + Dev AM', Plan 6: 'Existing+')

Traffic Flows, Desired

Desired Flow :

Origin	Destination					
		A	B	C	D	Tot.
	A	0	64	909	121	1094
	B	96	0	49	152	297
	C	1326	80	0	22	1428
	D	104	160	41	0	305
	Tot.	1526	304	999	295	3124

Traffic Lane Flows

Lane	Scenario 5: 2028 Base + AM
Junction: Kingsway x Talbot Road	
1/1	771
1/2	755
2/1	644
2/2 (with short)	450(In) 329(Out)
2/3 (short)	121
3/1	304
4/1 (short)	49
4/2 (with short)	297(In) 248(Out)
5/1	626
5/2	373
6/1 (short)	22
6/2 (with short)	693(In) 671(Out)
6/3 (with short)	735(In) 655(Out)
6/4 (short)	80
7/1	295
8/1	305

Full Input Data And Results

Lane Saturation Flows

Junction: Kingsway x Talbot Road								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (A34 (Kingsway, N) Lane 1)	Infinite Saturation Flow						Inf	Inf
1/2 (A34 (Kingsway, N) Lane 2)	Infinite Saturation Flow						Inf	Inf
2/1 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 3 Left Arm 5 Ahead	Inf Inf	9.9 % 90.1 %	1945	1945
2/2 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 5 Ahead	Inf	100.0 %	1945	1945
2/3 (A34 (Kingsway, N))	3.20	0.00	Y	Arm 7 Right	Inf	100.0 %	1935	1935
3/1 (Grangethorpe Drive Lane 1)	Infinite Saturation Flow						Inf	Inf
4/1 (Grangethorpe Drive)	4.00	0.00	Y	Arm 5 Left	Inf	100.0 %	2015	2015
4/2 (Grangethorpe Drive)	3.30	0.00	Y	Arm 1 Right Arm 7 Ahead	Inf Inf	38.7 % 61.3 %	1945	1945
5/1 (A34 (Kingsway, S) Lane 1)	Infinite Saturation Flow						Inf	Inf
5/2 (A34 (Kingsway, S) Lane 2)	Infinite Saturation Flow						Inf	Inf
6/1 (A34 (Kingsway, S))	5.00	0.00	Y	Arm 7 Left	Inf	100.0 %	2115	2115
6/2 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/3 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/4 (A34 (Kingsway, S))	3.20	0.00	Y	Arm 3 Right	Inf	100.0 %	1935	1935
7/1 (Talbot Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Talbot Road)	3.60	0.00	Y	Arm 1 Left Arm 3 Ahead Arm 5 Right	Inf Inf Inf	34.1 % 52.5 % 13.4 %	1975	1975

Scenario 6: '2028 Base+ PM' (FG7: '2028 Base + Dev PM', Plan 6: 'Existing+')

Traffic Flows, Desired

Desired Flow :

Origin	Destination					
	A	B	C	D	Tot.	
	A	0	100	1396	155	1651
	B	63	0	43	130	236
	C	811	91	0	34	936
	D	91	172	29	0	292
	Tot.	965	363	1468	319	3115

Full Input Data And Results

Traffic Lane Flows

Lane	Scenario 6: 2028 Base+ PM
Junction: Kingsway x Talbot Road	
1/1	477
1/2	488
2/1	797
2/2 (with short)	854(In) 699(Out)
2/3 (short)	155
3/1	363
4/1 (short)	43
4/2 (with short)	236(In) 193(Out)
5/1	734
5/2	734
6/1 (short)	34
6/2 (with short)	433(In) 399(Out)
6/3 (with short)	503(In) 412(Out)
6/4 (short)	91
7/1	319
8/1	292

Full Input Data And Results


Lane Saturation Flows

Junction: Kingsway x Talbot Road								
Lane	Lane Width (m)	Gradient	Nearside Lane	Allowed Turns	Turning Radius (m)	Turning Prop.	Sat Flow (PCU/Hr)	Flared Sat Flow (PCU/Hr)
1/1 (A34 (Kingsway, N) Lane 1)	Infinite Saturation Flow						Inf	Inf
1/2 (A34 (Kingsway, N) Lane 2)	Infinite Saturation Flow						Inf	Inf
2/1 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 3 Left Arm 5 Ahead	Inf Inf	12.5 % 87.5 %	1945	1945
2/2 (A34 (Kingsway, N))	3.30	0.00	Y	Arm 5 Ahead	Inf	100.0 %	1945	1945
2/3 (A34 (Kingsway, N))	3.20	0.00	Y	Arm 7 Right	Inf	100.0 %	1935	1935
3/1 (Grangethorpe Drive Lane 1)	Infinite Saturation Flow						Inf	Inf
4/1 (Grangethorpe Drive)	4.00	0.00	Y	Arm 5 Left	Inf	100.0 %	2015	2015
4/2 (Grangethorpe Drive)	3.30	0.00	Y	Arm 1 Right Arm 7 Ahead	Inf Inf	32.6 % 67.4 %	1945	1945
5/1 (A34 (Kingsway, S) Lane 1)	Infinite Saturation Flow						Inf	Inf
5/2 (A34 (Kingsway, S) Lane 2)	Infinite Saturation Flow						Inf	Inf
6/1 (A34 (Kingsway, S))	5.00	0.00	Y	Arm 7 Left	Inf	100.0 %	2115	2115
6/2 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/3 (A34 (Kingsway, S))	3.25	0.00	Y	Arm 1 Ahead	Inf	100.0 %	1940	1940
6/4 (A34 (Kingsway, S))	3.20	0.00	Y	Arm 3 Right	Inf	100.0 %	1935	1935
7/1 (Talbot Road Lane 1)	Infinite Saturation Flow						Inf	Inf
8/1 (Talbot Road)	3.60	0.00	Y	Arm 1 Left Arm 3 Ahead Arm 5 Right	Inf Inf Inf	31.2 % 58.9 % 9.9 %	1975	1975


Stage Sequence Diagram



Signal Timings Diagram



Full Input Data And Results
Network Layout Diagram



Full Input Data And Results

Network Results


Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network	-	-	N/A	-	-		-	-	-	-	-	-	81.4%
Kingsway x Talbot Road	-	-	N/A	-	-		-	-	-	-	-	-	81.4%
1/1	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	717	Inf	Inf	0.0%
1/2	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	710	Inf	Inf	0.0%
2/1	A34 (Kingsway, N) Left Ahead	U	N/A	N/A	A		1	59	-	913	1945	1122	81.4%
2/2+2/3	A34 (Kingsway, N) Ahead Right	U+O	N/A	N/A	A		1	59	-	129	1945:1935	0+181	0.0 : 71.1%
3/1	Grangethorpe Drive	U	N/A	N/A	-		-	-	-	284	Inf	Inf	0.0%
4/2+4/1	Grangethorpe Drive Right Left Ahead	U	N/A	N/A	B		1	16	-	280	1945:2015	299+57	78.5 : 78.5%
5/1	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	895	Inf	Inf	0.0%
5/2	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	41	Inf	Inf	0.0%
6/2+6/1	A34 (Kingsway, S) Ahead Left	U	N/A	N/A	C		1	62	-	651	1940:2115	1139+38	55.3 : 55.3%
6/3+6/4	A34 (Kingsway, S) Ahead Right	U+O	N/A	N/A	C		1	62	-	699	1940:1935	1071+131	58.2 : 58.2%
7/1	Talbot Road	U	N/A	N/A	-		-	-	-	295	Inf	Inf	0.0%
8/1	Talbot Road Left Ahead Right	U	N/A	N/A	D		1	18	-	270	1975	361	74.8%
Ped Link: P1	Unnamed Ped Link	-	N/A	-	E		0	0	-	0	-	0	0.0%
Ped Link: P2	Unnamed Ped Link	-	N/A	-	F		1	26	-	0	-	0	0.0%
Ped Link: P3	Unnamed Ped Link	-	N/A	-	G		1	26	-	0	-	0	0.0%
Ped Link: P4	Unnamed Ped Link	-	N/A	-	H		1	7	-	0	-	0	0.0%

Full Input Data And Results

Ped Link: P5	Unnamed Ped Link	-	N/A	-	J		1	31	-	0	-	0	0.0%
Ped Link: P6	Unnamed Ped Link	-	N/A	-	I		1	8	-	0	-	0	0.0%
Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network	-	-	77	125	4	15.5	7.8	1.5	24.9	-	-	-	-
Kingsway x Talbot Road	-	-	77	125	4	15.5	7.8	1.5	24.9	-	-	-	-
1/1	717	717	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
1/2	710	710	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
2/1	913	913	-	-	-	4.4	2.1	-	6.6	26.0	20.8	2.1	22.9
2/2+2/3	129	129	22	103	4	0.4	1.2	1.1	2.6	73.8	1.7	1.2	2.9
3/1	284	284	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
4/2+4/1	280	280	-	-	-	3.2	1.7	-	4.9	63.4	6.7	1.7	8.5
5/1	895	895	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
5/2	41	41	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2+6/1	651	651	-	-	-	2.2	0.6	-	2.8	15.6	11.0	0.6	11.6
6/3+6/4	699	699	55	21	0	2.3	0.7	0.4	3.4	17.5	11.2	0.7	11.9
7/1	295	295	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	270	270	-	-	-	3.0	1.4	-	4.5	59.5	7.4	1.4	8.8
Ped Link: P1	0	0	-	-	-	-	-	-	Inf	Inf	-	-	Inf
Ped Link: P2	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P3	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P4	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P5	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P6	0	0	-	-	-	-	-	-	-	-	-	-	-
C1 PRC for Signalled Lanes (%): 10.6 Total Delay for Signalled Lanes (pcuHr): 24.86 Cycle Time (s): 104 PRC Over All Lanes (%): 10.6 Total Delay Over All Lanes(pcuHr): 24.86													

Full Input Data And Results
Scenario 2: '2023PM' (FG3: '2023 Base PM', Plan 5: 'Existing')


Stage Sequence Diagram



Stage Timings


Stage	7	8	9	10
Duration	4	51	0	17
Change Point	0	13	71	78

Signal Timings Diagram



Full Input Data And Results

Network Layout Diagram



Full Input Data And Results

Network Results


Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network	-	-	N/A	-	-		-	-	-	-	-	-	71.9%
Kingsway x Talbot Road	-	-	N/A	-	-		-	-	-	-	-	-	71.9%
1/1	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	461	Inf	Inf	0.0%
1/2	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	473	Inf	Inf	0.0%
2/1	A34 (Kingsway, N) Left Ahead	U	N/A	N/A	A		1	58	-	753	1945	1103	68.2%
2/2+2/3	A34 (Kingsway, N) Ahead Right	U+O	N/A	N/A	A		1	58	-	825	1945:1935	904+243	71.9 : 71.9%
3/1	Grangethorpe Drive	U	N/A	N/A	-		-	-	-	344	Inf	Inf	0.0%
4/2+4/1	Grangethorpe Drive Right Left Ahead	U	N/A	N/A	B		1	17	-	224	1945:2015	312+68	58.9 : 58.9%
5/1	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	693	Inf	Inf	0.0%
5/2	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	683	Inf	Inf	0.0%
6/2+6/1	A34 (Kingsway, S) Ahead Left	U	N/A	N/A	C		1	62	-	424	1940:2115	1093+89	35.9 : 35.9%
6/3+6/4	A34 (Kingsway, S) Ahead Right	U+O	N/A	N/A	C		1	62	-	495	1940:1935	997+222	40.6 : 40.6%
7/1	Talbot Road	U	N/A	N/A	-		-	-	-	332	Inf	Inf	0.0%
8/1	Talbot Road Left Ahead Right	U	N/A	N/A	D		1	19	-	265	1975	380	69.8%
Ped Link: P1	Unnamed Ped Link	-	N/A	-	E		0	0	-	0	-	0	0.0%
Ped Link: P2	Unnamed Ped Link	-	N/A	-	F		1	26	-	0	-	0	0.0%
Ped Link: P3	Unnamed Ped Link	-	N/A	-	G		1	26	-	0	-	0	0.0%
Ped Link: P4	Unnamed Ped Link	-	N/A	-	H		1	7	-	0	-	0	0.0%

Full Input Data And Results

Ped Link: P5	Unnamed Ped Link	-	N/A	-	J		1	32	-	0	-	0	0.0%
Ped Link: P6	Unnamed Ped Link	-	N/A	-	I		1	7	-	0	-	0	0.0%
Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network	-	-	162	47	57	14.7	4.8	0.6	20.1	-	-	-	-
Kingsway x Talbot Road	-	-	162	47	57	14.7	4.8	0.6	20.1	-	-	-	-
1/1	461	461	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
1/2	473	473	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
2/1	753	753	-	-	-	3.3	1.1	-	4.4	21.0	15.3	1.1	16.3
2/2+2/3	825	825	162	8	5	3.5	1.3	0.0	4.8	21.0	15.9	1.3	17.2
3/1	344	344	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
4/2+4/1	224	224	-	-	-	2.4	0.7	-	3.1	50.2	4.8	0.7	5.5
5/1	693	693	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
5/2	683	683	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2+6/1	424	424	-	-	-	1.2	0.3	-	1.5	12.7	6.0	0.3	6.3
6/3+6/4	495	495	0	38	52	1.4	0.3	0.5	2.2	16.4	5.9	0.3	6.2
7/1	332	332	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	265	265	-	-	-	2.9	1.1	-	4.0	54.6	7.1	1.1	8.3
Ped Link: P1	0	0	-	-	-	-	-	-	Inf	Inf	-	-	Inf
Ped Link: P2	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P3	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P4	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P5	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P6	0	0	-	-	-	-	-	-	-	-	-	-	-
C1			PRC for Signalled Lanes (%):		25.1	Total Delay for Signalled Lanes (pcuHr):		20.09	Cycle Time (s): 104				
			PRC Over All Lanes (%):		25.1	Total Delay Over All Lanes(pcuHr):		20.09					

Full Input Data And Results
Scenario 3: '2028 Base AM' (FG4: '2028 Base AM', Plan 5: 'Existing')


Stage Sequence Diagram



Stage Timings


Stage	7	8	9	10
Duration	4	49	3	16
Change Point	0	13	69	79

Signal Timings Diagram



Full Input Data And Results

Network Layout Diagram



Full Input Data And Results

Network Results


Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network	-	-	N/A	-	-		-	-	-	-	-	-	86.7%
Kingsway x Talbot Road	-	-	N/A	-	-		-	-	-	-	-	-	86.7%
1/1	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	766	Inf	Inf	0.0%
1/2	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	754	Inf	Inf	0.0%
2/1	A34 (Kingsway, N) Left Ahead	U	N/A	N/A	A		1	59	-	973	1945	1122	86.7%
2/2+2/3	A34 (Kingsway, N) Ahead Right	U+O	N/A	N/A	A		1	59	-	137	1945:1935	0+197	0.0 : 69.6%
3/1	Grangethorpe Drive	U	N/A	N/A	-		-	-	-	303	Inf	Inf	0.0%
4/2+4/1	Grangethorpe Drive Right Left Ahead	U	N/A	N/A	B		1	16	-	299	1945:2015	299+59	83.6 : 83.6%
5/1	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	955	Inf	Inf	0.0%
5/2	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	44	Inf	Inf	0.0%
6/2+6/1	A34 (Kingsway, S) Ahead Left	U	N/A	N/A	C		1	60	-	695	1940:2115	1103+36	61.0 : 61.0%
6/3+6/4	A34 (Kingsway, S) Ahead Right	U+O	N/A	N/A	C		1	60	-	743	1940:1935	1037+127	63.8 : 63.8%
7/1	Talbot Road	U	N/A	N/A	-		-	-	-	313	Inf	Inf	0.0%
8/1	Talbot Road Left Ahead Right	U	N/A	N/A	D		1	18	-	288	1975	361	79.8%
Ped Link: P1	Unnamed Ped Link	-	N/A	-	E		0	0	-	0	-	0	0.0%
Ped Link: P2	Unnamed Ped Link	-	N/A	-	F		1	28	-	0	-	0	0.0%
Ped Link: P3	Unnamed Ped Link	-	N/A	-	G		1	28	-	0	-	0	0.0%
Ped Link: P4	Unnamed Ped Link	-	N/A	-	H		1	7	-	0	-	0	0.0%

Full Input Data And Results													
Ped Link: P5	Unnamed Ped Link	-	N/A	-	J		1	31	-	0	-	0	0.0%
Ped Link: P6	Unnamed Ped Link	-	N/A	-	I		1	10	-	0	-	0	0.0%
Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network	-	-	58	154	6	17.7	10.1	1.8	29.6	-	-	-	-
Kingsway x Talbot Road	-	-	58	154	6	17.7	10.1	1.8	29.6	-	-	-	-
1/1	766	766	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
1/2	754	754	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
2/1	973	973	-	-	-	5.0	3.1	-	8.2	30.2	23.8	3.1	26.9
2/2+2/3	137	137	0	133	4	0.5	1.1	1.2	2.8	73.9	1.8	1.1	2.9
3/1	303	303	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
4/2+4/1	299	299	-	-	-	3.4	2.4	-	5.8	69.9	7.3	2.4	9.7
5/1	955	955	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
5/2	44	44	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2+6/1	695	695	-	-	-	2.7	0.8	-	3.5	17.9	12.9	0.8	13.7
6/3+6/4	743	743	58	21	2	2.8	0.9	0.6	4.3	20.6	13.2	0.9	14.1
7/1	313	313	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	288	288	-	-	-	3.3	1.9	-	5.1	64.2	7.9	1.9	9.8
Ped Link: P1	0	0	-	-	-	-	-	-	Inf	Inf	-	-	Inf
Ped Link: P2	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P3	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P4	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P5	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P6	0	0	-	-	-	-	-	-	-	-	-	-	-
C1 PRC for Signalled Lanes (%): PRC Over All Lanes (%): 3.8 3.8 Total Delay for Signalled Lanes (pcuHr): Total Delay Over All Lanes(pcuHr): 29.63 29.63 Cycle Time (s): 104													

C1	PRC for Signalled Lanes (%):	3.8	Total Delay for Signalled Lanes (pcuHr):	29.63	Cycle Time (s): 104
	PRC Over All Lanes (%):	3.8	Total Delay Over All Lanes(pcuHr):	29.63	

Full Input Data And Results
Scenario 4: '2028 Base PM' (FG5: '2028 Base PM', Plan 5: 'Existing')


Stage Sequence Diagram



Stage Timings


Stage	7	8	9	10
Duration	4	51	0	17
Change Point	0	13	71	78

Signal Timings Diagram



Full Input Data And Results

Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network	-	-	N/A	-	-		-	-	-	-	-	-	76.3%
Kingsway x Talbot Road	-	-	N/A	-	-		-	-	-	-	-	-	76.3%
1/1	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	509	Inf	Inf	0.0%
1/2	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	521	Inf	Inf	0.0%
2/1	A34 (Kingsway, N) Left Ahead	U	N/A	N/A	A		1	58	-	808	1945	1103	73.2%
2/2+2/3	A34 (Kingsway, N) Ahead Right	U+O	N/A	N/A	A		1	58	-	875	1945:1935	902+245	76.3 : 76.3%
3/1	Grangethorpe Drive	U	N/A	N/A	-		-	-	-	367	Inf	Inf	0.0%
4/2+4/1	Grangethorpe Drive Right Left Ahead	U	N/A	N/A	B		1	17	-	273	1945:2015	316+59	72.9 : 72.9%
5/1	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	745	Inf	Inf	0.0%
5/2	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	723	Inf	Inf	0.0%
6/2+6/1	A34 (Kingsway, S) Ahead Left	U	N/A	N/A	C		1	62	-	453	1940:2115	1094+89	38.3 : 38.3%
6/3+6/4	A34 (Kingsway, S) Ahead Right	U+O	N/A	N/A	C		1	62	-	527	1940:1935	997+222	43.3 : 43.3%
7/1	Talbot Road	U	N/A	N/A	-		-	-	-	355	Inf	Inf	0.0%
8/1	Talbot Road Left Ahead Right	U	N/A	N/A	D		1	19	-	284	1975	380	74.8%
Ped Link: P1	Unnamed Ped Link	-	N/A	-	E		0	0	-	0	-	0	0.0%
Ped Link: P2	Unnamed Ped Link	-	N/A	-	F		1	26	-	0	-	0	0.0%
Ped Link: P3	Unnamed Ped Link	-	N/A	-	G		1	26	-	0	-	0	0.0%


Full Input Data And Results

Ped Link: P4	Unnamed Ped Link	-	N/A	-	H		1	7	-	0	-	0	0.0%
Ped Link: P5	Unnamed Ped Link	-	N/A	-	J		1	32	-	0	-	0	0.0%
Ped Link: P6	Unnamed Ped Link	-	N/A	-	I		1	7	-	0	-	0	0.0%
Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network	-	-	173	48	63	16.6	6.4	0.7	23.6	-	-	-	-
Kingsway x Talbot Road	-	-	173	48	63	16.6	6.4	0.7	23.6	-	-	-	-
1/1	509	509	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
1/2	521	521	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
2/1	808	808	-	-	-	3.7	1.4	-	5.1	22.7	17.1	1.4	18.4
2/2+2/3	875	875	173	9	5	3.9	1.6	0.0	5.5	22.8	17.6	1.6	19.2
3/1	367	367	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
4/2+4/1	273	273	-	-	-	3.0	1.3	-	4.3	57.2	6.4	1.3	7.7
5/1	745	745	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
5/2	723	723	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2+6/1	453	453	-	-	-	1.3	0.3	-	1.6	13.0	6.6	0.3	6.9
6/3+6/4	527	527	0	39	57	1.5	0.4	0.6	2.5	17.0	6.6	0.4	7.0
7/1	355	355	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	284	284	-	-	-	3.1	1.4	-	4.6	57.9	7.7	1.4	9.2
Ped Link: P1	0	0	-	-	-	-	-	-	Inf	Inf	-	-	Inf
Ped Link: P2	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P3	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P4	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P5	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P6	0	0	-	-	-	-	-	-	-	-	-	-	-
C1 PRC for Signalled Lanes (%): 18.0 Total Delay for Signalled Lanes (pcuHr): 23.64 Cycle Time (s): 104 PRC Over All Lanes (%): 18.0 Total Delay Over All Lanes(pcuHr): 23.64													

Full Input Data And Results

Scenario 5: '2028 Base + AM' (FG6: '2028 Base + Dev AM', Plan 6: 'Existing+')


Stage Sequence Diagram



Stage Timings


Stage	11	12	13	14
Duration	5	44	2	21
Change Point	0	14	65	74

Signal Timings Diagram



Full Input Data And Results

Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network	-	-	N/A	-	-		-	-	-	-	-	-	67.9%
Kingsway x Talbot Road	-	-	N/A	-	-		-	-	-	-	-	-	67.9%
1/1	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	771	Inf	Inf	0.0%
1/2	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	755	Inf	Inf	0.0%
2/1	A34 (Kingsway, N) Left Ahead	U	N/A	N/A	A		1	53	-	644	1945	1010	63.8%
2/2+2/3	A34 (Kingsway, N) Ahead Right	U+O	N/A	N/A	A		1	53	-	450	1945:1935	485+178	67.9 : 67.9%
3/1	Grangethorpe Drive	U	N/A	N/A	-		-	-	-	304	Inf	Inf	0.0%
4/2+4/1	Grangethorpe Drive Right Left Ahead	U	N/A	N/A	B		1	21	-	297	1945:2015	377+75	65.7 : 65.7%
5/1	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	626	Inf	Inf	0.0%
5/2	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	373	Inf	Inf	0.0%
6/2+6/1	A34 (Kingsway, S) Ahead Left	U	N/A	N/A	C		1	56	-	693	1940:2115	1031+34	65.1 : 65.1%
6/3+6/4	A34 (Kingsway, S) Ahead Right	U+O	N/A	N/A	C		1	56	-	735	1940:1935	971+119	67.5 : 67.5%
7/1	Talbot Road	U	N/A	N/A	-		-	-	-	295	Inf	Inf	0.0%
8/1	Talbot Road Left Ahead Right	U	N/A	N/A	D		1	23	-	305	1975	456	66.9%
Ped Link: P1	Unnamed Ped Link	-	N/A	-	E		1	7	-	0	-	0	0.0%
Ped Link: P2	Unnamed Ped Link	-	N/A	-	F		1	32	-	0	-	0	0.0%
Ped Link: P3	Unnamed Ped Link	-	N/A	-	G		1	32	-	0	-	0	0.0%
Ped Link: P4	Unnamed Ped Link	-	N/A	-	H		1	8	-	0	-	0	0.0%


Full Input Data And Results

Ped Link: P5	Unnamed Ped Link	-	N/A	-	J		1	37	-	0	-	0	0.0%
Ped Link: P6	Unnamed Ped Link	-	N/A	-	I		1	9	-	0	-	0	0.0%
Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network	-	-	57	141	3	17.6	5.8	1.3	24.8	-	-	-	-
Kingsway x Talbot Road	-	-	57	141	3	17.6	5.8	1.3	24.8	-	-	-	-
1/1	771	771	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
1/2	755	755	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
2/1	644	644	-	-	-	3.2	0.9	-	4.1	22.9	13.2	0.9	14.1
2/2+2/3	450	450	0	118	3	1.8	1.0	1.1	3.9	31.2	6.0	1.0	7.1
3/1	304	304	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
4/2+4/1	297	297	-	-	-	3.0	0.9	-	4.0	48.1	6.8	0.9	7.7
5/1	626	626	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
5/2	373	373	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2+6/1	693	693	-	-	-	3.2	0.9	-	4.1	21.4	14.0	0.9	14.9
6/3+6/4	735	735	57	23	0	3.3	1.0	0.3	4.6	22.6	14.3	1.0	15.3
7/1	295	295	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	305	305	-	-	-	3.1	1.0	-	4.1	48.2	8.0	1.0	9.0
Ped Link: P1	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P2	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P3	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P4	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P5	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P6	0	0	-	-	-	-	-	-	-	-	-	-	-
C1			PRC for Signalled Lanes (%):		32.6	Total Delay for Signalled Lanes (pcuHr):		24.76	Cycle Time (s): 104				
			PRC Over All Lanes (%):		32.6	Total Delay Over All Lanes(pcuHr):		24.76					

Full Input Data And Results

Scenario 6: '2028 Base+ PM' (FG7: '2028 Base + Dev PM', Plan 6: 'Existing+')


Stage Sequence Diagram



Stage Timings


Stage	11	12	13	14
Duration	5	50	0	17
Change Point	0	14	71	78

Signal Timings Diagram



Full Input Data And Results

Network Layout Diagram



Full Input Data And Results

Network Results

Item	Lane Description	Lane Type	Controller Stream	Position In Filtered Route	Full Phase	Arrow Phase	Num Greens	Total Green (s)	Arrow Green (s)	Demand Flow (pcu)	Sat Flow (pcu/Hr)	Capacity (pcu)	Deg Sat (%)
Network	-	-	N/A	-	-		-	-	-	-	-	-	76.9%
Kingsway x Talbot Road	-	-	N/A	-	-		-	-	-	-	-	-	76.9%
1/1	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	477	Inf	Inf	0.0%
1/2	A34 (Kingsway, N)	U	N/A	N/A	-		-	-	-	488	Inf	Inf	0.0%
2/1	A34 (Kingsway, N) Left Ahead	U	N/A	N/A	A		1	57	-	797	1945	1085	73.5%
2/2+2/3	A34 (Kingsway, N) Ahead Right	U+O	N/A	N/A	A		1	57	-	854	1945:1935	918+204	76.1 : 76.1%
3/1	Grangethorpe Drive	U	N/A	N/A	-		-	-	-	363	Inf	Inf	0.0%
4/2+4/1	Grangethorpe Drive Right Left Ahead	U	N/A	N/A	B		1	17	-	236	1945:2015	312+69	61.9 : 61.9%
5/1	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	734	Inf	Inf	0.0%
5/2	A34 (Kingsway, S)	U	N/A	N/A	-		-	-	-	734	Inf	Inf	0.0%
6/2+6/1	A34 (Kingsway, S) Ahead Left	U	N/A	N/A	C		1	62	-	433	1940:2115	1090+93	36.6 : 36.6%
6/3+6/4	A34 (Kingsway, S) Ahead Right	U+O	N/A	N/A	C		1	62	-	503	1940:1935	998+220	41.3 : 41.3%
7/1	Talbot Road	U	N/A	N/A	-		-	-	-	319	Inf	Inf	0.0%
8/1	Talbot Road Left Ahead Right	U	N/A	N/A	D		1	19	-	292	1975	380	76.9%
Ped Link: P1	Unnamed Ped Link	-	N/A	-	E		1	7	-	0	-	0	0.0%
Ped Link: P2	Unnamed Ped Link	-	N/A	-	F		1	26	-	0	-	0	0.0%
Ped Link: P3	Unnamed Ped Link	-	N/A	-	G		1	26	-	0	-	0	0.0%
Ped Link: P4	Unnamed Ped Link	-	N/A	-	H		1	8	-	0	-	0	0.0%

Full Input Data And Results

Ped Link: P5	Unnamed Ped Link	-	N/A	-	J		1	33	-	0	-	0	0.0%
Ped Link: P6	Unnamed Ped Link	-	N/A	-	I		1	7	-	0	-	0	0.0%
Item	Arriving (pcu)	Leaving (pcu)	Turners In Gaps (pcu)	Turners When Unopposed (pcu)	Turners In Intergreen (pcu)	Uniform Delay (pcuHr)	Rand + Oversat Delay (pcuHr)	Storage Area Uniform Delay (pcuHr)	Total Delay (pcuHr)	Av. Delay Per PCU (s/pcu)	Max. Back of Uniform Queue (pcu)	Rand + Oversat Queue (pcu)	Mean Max Queue (pcu)
Network	-	-	143	49	54	16.2	6.0	0.5	22.7	-	-	-	-
Kingsway x Talbot Road	-	-	143	49	54	16.2	6.0	0.5	22.7	-	-	-	-
1/1	477	477	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
1/2	488	488	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
2/1	797	797	-	-	-	3.8	1.4	-	5.2	23.4	17.0	1.4	18.4
2/2+2/3	854	854	143	7	4	4.0	1.6	0.0	5.6	23.4	17.6	1.6	19.2
3/1	363	363	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
4/2+4/1	236	236	-	-	-	2.6	0.8	-	3.4	51.2	5.1	0.8	5.9
5/1	734	734	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
5/2	734	734	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
6/2+6/1	433	433	-	-	-	1.2	0.3	-	1.5	12.8	6.2	0.3	6.5
6/3+6/4	503	503	0	42	49	1.4	0.4	0.5	2.2	16.1	6.2	0.4	6.5
7/1	319	319	-	-	-	0.0	0.0	-	0.0	0.0	0.0	0.0	0.0
8/1	292	292	-	-	-	3.2	1.6	-	4.8	59.6	7.9	1.6	9.6
Ped Link: P1	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P2	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P3	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P4	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P5	0	0	-	-	-	-	-	-	-	-	-	-	-
Ped Link: P6	0	0	-	-	-	-	-	-	-	-	-	-	-
C1			PRC for Signalled Lanes (%):		17.1	Total Delay for Signalled Lanes (pcuHr):		22.72	Cycle Time (s): 104				
			PRC Over All Lanes (%):		17.1	Total Delay Over All Lanes(pcuHr):		22.72					



All rights are reserved. Copyright © 2022

Andrew Moseley Associates, 15 St Paul's Street, Leeds, LS1 2JG

www.amatp.co.uk

info@amatp.co.uk