

Our Ref: 4999/TW.23

**Elmwood Lodge,
Parkfield Road South,
Manchester M20 6DB**

Tree Ref No.	Species	Work
G1	Beech	Crown lift on the eastern canopy to give 3m clear canopy height removing minor lateral branches creating wounds of no more than 20mm Ø. Remove dead wood throughout the three trees.
1	Sycamore	Fell. Leave stump as close to ground level as possible. Replace.
G2	Sycamore	Cut ivy and allow to wither.
G3	Sycamore	Remove dead wood.
2	Sycamore	Crown clean. Cut ivy and allow to wither.
3	Beech	Fell. Stump management to be agreed.
4	Beech	Crown clean. Crown reduce the northern stem by up 2m throughout the whole northern stem profile to leave a canopy of approximately 8-10m in width, cutting back to suitable lateral branches creating wounds of no more than 50-60mm Ø. Crown reduce the southern and south western canopy by up to 1m cutting back to suitable lateral branches creating wounds of no more than 15mm Ø.
5	Prunus	Fell. Stump management to be agreed.
6	Prunus	Fell. Stump management to be agreed.
7	Willow	Fell. Stump management to be agreed.

Tree Ref No.	Species	Work
8	Sorbus	Fell. Stump management to be agreed.
9	Sorbus	Fell. Stump management to be agreed.
10	Maple	Fell. Stump and root management to be agreed.
11	Prunus	Fell. Stump management to be agreed. Replace.
12	Beech	Crown clean.
13	Birch	Cut ivy and allow to wither.
14	Beech	Crown clean.

Notes

Works in accordance with BS3998 – 2010

Not for planning control.

Any defects are to be reported to ACS Consulting – 01565 755422

No deviation from the specification without written consent.

General Risk Assessment and Method Statement to be supplied. Bat risk assessment to be supplied

Crown cleaning i.e. removal of any dead, diseased, broken or rubbing branches that were found.