



Key

- root penetration zone to trees to be removed
- root penetration zone to trees to be retained
- proposed trees
- trees to be retained
- trees to be removed
- SR Social Rent
- SO Shared Ownership
- Refuse bins
- Area overlapping root protection zone
- secure cycle storage
- low level semi-mature hedge planting
- 1.8m high timber fence
- 2.1m high timber fence with 300 mm trellis
- 2.4m / 3.0m high existing wire mesh fence
- 975 mm high Front and side boundary treatments where fronting roadways to be in brick dwarf wall construction with saddle back copings and pier capping's, including drip feature, that are to be secretly mechanically fixed into the brickwork.

House Type One
3b5p house @ 96m²
6No

House Type Two and Three
2b4p house @ 84m²
14No

C 01.11.23 Front boundary treatment amended
B 17.10.23 Front boundary treatment added
Rev. A 21.8.23 boundary treatment revised

Client			
WCHG			
Project			
Oakwood Lodge			
Title			
Proposed Site Plan			
Scale	Date	Stage	
1:500	27.07.23		
Job No	Drawing No	Rev.	Drawn
5415	C-09	C	AG



Arcus Consulting LLP
Manchester 0161 905 3222 Liverpool 0151 708 1080
Newcastle 0191 272 5781 London 020 8742 2512
Wakefield 0192 466 9000 www.arcus.uk.com

This document is copyright of Arcus Consulting LLP. Do not scale this drawing.
Only use figured dimensions. All dimensions to be checked on site prior to construction.

Proposed Site Plan

1:500