NOTES :

1. Drawing scaled & issued for planning purposes only.
2. All setting out, levels & dimensions to be checked on site by the Contractor (s) prior to the relevant orders being placed & installation of materials, any discrepancies are to be brought to the attention of the client & contract administrator.
3. This drawing is to be read in conjunction with all others relating to the project & all information derived accordingly, any anomolies to be reported to the client & contract administrator.
4. Work shown on this drawing to be carried out in accordance with current British Standards & Codes of Practice.
5. © This drawing is the Copyright of Saville Landscape Design Ltd & may not be reproduced in any form without prior written consent from Saville Landscape Design Ltd

KEY

- Existing tree or vegetation to be retained & protected in line with Arborculturalist proposals
- Existing tree or vegetation to be removed in line with Arborculturalist proposals
- Native Tree Species
- Fruit Tree
- Native hedge mix
- Amenity Turf
- Sports Turf
- Ornamental shrub planting
- Wildflower mix 1
- Wildflower mix 2
- Tarmac/ rubber crumb surfacing
- Bark mulch surfacing
- Hoggin/ sealed surface
- Block paving
- Non permeable Tarmac - Pedestrian
- Permable Tarmac - Pedestrian
- Non permeable Tarmac - Vehicular
- MUGA Permeable Sports pitch surfacing
- Permeable Sports pitch surfacing - Cricket
- Artificial grass surfacing
- 2400mm high welded mesh security fence
- 2100mm high welded mesh security fence
- Security fence 1800mm high welded mesh security fence
- Metal railings 1200mm high bow top railings
- Timber fence 1800mm high timber close boarded fence
- Sports perimeter fence 1500mm high welded mesh fence
- 4000mm high cricket netting & cage
- 1000-1300mm high pedestrian door barrier
- 1000-1200mm high pedestrian guard rail
- Hand rail
- FOE RTW — Flag on edge retaining wall

LANDSCAPE IMAGE EXAMPLES

Security & sports fencing

Bow top fencing

Block paving

Rubber crumb path

Outdoor teaching zone

Native tree planting

Native hedge mix

Low maintenance ornamental planting & wildflower meadow

Raised vegetable beds

Willow tunnel

Rev	Description	Initial	Date
E	Amended to latest arc site plan	KAS	May23
D	Parking updated, bins & benches added	KAS	Mar23
C	Amended to latest arc site plan	KAS	Mar23
B	Updated to arc site plan & detailed planting prps	KAS	Jan23
A	Amended to latest arc site plan	KAS	Nov22

saville LANDSCAPE DESIGN
Hatherlow House Romiley Stockport Cheshire SK6 3DY
T : 0161 406 7333
M : 07502 269193
E : info@savillelandscape.co.uk
W : www.savillelandscape.co.uk

CLIENT
Conlon Construction Ltd

PROJECT TITLE
Olive Primary School, Manchester

DRAWING TITLE
Landscape Masterplan

STATUS
PLANNING

SCALE	SHEET SIZE	DRAWN	CHECKED	DATE
1:250	A1	KAS	-	May23

PROJECT NO.	DRAWING NO.	REV.
406	01	E