



Blue Roof Calculation Summary

Project Name: Echo Street
Location: Manchester

Client:
Completed By: N.Todd

Reference: BR-5111-05
Date: 28/06/2023

Roof ID:	Catchment Area (m ²)	Area of Blue Roof Storage (m ²)	Area of other roofs draining onto Blue Roof (m ²)	Max allowable depth of water (mm)	Hmax (mm)	Allowable discharge (l/s)	Achievable discharge (l/s)	Minimum number of outlets
Block A	533	385	148	100	99		1.49	3
Link A-B (level 11)	67	60	7	100	96		0.10	1
Link A-B (level 12)	110	98	12	100	98		0.15	1
Block B	558	398	160	100	100		1.60	3
Link B-C (Level 15)	67	60	7	100	96		0.10	1
Link B-C (Level 16)	110	98	12	100	98		0.15	1
Block C	548	377	171	100	99		1.83	3
Over Level 0	90	84	6	100	96		0.10	1
Over Level -01	151	93	58		150		0.14	1
TOTAL discharge						0.00	5.66	

Notes:	<p>Areas of Blue Roof Storage taken from Data Capture Form completed by A.Rubinstein & D.Burrows.</p> <p>Blue Roof Calculations based on FEH data with a 45% percentage increase for Climate Change.</p> <p>Radmat Blue Roof outlet restrictors incorporate an integral overflow unless otherwise specified. Radmat recommend that at least one additional 'tell-tale' overflow is installed to alert building users of maintenance issues.</p>
--------	---

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Block A

Roof Details:

BlueRoof	385 m ²	x 100 %
Additional Area	148 m ²	x 100 %
Effective Area	533 m ²	

Storage Details:

Length	385 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	45 %

Summer Storm Profile

Duration	Intensity mm	Intensity mm/h	Required storage(m ³)
5 min	20.9	250.6	11.0
10 min	30.6	183.7	16.0
15 min	38.3	153.2	19.8
30 min	51.1	102.3	25.9
45 min	59.2	78.9	29.4
60 min	65.2	65.2	31.7
2 hours	78.2	39.1	35.2
6 hours	101.8	17.0	36.2
24 hours	134.9	5.6	27.7

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	27 mm
Sump Depth	None
Discharge rate	1.49 l/s
Outlet	3 No
Flow Per Outlet	0.5 l/s

Result:

Outcome	Pass
Critical Storm Duration	4.47 hrs
Hmax	99 mm
Required Volume	36.4 m ³
Time to half empty	3.4 hrs
Roof Loading	94.55 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Link A-B (Level 11)

Roof Details:

BlueRoof	60 m ²	x 100 %
Additional Area	7 m ²	x 100 %
Effective Area	67 m ²	

Storage Details:

Length	60 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	45 %

Summer Storm Profile

Duration	Intensity		Required storage(m ³)
	mm	mm/h	
5 min	20.9	250.6	1.4
10 min	30.6	183.7	2.0
15 min	38.3	153.2	2.5
30 min	51.1	102.3	3.3
45 min	59.2	78.9	3.8
60 min	65.2	65.2	4.2
2 hours	78.2	39.1	4.8
6 hours	101.8	17.0	5.5
24 hours	134.9	5.6	5.0

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	12 mm
Sump Depth	None
Discharge rate	0.1 l/s
Outlet	1 No

Result:

Outcome	Pass
Critical Storm Duration	6.22 hrs
Hmax	96 mm
Required Volume	5.5 m ³
Time to half empty	7.9 hrs
Roof Loading	91.67 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Link A-B (Level 12)

Roof Details:

BlueRoof	98 m ²	x 100 %
Additional Area	12 m ²	x 100 %
Effective Area	110 m ²	

Storage Details:

Length	98 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	45 %

Summer Storm Profile

Duration	Intensity		Required storage(m ³)
	mm	mm/h	
5 min	20.9	250.6	2.3
10 min	30.6	183.7	3.3
15 min	38.3	153.2	4.2
30 min	51.1	102.3	5.5
45 min	59.2	78.9	6.3
60 min	65.2	65.2	6.9
2 hours	78.2	39.1	8.0
6 hours	101.8	17.0	9.1
24 hours	134.9	5.6	8.5

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	15 mm
Sump Depth	None
Discharge rate	0.15 l/s
Outlet	1 No

Result:

Outcome	Pass
Critical Storm Duration	6.58 hrs
Hmax	98 mm
Required Volume	9.1 m ³
Time to half empty	8.3 hrs
Roof Loading	92.86 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Block B

Roof Details:

BlueRoof	398 m ²	x 100 %
Additional Area	160 m ²	x 100 %
Effective Area	558 m ²	

Storage Details:

Length	398 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	45 %

Summer Storm Profile

Duration	Intensity mm	Intensity mm/h	Required storage(m ³)
5 min	20.9	250.6	11.5
10 min	30.6	183.7	16.7
15 min	38.3	153.2	20.8
30 min	51.1	102.3	27.1
45 min	59.2	78.9	30.7
60 min	65.2	65.2	33.1
2 hours	78.2	39.1	36.6
6 hours	101.8	17.0	37.6
24 hours	134.9	5.6	28.5

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	28 mm
Sump Depth	None
Discharge rate	1.6 l/s
Outlet	3 No
Flow Per Outlet	0.53 l/s

Result:

Outcome	Pass
Critical Storm Duration	4.3 hrs
Hmax	100 mm
Required Volume	37.8 m ³
Time to half empty	3.3 hrs
Roof Loading	94.97 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Link B-C (Level 15)

Roof Details:

BlueRoof	60 m ²	x 100 %
Additional Area	7 m ²	x 100 %
Effective Area	67 m ²	

Storage Details:

Length	60 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	45 %

Summer Storm Profile

Duration	Intensity		Required storage(m ³)
	mm	mm/h	
5 min	20.9	250.6	1.4
10 min	30.6	183.7	2.0
15 min	38.3	153.2	2.5
30 min	51.1	102.3	3.3
45 min	59.2	78.9	3.8
60 min	65.2	65.2	4.2
2 hours	78.2	39.1	4.8
6 hours	101.8	17.0	5.5
24 hours	134.9	5.6	5.0

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	12 mm
Sump Depth	None
Discharge rate	0.1 l/s
Outlet	1 No

Result:

Outcome	Pass
Critical Storm Duration	6.22 hrs
Hmax	96 mm
Required Volume	5.5 m ³
Time to half empty	7.9 hrs
Roof Loading	91.67 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations.

References should be made to any relevant codes of practice.

Final determination of the suitability of any system is the sole responsibility of the user.

Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Link B-C (Level 16)

Roof Details:

BlueRoof	98 m ²	x 100 %
Additional Area	12 m ²	x 100 %
Effective Area	110 m ²	

Storage Details:

Length	98 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	45 %

Summer Storm Profile

Duration	Intensity		Required storage(m ³)
	mm	mm/h	
5 min	20.9	250.6	2.3
10 min	30.6	183.7	3.3
15 min	38.3	153.2	4.2
30 min	51.1	102.3	5.5
45 min	59.2	78.9	6.3
60 min	65.2	65.2	6.9
2 hours	78.2	39.1	8.0
6 hours	101.8	17.0	9.1
24 hours	134.9	5.6	8.5

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	15 mm
Sump Depth	None
Discharge rate	0.15 l/s
Outlet	1 No

Result:

Outcome	Pass
Critical Storm Duration	6.58 hrs
Hmax	98 mm
Required Volume	9.1 m ³
Time to half empty	8.3 hrs
Roof Loading	92.86 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Block C

Roof Details:

BlueRoof	377 m ²	x 100 %
Additional Area	171 m ²	x 100 %
Effective Area	548 m ²	

Storage Details:

Length	377 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	45 %

Summer Storm Profile

Duration	Intensity mm	Intensity mm/h	Required storage(m ³)
5 min	20.9	250.6	11.3
10 min	30.6	183.7	16.4
15 min	38.3	153.2	20.3
30 min	51.1	102.3	26.3
45 min	59.2	78.9	29.7
60 min	65.2	65.2	31.9
2 hours	78.2	39.1	34.7
6 hours	101.8	17.0	35.1
24 hours	134.9	5.6	24.9

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	30 mm
Sump Depth	None
Discharge rate	1.83 l/s
Outlet	3 No
Flow Per Outlet	0.61 l/s

Result:

Outcome	Pass
Critical Storm Duration	4 hrs
Hmax	99 mm
Required Volume	35.5 m ³
Time to half empty	2.7 hrs
Roof Loading	94.16 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Over Level 0

Roof Details:

BlueRoof	84 m ²	x 100 %
Additional Area	6 m ²	x 100 %
Effective Area	90 m ²	

Storage Details:

Length	84 m
Width	1 m
Depth	100 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	40 %

Summer Storm Profile

Duration	Intensity		Required storage(m ³)
	mm	mm/h	
5 min	20.2	241.9	1.8
10 min	29.6	177.4	2.6
15 min	37.0	147.9	3.3
30 min	49.4	98.7	4.4
45 min	57.1	76.2	5.0
60 min	62.9	62.9	5.5
2 hours	75.5	37.8	6.4
6 hours	98.3	16.4	7.5
24 hours	130.2	5.4	7.3

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	12 mm
Sump Depth	None
Discharge rate	0.1 l/s
Outlet	1 No

Result:

Outcome	Pass
Critical Storm Duration	8.68 hrs
Hmax	96 mm
Required Volume	7.6 m ³
Time to half empty	11 hrs
Roof Loading	90.48 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.

Client:

Project: Echo Street

Reference: BR-5111-05 Designer: N.Todd Date: 01/07/2023

Location: Manchester

Roof Location: Over Level -01

Roof Details:

BlueRoof	93 m ²	x 100 %
Additional Area	58 m ²	x 100 %
Effective Area	151 m ²	

Storage Details:

Length	93 m
Width	1 m
Depth	150 mm
Porosity	95 %
Slope	none

Rainfall Details - FEH Method:

Return Period	100 years
Climate Change Factor	40 %

Summer Storm Profile

Duration	Intensity		Required storage(m ³)
	mm	mm/h	
5 min	20.2	241.9	3.0
10 min	29.6	177.4	4.4
15 min	37.0	147.9	5.5
30 min	49.4	98.7	7.3
45 min	57.1	76.2	8.4
60 min	62.9	62.9	9.2
2 hours	75.5	37.8	10.8
6 hours	98.3	16.4	12.9
24 hours	130.2	5.4	12.8

Outflow Details:

Attenuation Control	Orifice Plate
Control Diameter	13 mm
Sump Depth	None
Discharge rate	0.14 l/s
Outlet	1 No

Result:

Outcome	Pass
Critical Storm Duration	10.22 hrs
Hmax	150 mm
Required Volume	13.2 m ³
Time to half empty	13 hrs
Roof Loading	141.94 Kg/m ²

Blue Roof calculation service is provided in good faith using the information supplied to us in the brief and the stated parameters in the calculation. If any of these parameters are incorrect or have been superseded, Radmat should be contacted to provide updated calculations. References should be made to any relevant codes of practice. Final determination of the suitability of any system is the sole responsibility of the user. Radmat obligations in respect of any sale of its products are governed by the respective sales contract.