Window Ref	Width (mm)	Height (mm)	Area of window (m2)	Room Name	Floor Area (m²)	O/P Area (m²) 5% of room area opening at 30°.	Required Opening Light Area (m²)	New Secondary Glazing, aluminium framed, double glazed	Privacy Glazing Required	Blinds	Finishes Required to Existing Window	Repairs Required	M&E Works	Photo	Photo	Photo	Photo	Photo
WG01	707	1261	0.9	Room 3	44.71	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-1				
WG02	707	1261	0.9	Room 3	44.71	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass	Replace 1 no. Critall casement stay		9760-1				
WG03	701	1251	0.9	Room 3	44.71	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-2				
WG04	701	1251	0.9	Room 3	44.71	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-2				
WG05	701	1251	0.9	Room 3	44.71	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-2				
WG06	701	1251	0.9	Room 2	34.69	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-3	9760-4			
WG07	701	1251	0.9	Room 2	34.69	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-3	9760-4			
WG08	701	1251	0.9	Room 2	34.69	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-3	9760-4			
WG09	701	1251	0.9	Room 2	34.69	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-5	9760-6			
WG10	701	1251	0.9	Room 2	34.69	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-5	9760-6			
WG11	701	1251	0.9	Room 2	34.69	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-5	9760-6			
WG12	701	1251	0.9	Room 8	5.1	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-7	9760-8			
WG13	701	1251	0.9	Room 8	5.1	N/A	N/A	Opening light needed		Remove and reinstate blinds	Rub down and redecorate, clean all glass			9760-7	9760-8			
WG14	701	1251	0.9	Corridor	136.9	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-9	9760-10			
WG15	694	1266	0.9	W.C 1	3.54	N/A	N/A	Fixed light	y		Rub down and redecorate, clean all glass	Replace 1 x broken pane	Remove window mounted fan. Install new through wall fan.	9760-11	9760-12	9760-13		
WG16	990	1267	1.3	W.C 2	7.83	N/A	N/A	Fixed light	y		Rub down and redecorate, clean all glass			9760-14	9760-15			
WG17	694	1266	0.9	W.C 2	7.83	N/A	N/A	Fixed light	y		Rub down and redecorate, clean all glass			9760-16	9760-17			
WG18	701	1252	0.9	W.C 2	7.83	N/A	N/A	Fixed light	y		Rub down and redecorate, clean all glass	Replace 1 x broken pane	Remove window mounted fan. Install new through wall fan.	9760-18	9760-19			
WG19	701	1252	0.9	W.C 3	7.73	N/A	N/A	Fixed light	y		Rub down and redecorate, clean all glass			9760-20	9760-21			
WG20	702	1262	0.9	W.C 3	7.73	N/A	N/A	Fixed light	y		Rub down and redecorate, clean all glass			9760-22	9760-23			
WG21	702	1262	0.9	W.C 3	7.73	N/A	N/A	Fixed light	y		Rub down and redecorate, clean all glass	Replace 1 x broken pane	Remove window mounted fan. Install new through wall fan.	9760-24	9760-25			
WG22	702	1262	0.9	Kitchen	5.08	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass	Replace 1 x broken pane	Remove window mounted fan. Install new through wall fan.	9760-26	9760-27	9760-28	9760-29	
WG23	702	1240	0.9	Room 4	57.32	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-30				
WG24	702	1240	0.9	Room 4	57.32	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass	Replace 1 no. Critall casement stay		9760-30				
WG25	702	1240	0.9	Room 4	57.32	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-30				
WG26	702	1240	0.9	Room 4	57.32	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-31				
WG27	702	1240	0.9	Room 4	57.32	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass	Replace 1 no. Critall casement stay		9760-31				
WG28	702	1240	0.9	Room 4	57.32	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-31				
WG29	702	1240	0.9	IT	35	N/A	N/A	Opening light needed		Remove and clear old blinds track	Rub down and redecorate, clean all glass			9760-32	9760-33			
WG30	702	1240	0.9	IT	35	N/A	N/A	Opening light needed		Remove and clear old blinds track	Rub down and redecorate, clean all glass			9760-32	9760-33			
WG31	702	1240	0.9	IT	35	N/A	N/A	Opening light needed		Remove and clear old blinds track	Rub down and redecorate, clean all glass			9760-32	9760-33			
WG32	702	1240	0.9	IT	35	N/A	N/A	Opening light needed		Remove and clear old blinds track	Rub down and redecorate, clean all glass			9760-34	9760-35	9760-36	9760-37	9760-38
WG33	702	1240	0.9	IT	35	N/A	N/A	Opening light needed		Remove and clear old blinds track	Rub down and redecorate, clean all glass			9760-34	9760-35	9760-36	9760-37	9760-38
WG34	702	1240	0.9	IT	35	N/A	N/A	Opening light needed		Remove and clear old blinds track	Rub down and redecorate, clean all glass	Replace 1 x broken pane	Remove window mounted fan. Install new through wall fan.	9760-34	9760-35	9760-36	9760-37	9760-38
WG35	702	1260	0.9	Plant	12.57	N/A	N/A	Opening light needed	Y		Rub down and redecorate, clean all glass		Would require removal of existing electrical distribution boards and busbars.	9760-39	9760-40	9760-41		
WG36	702	1260	0.9	Plant	12.57	N/A	N/A	Opening light needed	Y		Rub down and redecorate, clean all glass		Would require removal of existing electrical distribution boards and busbars.	9760-42	9760-43			
WG37	702	1260	0.9	Plant	12.57	N/A	N/A	Opening light needed	Y		Rub down and redecorate, clean all glass		Would require removal of existing electrical distribution boards and busbars.	9760-44	9760-45			
WG38	62	1340	0.1	Plant	12.57	N/A	N/A	Opening light needed	Y		Rub down and redecorate, clean all glass		Would require removal of existing electrical distribution boards and busbars.	9760-46				
WG39	62	1340	0.1	Store 1	12.57	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			No image				
WG40	708	1260	0.9	Corridor	5.1	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-47				
WG41	708	1260	0.9	Room 6	5.1	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-48				
WG42	708	1260	0.9	Room 6	5.1	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-48				
WG43	708	1260	0.9	Room 1	34.3	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-49	9760-50			
WG44	708	1260	0.9	Room 1	34.3	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-49	9760-50			
WG45	708	1260	0.9	Room 1	34.3	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-49	9760-50			
WG46	708	1260	0.9	Room 1	34.3	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-51	9760-52			
WG47	708	1260	0.9	Room 1	34.3	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-51	9760-52			
WG48	708	1260	0.9	Room 1	34.3	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass		Allow 50mm s.w. jamb packers to enable cable penetrations	9760-51	9760-52			
WG49	708	1260	0.9	Staff Room	19.05	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-53	9760-54	9760-55	9760-56	9760-57
WG50	708	1260	0.9	Staff Room	19.05	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass		Allow 50mm s.w. jamb packers to enable cable penetrations	9760-53	9760-54	9760-55	9760-56	9760-57
WG51	708	1260	0.9	Staff Room	19.05	N/A	N/A	Opening light needed			Rub down and redecorate, clean all glass			9760-53	9760-54	9760-55	9760-56	9760-57
WF01	1142	1798	2.1	Lift	7.28	0.4	0.2					Replace window complete with timber sliding sash, double glazed		9760-58	9760-59	9760-60	9760-61	
WF02	1163	2200	2.6	Lift	7.28	0.4	0.2					Replace window complete with timber sliding sash, double glazed		9760-62	9760-63			
WF03	1142	1798	2.1	Store 2	4.9	0.2	0.2					Replace window complete with timber sliding sash, double glazed		9760-64	9760-65	9760-66		
WF04	1163	2200	2.6	Office 1	10.42	0.5	0.5					Replace window complete with timber sliding sash, double glazed		9760-67	9760-68	9760-69	9760-70	9760-71
WF05	1163	2200	2.6	Main Office 1	10.7	0.5	0.2					Replace window complete with timber sliding sash, double glazed		9760-72	9760-73	9760-74	9760-75	9760-76
WF06	1163	2200	2.6	Main Office 1	12.23	0.6	0.2					Replace window complete with timber sliding sash, double glazed		9760-77	9760-78	9760-79		
WF07	1163	2200	2.6	Office 2	12.21	0.6	0.6					Replace window complete with timber sliding sash, double glazed		9760-83	9760-84	9760-85		
WF08	1142	1798	2.1	Office 3	12.21	0.6	0.6			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-80	9760-81	9760-82		
WF09	693	1839	1.3	Office 4	69.44	3.5	3.5			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-86				
WF10	693	1839	1.3	Office 5	69.44	3.5	3.5			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-87	9760-88			
WF11	1152	2172	2.5	Main Office 2	69.44	3.5	0.9			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-89	9760-90			
WF12	1152	2172	2.5	Main Office 2	10.42	0.5	0.1			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-91	9760-92	9760-93	9760-94	
WF13	1152	2172	2.5	Main Office 2	5.54	0.3	0.1					Replace window complete with timber sliding sash, double glazed		No image				
WF14	1152	2172	2.5	Kitchen 1	6.1	0.3	0.3			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed	Remove redundant window fan	9760-106				
WF15	1152	2172	2.5	Kitchen 2	6.1	0.3	0.3			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-95	9760-96	9760-97		
WF16	693	1789	1.2	W.C 4	4.62	0.2	0.1		Y			Replace window complete with timber sliding sash, double glazed		9760-98	9760-99			
WF17	693	1381	1.0	W.C 4	21.58	1.1	0.5		Y			Replace window complete with timber sliding sash, double glazed		9760-100	9760-101			
WF18	693	1789	1.2	W.C 5	21.58	1.1	1.1		Y			Replace window complete with timber sliding sash, double glazed	Remove window mounted fan. Install new through wall fan.	9760-102	9760-103			
WF19	693	1789	1.2	Stair 2	21.58	1.1	1.1					Replace window complete with timber sliding sash, double glazed		9760-104	9760-105			
WF20	1142	1798	2.1	Store 3	11.27	0.6	0.6					Replace window complete with timber sliding sash, double glazed		No image				
WF21	1128	2158	2.4	Office 6	10.9	0.5	0.5			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-107	9760-108			
WF22	1128	2158	2.4	Store 7	4.82	0.2	0.2			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-109				
WF23	1128	2158	2.4	Main Office 2	137.56	6.9	1.7			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-110				
WF24	1128	2158	2.4	Store 8	137.56	6.9	6.9					Replace window complete with timber sliding sash, double glazed		9760-111	9760-112			
WF25	1142	1798	2.1	Main Office 1	137.56	6.9	2.3			Remove and reinstate blinds		Replace window complete with timber sliding sash, double glazed		9760-113	9760-114			
WF26	1181	1775	2.1	Stair 1	138.56	6.9	2.3					Replace window complete with timber sliding sash, double glazed		9760-115				
WF27	1142	1798	2.1	Stair 1	22.36	1.1	0.4					Replace window complete with timber sliding sash, double glazed		9760-116				
WF28	1142	1798	2.1	Stair 1	22.36	1.1	0.4					Replace window complete with timber sliding sash, double glazed		9760-117				