



Arboricultural Implications Assessment



Newall Green
HS,
Greenbrow
Rd,
Manchester,
M23 2SX

April 2023

Ref 23-10490

Quality Standards Control

The signatories below verify that this document has been prepared in accordance with our quality control requirements. These procedures do not affect the content and views expressed by the originator.

This document must only be treated as a draft unless it has been signed by the originators and approved by a director.

Revision	-
Date	19/04/2023
Prepared by	C. Salisbury
Checked by	A. Gonzales
Authorised by	E. Snape

Limitations

Syntegra Consulting Ltd ("SC") has prepared this report for the sole use of the client in accordance with the agreement under which our services were performed. No other warranty, expressed or implied, is made as to the professional advice included in this report or any other services provided by SC.

The conclusions and recommendations contained in this report are based upon information provided by others and upon the assumption that all relevant information has been provided by those parties from whom it has been requested and that such information is accurate. Information obtained by SC has not been independently verified by SC, unless otherwise stated in the report.

The methodology adopted and the sources of information used by SC in providing its services are outlined in this report. The work described in this report was undertaken in **April 2023** and is based on the conditions encountered and the information available during the said period of time. The scope of this report and the services are accordingly factually limited by these circumstances.

Where assessments of works or costs identified in this report are made, such assessments are based upon the information available at the time and where appropriate are subject to further investigations or information which may become available.

SC disclaim any undertaking or obligation to advise any person of any change in any matter affecting the report, which may come or be brought to SC's attention after the date of the report.

Certain statements made in the report that are not historical facts may constitute estimates, projections or other forward-looking statements and even though they are based on reasonable assumptions as of the date of the report, such forward-looking statements by their nature involve risks and uncertainties that could cause actual results to differ materially from the results predicted. SC specifically does not guarantee or warrant any estimate or projections contained in this report.

Costs may vary outside the ranges quoted. Whilst cost estimates are provided for individual issues in this report these are based upon information at the time which can be incomplete. Cost estimates for such issues may therefore vary from those provided. Where costs are supplied, these estimates should be considered in aggregate only. No reliance should be made in relation to any division of aggregate costs, including in relation to any issue, site or other subdivision.

No allowance has been made for changes in prices or exchange rates or changes in any other conditions which may result in price fluctuations in the future. Where assessments of works or costs necessary to achieve compliance have been made, these are based upon measures which, in SC's experience, could normally be negotiated with the relevant authorities under present legislation and enforcement practice, assuming a pro-active and reasonable approach by site management.

Forecast cost estimates do not include such costs associated with any negotiations, appeals or other non-technical actions associated with the agreement on measures to meet the requirements of the authorities, nor are potential business loss and interruption costs considered that may be incurred as part of any technical measures.

Copyright

© This report is the copyright of SC. Any unauthorised reproduction or usage by any person other than the addressee is strictly prohibited.

Introduction.....	5
Survey Methodology	6
Development Proposals	6
Impact Assessment	7
Mitigation Proposals.....	7
Conclusions and Recommendations	8
Appendix One: Tree Survey Schedule	10
Appendix Two: Tree Survey Key	12
Appendix Three: Plans.....	14

1.0 Introduction

- 1.1 We were instructed to carry out an arboricultural survey of trees at Dixons Academy, Greenbrow Road, Manchester.
- 1.2 This report details the arboricultural implications of developing the site, including:
- a survey of the trees on and near the development which may impact the proposal from ground level, noting their location, species and all relevant parameters, i.e. stem diameter, height, crown spread, condition etc;
 - providing advice on the removal, retention and management of trees;
 - assessment of the potential effects of the proposal on retained trees and vice versa;
 - assessment of the requirement for tree protection for the duration of the works;
 - mitigation for any loss;
 - preparation of a tree schedule;
 - and report on the above matters.
- 1.3 The survey was carried out on 5 April 2023 by means of inspection from ground level by an experienced and qualified arboriculturalist. The inspection can be restricted in cases where trees were Ivy clad or surrounded by vegetation.
- 1.4 Under *BS5837: 2012 Trees in Relation to Construction - Recommendations*, the assessment of trees is made objectively. The tree categorisation method identifies the quality and value of the existing tree stock, allowing informed decisions to be made concerning development design layout.
- 1.5 The following documents have been made available by the client:
- Drawing- FS0998-IBI-TB-00-PL-L-700-001.dwg
 - Drawing- FS0998-IBI-TB-00-PL-L-700-002.dwg
- 1.6 The supplied drawing included some tree positions plotted. Any dimensions regarding tree positions and protective fencing must be checked on site.
- 1.7 Weather conditions during the survey were wet and windy.
- 1.8 The survey was carried out noting the conditions of the trees at the time of inspection. As trees are part of the natural environment, conditions can naturally change; therefore, the contents of this report are valid for one year only. After this period, re-inspection may be necessary.

2.0 Survey Methodology

- 2.1 The trees were surveyed (prefixed T, or G for group) and recorded in the tree schedule in appendix one. Where groups are recorded, average height and diameter at breast height (DBH) of the trees in the group are reported. Where access to the base of any trees was limited, stem size was estimated.
- 2.2 All the trees were assessed using: a grading A to C (retention) and U (removal); condition and age class as defined in appendix two.
- 2.3 Where appropriate, canopy spread for each tree was recorded at four cardinal points in order to reproduce an accurate representation of the crown shape of the tree on the tree plan in appendix three.
- 2.4 The survey included all trees within the proposal area and trees near to the proposal.

3.0 Development Proposals

- 3.1 Due to the proposed development and its associated infrastructure there are a number of locations where the proposals are in close proximity to the trees surveyed. The Site Layout Plan within appendix three identifies the trees in relation to the proposed development.
- 3.2 In order to fully assess the impact of the proposals an Impact Table has been created detailing each tree, which shows the proximity of the associated works to the tree.
- 3.3 This can then be assessed in accordance with BS 5837:2012 to determine whether the development will have a detrimental impact on the health of each tree. Once this has been determined remedial measures can be detailed to reduce the impact the proposals will have on the treescape.
- 3.4 Impact Table: -

Tree No.	Root Protection Area identified in Table 2 of BS 5837:2012	Distance to Proposed Hard Standing (m)	Distance to Proposed Development (m)	Can the Tree/s be Successfully Retained
T1	228m ²	N/A	38.00	Yes
T2	203m ²	N/A	30.00	Yes
T3	215m ²	N/A	22.00	Yes
T4	282m ²	N/A	19.00	Yes
T5	275m ²	N/A	25.00	Yes
T6	Not Assessed as the Tree Requires Removal Due to its Condition			
T7	235m ²	N/A	45.00	Yes

Tree No.	Root Protection Area identified in Table 2 of BS 5837:2012	Distance to Proposed Hard Standing (m)	Distance to Proposed Development (m)	Can the Tree/s be Successfully Retained
T8	118m ²	N/A	31.00	Yes
T9	180m ²	N/A	9.00	Yes
T10	137m ²	N/A	9.00	Yes
G1	65m ²	N/A	11.00	Yes
G2	Fell Due to Development			
G3	20m ²	N/A	34.00	Yes
G4	24m ²	N/A	55.00	Yes
G5	10m ²	N/A	19.00	Yes

4.0 Impact Assessment

4.1 To assess the implications of the Impact Table each tree can be categorised in the following way: -

	Trees to be retained		Trees to be removed	
	With No Impact	With detailed construction	Due to Condition	Due to Development
Tree No.	T1, T2, T3, T4, T5, T7, T8, T9, T10, G1, G2, G4 & G5	N/A	T6	G2

5.0 Mitigation Proposals

5.1 Compensatory Planting

5.1.1 Due to the loss of the trees identified in section 3.4 it is proposed that along with the general soft landscaping for the development, supplementary tree planting will support the application.

5.1.2 This will have a number of benefits for the development and the character of the area. These being: -

- Give a greater diversity of age class on the site, increasing sustainability.
- Give a greater diversity of species and therefore wildlife habitat.

6.0 Conclusions and Arboricultural Recommendations

- 6.1 The tree categorisation method identifies the quality and value of the existing tree stock, but it is not meant to be interpreted rigidly and is presented in order to form a balanced judgement on tree retention and removal.
- 6.2 A precautionary method of working near trees is detailed in the accompanying Arboricultural Method Statement.
- 6.3 Following site development, regular (annual or biannual) inspections of all retained trees should be undertaken by a qualified Arboricultural Consultant.
- 6.4 It is considered that in following the advice in this document, any negative factors affecting trees on the site will be minimised.

Appendix One

Tree Survey Schedule

TREE SURVEY SCHEDULE

Arboricultural Data Sheet: Date of Survey: 05/04/23 Surveyor: C. Salisbury													
Tree No.	Species	DBH (mm)	Height (m)	Age	Crown Spread (m)				Crown clearance	Condition rating	Comments and preliminary management recommendations	Estimated remaining contribution	Tree quality category rating
					N	E	S	W					
T1	Oak	710	18.60	M	6.5	5.0	5.0	6.5	3.00	B	A co-dominant specimen with reasonable form	80+	B2
T2	Oak	670	19.40	M	6.5	6.0	5.0	6.0	3.50	B	A co-dominant specimen with reasonable form.	80+	B2
T3	Beech	690	18.00	FM	5.5	4.0	6.0	4.0	3.00	B	A co-dominant specimen with reasonable form.	80+	B2
T4	Oak	790	18.00	M	9.0	8.5	9.0	8.5	2.50	B/C	A co-dominant specimen with reasonable form with early decline in canopy.	60-80	B2
T5	Oak	780	18.40	FM	6.5	6.0	6.5	6.5	3.00	B/C	A co-dominant specimen with reasonable form with early decline in canopy.	60-80	B2
T6	Maple	110	3.50	Y	0.5	0.5	0.5	0.5	2.50	C/D	An individual specimen in extensive decline – Fell	0-10	U
T7	Horse Chestnut	720	15.20	M	7.0	7.0	7.0	5.5	2.00	C	A co-dominant specimen situated adjacent to a highway in decline due to Bleeding Canker.	10-20	C2
T8	Ash	510	15.80	EM	6.0	5.0	5.0	5.0	1.50	C	A co-dominant specimen situated adjacent to a highway in decline due to Ash Dieback.	10-20	C2
T9	Lime	630	18.60	EM	7.0	7.0	7.0	6.0	3.50	B	An individual specimen with reasonable form situated adjacent to a highway.	40-60	B2

Arboricultural Data Sheet: Date of Survey: 05/04/23 Surveyor: C. Salisbury													
Tree No.	Species	DBH (mm)	Height (m)	Age	Crown Spread (m)				Crown clearance	Condition rating	Comments and preliminary management recommendations	Estimated remaining contribution	Tree quality category rating
					N	E	S	W					
T10	Lime	550	18.60	EM	6.0	5.0	6.5	6.0	2.00	B/C	An individual specimen with reasonable form but minor deadwood situated adjacent to a highway.	40-60	B2
G1	Ash, Alder & Willow	380<	14.20	Y/SM	-	-	-	-	1.50	B/C	A poor-quality mixed species group.	20-40	C2
G2	Birch & Beech	130 avg.	6.80	Y	-	-	-	-	0.00	B/C	A poor-quality linear internal belt.	20-40	C2
G3	Alder & Cherry	210 avg.	7.20	SM	-	-	-	-	1.00	B/C	An internal ornamental group.	40-60	C2
G4	Sycamore & Elm	230 avg.	8.20	SM	-	-	-	-	1.50	B/C	A poor-quality self-seeded linear belt.	40-60	C2
G5	Beech & Sycamore	150 avg.	5.80	SM	-	-	-	-	0.00	B/C	A poor-quality group which will outgrow its location	10-20	C2

Appendix Two

Tree Survey Key

Trees for removal				
Category and definition		Criteria		
Category U Those in such a condition that any existing value would be lost within 10 years, and which should, in the current context, be removed for reasons of sound arboricultural management		Trees that have a serious, irremediable, structural defect, such that their early loss is expected due to collapse, including those that will become unviable after removal of other R category trees (i.e., where, for whatever reason, the loss of companion shelter cannot be mitigated by pruning) Trees that are dead or are showing signs of significant, immediate, and irreversible overall decline Trees infected with pathogens of significance to the health and/or safety of other trees nearby (e.g. Dutch elm disease), or very low quality trees suppressing adjacent trees of better quality Note – Habitat reinstatement may be appropriate (e.g. R category tree used as a bat roost: installation of bat box in nearby tree).		
Trees to be considered for retention				
Category and definition		Criteria - Subcategories		
		1 Arboriculture values	2 Landscape values	3 Conservation values
Category A Those of high quality and value: in such a condition as to be able to make a substantial contribution (a minimum 40 years is suggested)		Trees that are particularly good examples of their species, especially if rare or unusual, or essential components of groups, or of formal or semi-formal arboriculture features (e.g. the dominant and/or principal trees within an avenue)	Trees, groups or woodlands which provide a definite screening or softening effect to the locality in relation to views into or out of the site, or those of particular visual importance (e.g. avenues or other arboricultural features assessed as groups)	Trees, groups or woodlands of significant conservation, historical, commemorative or other value (e.g. veteran trees or wood pasture)
Category B Those of moderate quality and value: those in such a condition as to make a significant contribution (a minimum of 20 years is suggested)		Trees that might be included in the high category, but are downgraded because of impaired condition (e.g. presence of remediable defects including unsympathetic past management and minor storm damage)	Trees present in numbers, usually as groups or woodlands, such that they form distinct landscape features, thereby attracting a higher collective rating than they might as individuals but which are not, individually, essential components of formal or semi-formal arboriculture features (e.g. trees of moderate quality within avenue that includes better, A category specimens), or trees situated mainly internally to the site, therefore individually having little impact on the wider locality	Trees with clearly identifiable conservation or other cultural benefits
Category C Those of low quality and value: currently in adequate condition to remain until new planting could be established (a minimum of 10 years is suggested), or young trees with a stem diameter below 150 mm		Trees not qualifying in higher categories	Trees present in groups or woodlands, but without this conferring on them significantly greater landscape value, and/or trees offering low or only temporary screening benefit	Trees with very limited conservation or other cultural benefits
		Note - Whilst C category trees will usually not be retained where they would impose a significant constraint on development, young trees with a stem diameter of less than 150 mm should be considered for relocation		

Age Class

Y	Young	Trees that have not yet established
SM	Semi-Mature	Established trees up to 1/3 of expected height and crown
EM	Early mature	Between 1/3 and 2/3 expected height and crown
M	Mature	Between 2/3 and full expected height and crown
FM	Fully Mature	Full expected height and crown
OM	Over-Mature	Crown beginning to break up and decrease in size
S	Senescent	Crown in advanced stage of break-up

Condition

A	Good
B	Fair
C	Poor
D	Dead

Appendix Three

Plans



- Category A Trees
- Category B Trees
- Category C Trees
- Category U Trees
- Root protection area

Site Address:
Dixons Academy
Greenbrow Road
Manchester

Drawing Title:
AIS Plan

Drawing No:
DAGRM/AIS/01

Date:
12/04/2023

Scale:
1:400@A1

Drawn by:
CS

Note: Dimensions are not to be scaled from this drawing.
All written measurements are to be checked on site by the contractor. Copyright Mulberry TMC.

Note: All rights described in Chapter IV of the Copyright Design & Patents Act 1988 have generally been asserted.



- Category A Trees
- Category B Trees
- Category C Trees
- Category U Trees
- Root protection area



- Existing Trees Retained
- Existing Trees Removed
- Root Protection Area
- Tree protection fencing

Site Address:
Dixon's Academy
Greenbrow Road
Manchester

Drawing Title:
Method Statement Plan

Drawing No:
DAGRM/MS/01

Date:
12/04/2023

Scale:
1:400@A1

Drawn by:
CS

Note: Dimensions are not to be scaled from this drawing.
All written measurements are to be checked on site by
the contractor. Copyright Mulberry TMC.
Note: All rights described in Chapter IV of the Copyright
Design & Patents Act 1988 have generally been asserted.