

S106 Part 2 'Request for permission to work on a public sewer (MEDIUM / HIGH RISK)' Approval Notice



United Utilities Reference Number:		EC5429	
Contractor details			
Contractor/company name	Sub-Tech Contracts Ltd		
Contractor email address	info@sub-tech.co.uk		
Works Supervisor	Jon Cannon		
Principal Contractor details (if applicable):			
Company name	Dex Construction Group Limited		
Name of contact for project	Darren Hynes on behalf of Dex Construction		
Email address	darren.hynes@jreddington.co.uk		
Date of proposed works	20/09/2021	Type of connection approved	Saddle
Site details: The site / property which is proposed for connection to the public sewer			
- Addington Street Manchester M4 5FH			
APPROVED Your application for permission to work on the public sewer has been approved. THIS PERMIT SHOULD BE AVAILABLE ON SITE FOR INSPECTION			
This notice constitutes your permit make a connection to the public sewer network as detailed on your application, 'Request for permission to work on a public sewer'. You are now authorised to make the connection to the public sewer based on the agreed method and on the date given. Please provide 5 days' notice to the Development Support Technician named below to arrange an inspection of the works. The excavation should not be backfilled until the United Utilities appointed person has inspected the works. United Utilities reserve the right to request a connection to the public sewer be laid open for inspection. United Utilities will also be entitled to recover all costs associated for any excavation, remedial works and repeat visits if these requirements are not met. You must log on and off the sewer network at the beginning and end of each shift when working on the public sewer by calling 07826 539459 and quoting the United Utilities reference number at the top of this decision notice. Any gas alarms, residual risks or sewer incidents should also be reported on this number.			
Comments			
Approval granted for a 225mm <i>combined</i> connection via a <i>saddle connection</i> on the <i>combined</i> sewer located within Addington Street.			
*Saddle connection should be core drilled with care taken to ensure the core does not fall into the public sewer. United Utilities request that the core piece is to be retained for the scheduled inspection.			
Developer Services Inspector	Marcus Jones		
Contact number	07823553970		
Date	20/09/2021		